

Chapter 1 **General Information**

1.1	Manual Description	1-1
1.1.1	Purpose.....	1-1
1.1.1.A	Use of <i>Bridge Design Manual</i> on Design-Build and Progressive Design-Build Projects.....	1-1
1.1.2	Specifications.....	1-1
1.1.3	Format.....	1-2
1.1.3.A	General.....	1-2
1.1.3.B	Chapters.....	1-2
1.1.3.C	Numbering System.....	1-3
1.1.3.C.1	Numbering of Sections.....	1-3
1.1.3.C.2	Numbering of Sheets.....	1-3
1.1.3.C.3	Appendices.....	1-3
1.1.3.C.4	Numbering of Tables and Figures.....	1-3
1.1.4	Revisions.....	1-4
1.1.5	Design Memorandums.....	1-4
1.2	Bridge and Structures Office Organization	1-5
1.2.1	General.....	1-5
1.2.2	Organizational Elements of the Bridge Office.....	1-5
1.2.2.A	State Bridge and Structures Engineer.....	1-5
1.2.2.B	State Bridge Design Engineer.....	1-5
1.2.2.B.1	Structural Design Units.....	1-5
1.2.2.B.2	Bridge Projects Unit.....	1-6
1.2.2.B.3	Mega Projects Bridge Unit Manager.....	1-7
1.2.2.B.4	Floating Bridge & Special Structures Design Unit Manager.....	1-7
1.2.2.B.5	Bridge Design Technology Unit Manager.....	1-8
1.2.2.C	State Bridge Preservation Engineer.....	1-8
1.2.2.C.1	Bridge Preservation Office (BPO).....	1-8
1.2.2.D	Bridge Asset Management Engineer.....	1-8
1.2.2.E	Staff Support.....	1-9
1.2.2.F	Office Administrator.....	1-9
1.2.3	Unit Responsibilities and Expertise.....	1-9
1.3	Roles, Responsibilities and Procedures	1-10
1.3.1	General.....	1-10
1.3.1.A	Requirements for Engineering.....	1-10

1.3.2	General Design Procedures	1-10
1.3.2.A	PS&E Prepared by WSDOT Bridge and Structures Office	1-10
1.3.2.A.1	Design Team	1-10
1.3.2.A.2	Designer Responsibility	1-10
1.3.2.A.3	Structural Detailer Responsibility	1-12
1.3.2.A.4	Specialist Responsibility	1-12
1.3.2.A.5	Specification and Estimating Engineer Responsibilities	1-13
1.3.2.A.6	Design Unit Manager Responsibility	1-13
1.3.2.A.7	State Bridge Design Engineer’s Responsibilities	1-15
1.3.2.A.8	Bridge Scheduling Engineer Responsibilities	1-15
1.3.2.A.9	WSDOT Design Reviewer’s or Coordinator’s Responsibilities	1-16
1.3.2.B	Consultant PS&E — Projects on WSDOT Right of Way	1-16
1.3.2.B.1	WSDOT Consultant Liaison Engineer Responsibility	1-16
1.3.2.B.2	WSDOT Project Manager Responsibility	1-16
1.3.2.C	Consultant PS&E — Projects on County and City Right of Way	1-16
1.3.2.D	Structural Engineering and Significant Structures	1-17
1.3.3	Design/Check Calculation File	1-17
1.3.3.A	File Format and Naming	1-17
1.3.3.B	File Inclusions	1-18
1.3.3.C	File Exclusions	1-19
1.3.4	PS&E Review Period	1-19
1.3.5	Addenda	1-19
1.3.6	Construction Support	1-20
1.3.6.A	Shop Plans and Permanent Structure Construction Procedures	1-20
1.3.6.A.1	Bridge Shop Plans and Procedures	1-20
1.3.6.A.2	Sign Structure, Signal, and Illumination Shop Plans	1-22
1.3.6.A.3	Geotechnical Submittals	1-22
1.3.6.B	Contract Changes (Change Orders and As-Builts)	1-23
1.3.6.B.1	Request for Changes	1-23
1.3.6.B.2	Processing Contract Revisions	1-23
1.3.6.B.3	As-Built Plan Process	1-24
1.3.7	Vacant	1-24
1.3.8	Archiving Design Calculations, Job Files, and S&E Files	1-24
1.3.8.A	Upon Award of the Project	1-24
1.3.8.B	Upon Physical Contract Completion	1-25
1.3.8.C	Consultant Designs	1-26
1.3.8.D	Design-Build and Progressive Design-Build Projects	1-27
1.3.9	Public Disclosure Policy Regarding Bridge Plans	1-27
1.3.10	Use of Computer Software	1-27
1.3.10.A	Policy on Open Source Software	1-27
1.3.10.B	Approved Software Tools	1-27

1.4	Quality Control/Quality Assurance/Quality Verification (QC/QA/QV) Procedures	1-28
1.4.1	General	1-28
1.4.2	WSDOT Prepared Bridge (or Structure) Preliminary Plans	1-29
1.4.2.A	Description of Terms	1-29
1.4.3	WSDOT Prepared PS&E	1-30
1.4.3.A	Plans, Calculations and Quantities Prepared by WSDOT Bridge and Structures Office	1-30
1.4.3.A.1	Description of Terms	1-30
1.4.3.A.2	Designer Responsibility	1-30
1.4.3.A.3	Checker Responsibility	1-31
1.4.3.A.4	Specialist/Bridge and Structures Architect Responsibility	1-32
1.4.3.A.5	Design Unit Manager Responsibility	1-32
1.4.3.A.6	State Bridge Design Engineer's Responsibilities	1-33
1.4.3.A.7	General Bridge Plan Stamping and Signature Policy	1-33
1.4.3.B	Specifications and Estimates (S&E) Prepared by WSDOT Bridge and Structures Office	1-34
1.4.3.B.1	Description of Terms	1-34
1.4.3.B.2	General Specification and Estimate Stamping and Signature Policy	1-35
1.4.4	Consultant Prepared PS&E/Preliminary Plans on WSDOT Right of Way	1-35
1.4.5	Structural Design Work Prepared Under Design-Build Method of Project Delivery	1-36
1.4.6	Structural Design Work Prepared Under Contractor Supplied Design Method of Project Delivery	1-36
1.5	Bridge Design Scheduling	1-37
1.5.1	General	1-37
1.5.2	Preliminary Design Schedule	1-37
1.5.3	Final Design Schedule	1-37
1.5.3.A	Breakdown of Project Staff-Hours Required	1-37
1.5.3.B	Estimate Design Time Required	1-38
1.5.3.C	Monthly Project Progress Report	1-39
1.6	Guidelines for Bridge Site Visits	1-40
1.6.1	Existing Structure Modifications	1-40
1.6.2	New Structures	1-41
1.6.3	Structure Demolition	1-41
1.7	Appendices	1-42
Appendix 1.1-A1	Bridge Design Manual Revision QC/QA Worksheet	1-43
Appendix 1.2-A1	Bridge & Structures Design Office Workflow	1-44
Appendix 1.3-A1	Bridge & Structures Design Calculations	1-45
Appendix 1.4-A1	QC/QA Signature Sheet	1-46
Appendix 1.4-A2	Min. Requirements for Check of Contractor-Design Buried Structure	1-47
1.99	References	1-48

Chapter 2 Preliminary Design

2.1 Preliminary Studies 2-1

 2.1.1 Interdisciplinary Design Studies 2-1

 2.1.2 Value Engineering Studies 2-1

 2.1.3 Preliminary Recommendations for Bridge Rehabilitation Projects 2-2

 2.1.4 Preliminary Recommendations for New Bridge Projects 2-2

 2.1.5 Type, Size, and Location (TS&L) Reports. 2-3

 2.1.5.A TS&L General 2-3

 2.1.5.B TS&L Outline. 2-4

 2.1.5.B.1 Cover, Title Sheet, and Index 2-4

 2.1.5.B.2 Photographs 2-4

 2.1.5.B.3 Introduction. 2-4

 2.1.5.B.4 Project Description 2-4

 2.1.5.B.5 Design Criteria 2-5

 2.1.5.B.6 Structural Studies 2-5

 2.1.5.B.7 Executive Summary 2-5

 2.1.5.B.8 Drawings. 2-5

 2.1.5.C Reviews and Submittals 2-5

 2.1.6 Alternate Bridge Designs 2-6

2.2 Preliminary Plan 2-7

 2.2.1 Development of the Preliminary Plan 2-7

 2.2.1.A Process and Sequence of Development. 2-7

 2.2.1.A.1 Schedule. 2-7

 2.2.1.A.2 Structure Site Data 2-7

 2.2.1.A.3 Preliminary Plan Design Assignment 2-7

 2.2.1.A.4 Preliminary Plan Development 2-8

 2.2.1.A.5 Initial Internal Review 2-8

 2.2.1.A.6 Request for Geotechnical and Hydraulics Information . . . 2-9

 2.2.1.A.7 Cost Estimate 2-9

 2.2.1.A.8 Distribution for Preliminary Plan Approval 2-9

 2.2.1.A.9 Distribution of Final Preliminary Plan 2-9

 2.2.1.B Responsibilities 2-9

 2.2.1.C Site Reconnaissance. 2-10

 2.2.1.D Coordination 2-10

 2.2.1.E Consideration of Alternatives. 2-10

 2.2.1.F Designer Recommendation. 2-11

 2.2.1.G Concept Approval 2-11

 2.2.1.H Consideration for Accelerated Bridge Construction. 2-11

2.2.2	Documentation	2-11
2.2.2.A	Job File	2-11
2.2.2.B	Structure Site Data	2-11
2.2.2.C	Design Report or Design Summary and Value Engineering Studies . . .	2-12
2.2.2.D	Other Resources	2-12
2.2.2.E	Notes	2-12
2.2.3	General Factors for Consideration	2-12
2.2.3.A	Site Requirements	2-12
2.2.3.B	Safety	2-12
2.2.3.C	Economic	2-12
2.2.3.D	Structural	2-13
2.2.3.E	Environmental	2-13
2.2.3.F	Aesthetic	2-13
2.2.3.G	Construction	2-13
2.2.3.H	Hydraulic	2-13
2.2.3.I	Maintenance	2-13
2.2.3.J	Bridge Security	2-13
2.2.3.K	Alternatives	2-14
2.2.3.L	Other	2-14
2.2.4	Permits	2-14
2.2.4.A	Coast Guard Waterway Jurisdiction and Navigation Permits for New Construction	2-14
2.2.4.B	Coast Guard Temporary Regulation Adjustments for Construction Operations at Existing Structures	2-15
2.2.4.C	Other	2-15
2.2.5	Preliminary Cost Estimate	2-15
2.2.6	Approvals	2-16
2.2.6.A	State Bridge and Structures Architect/Specialists	2-16
2.2.6.B	Bridge and Buried Structures Design	2-17
2.2.6.C	Region	2-17
2.2.6.D	Railroad	2-18
2.3	Preliminary Plan Criteria	2-19
2.3.1	Highway Crossings	2-19
2.3.1.A	General	2-19
2.3.1.A.1	Mainline Highway Crossings	2-19
2.3.1.A.2	Ramp Highway Crossings	2-19
2.3.1.B	Bridge Width	2-19
2.3.1.C	Horizontal Clearances	2-19
2.3.1.D	Vertical Clearances	2-21
2.3.1.E	End Slopes	2-21
2.3.1.F	Determination of Bridge Length	2-21
2.3.1.G	Pedestrian Crossings	2-22
2.3.1.H	Bridge Redundancy	2-22

2.3.2	Railroad Crossings	2-23
2.3.2.A	General	2-23
2.3.2.B	Criteria.	2-23
2.3.2.C	Bridge Width	2-23
2.3.2.D	Horizontal Clearances.	2-23
2.3.2.E	Crash Walls.	2-23
2.3.2.F	Vertical Clearances	2-24
2.3.2.G	Determination of Bridge Length.	2-24
2.3.2.H	Special Considerations	2-24
2.3.2.I	Construction Openings	2-24
2.3.3	Water Crossings	2-25
2.3.3.A	Bridge Width	2-25
2.3.3.B	Horizontal Clearances.	2-25
2.3.3.C	Vertical Clearances	2-25
2.3.3.D	End Slopes	2-25
2.3.3.E	Determination of Bridge Length.	2-26
2.3.3.F	Scour and Stream Migration	2-26
2.3.3.G	Pier Protection.	2-26
2.3.3.H	Construction Access and Time Restrictions	2-26
2.3.3.I	Buried structures that qualify as a bridge per National Bridge Inspection Standards (NBIS) shall be designed to meet above requirements for Water Crossings.	2-27
2.3.4	Bridge Widening	2-27
2.3.4.A	Bridge Width	2-27
2.3.4.B	Traffic Restrictions.	2-27
2.3.4.C	Construction Sequence.	2-27
2.3.5	Temporary Bridges	2-28
2.3.5.A	Bridge Width	2-28
2.3.5.B	Live Load.	2-28
2.3.5.C	Temporary Bridge Type	2-28
2.3.5.D	Temporary Bridge Traffic Barrier	2-28
2.3.6	Retaining Walls and Noise Walls	2-28
2.3.7	Bridge Deck Drainage.	2-28
2.3.8	Bridge Deck Protection Systems	2-29
2.3.9	Construction Clearances.	2-29
2.3.10	Design Guides for Falsework Depth Requirements	2-29
2.3.10.A	Falsework Spans < 36' and No Skews	2-30
2.3.10.B	Falsework Spans > 36' or Spans with Skews or Limited Falsework Depth.	2-30
2.3.10.C	Bridge Widening	2-30
2.3.10.D	Bridge with Skews.	2-30

2.3.11	Inspection and Maintenance Access	2-31
2.3.11.A	General	2-31
2.3.11.B	Safety Cables	2-32
2.3.11.C	Travelers	2-32
2.3.11.D	Abutment Slopes	2-32
2.3.11.E	Inspection Lighting and Access	2-32
2.3.11.E.1	Reinforced Concrete Box and Post-Tensioned Concrete Box Girders	2-32
2.3.11.E.2	Composite Steel Box Girders	2-32
2.4	Selection of Structure Type	2-33
2.4.1	Bridge Types	2-33
2.4.1.A	Reinforced Concrete Slab	2-33
2.4.1.A.1	Application	2-33
2.4.1.A.2	Characteristics	2-33
2.4.1.A.3	Depth/Span Ratios	2-33
2.4.1.B	Reinforced Concrete Tee-Beam	2-34
2.4.1.B.1	Application	2-34
2.4.1.B.2	Characteristics	2-34
2.4.1.B.3	Depth/Span Ratios	2-34
2.4.1.C	Reinforced Concrete Box Girder	2-34
2.4.1.C.1	Application	2-34
2.4.1.C.2	Characteristics	2-34
2.4.1.C.3	Depth/Span Ratios*	2-34
2.4.1.D	Post-tensioned Concrete Box Girder	2-35
2.4.1.D.1	Application	2-35
2.4.1.D.2	Characteristics	2-35
2.4.1.D.3	Depth/Span Ratios*	2-35
2.4.1.E	Prestressed Concrete Girder Sections	2-35
2.4.1.E.1	Application	2-35
2.4.1.E.2	Characteristics	2-36
2.4.1.F	Composite Steel Plate Girder	2-37
2.4.1.G	Composite Steel Box Girder	2-37
2.4.1.G.1	Use	2-37
2.4.1.G.2	Characteristics	2-37
2.4.1.G.3	Depth/Span Ratios	2-37
2.4.1.H	Steel Truss (Through or Deck)	2-38
2.4.1.H.1	Application	2-38
2.4.1.H.2	Characteristics	2-38
2.4.1.H.3	Depth/Span Ratios	2-38
2.4.1.I	Segmental Concrete Box Girder	2-38
2.4.1.I.1	Application	2-38
2.4.1.I.2	Characteristics	2-38
2.4.1.I.3	Depth/Span Ratios	2-38

2.4.1.J	Railroad Bridges	2-38
2.4.1.J.1	Use	2-38
2.4.1.J.2	Characteristics	2-38
2.4.1.J.3	Depth/Span Ratios	2-39
2.4.1.K	Timber	2-39
2.4.1.K.1	Use	2-39
2.4.1.K.2	Characteristics	2-39
2.4.1.K.3	Depth/Span Ratios	2-39
2.4.1.L	Other	2-39
2.4.2	Wall Types	2-39
2.4.3	Buried Structure Types	2-39
2.5	Aesthetic Considerations	2-40
2.5.1	General Visual Impact	2-40
2.5.2	End Piers	2-40
2.5.2.A	Wingwalls	2-40
2.5.2.B	Retaining Walls	2-40
2.5.2.C	Slope Protection	2-41
2.5.2.D	Noise Walls	2-41
2.5.3	Intermediate Piers	2-41
2.5.4	Barrier and Wall Surface Treatments	2-41
2.5.4.A	Plain Surface Finish	2-41
2.5.4.B	Formliner Finishes	2-41
2.5.4.C	Pigmented Sealer	2-41
2.5.4.D	Architectural Details	2-42
2.5.5	Superstructure	2-42
2.6	Miscellaneous	2-43
2.6.1	Structure Costs	2-43
2.6.2	Handling and Shipping Precast Members and Steel Beams	2-43
2.7	WSDOT Standards for Highway Bridges	2-45
2.7.1	Design Elements	2-45
2.7.1.A	General	2-45
2.7.1.B	Substructure	2-45
2.7.1.C	Superstructure	2-46
2.7.1.D	Examples	2-46
2.7.2	Detailing the Preliminary Plan	2-47
2.8	Bridge Security	2-48
2.8.1	General	2-48
2.8.2	Design	2-48
2.8.3	Design Criteria	2-49

2.9	Bridge Standard Drawings	2-51
2.10	Appendices	2-52
	Appendix 2.2-A1 Bridge Site Data General	2-53
	Appendix 2.2-A2 Structure Site Data Rehabilitation	2-54
	Appendix 2.2-A3 Structure Site Data Stream Crossings	2-55
	Appendix 2.2-A4 Preliminary Plan Checklist	2-56
	Appendix 2.2-A5 Request For Geotechnical & Hydraulic Information for Bridge Preliminary Plan	2-58
2.99	References	2-59

Chapter 3 Loads

3.1 Scope 3-1

3.2 Definitions 3-2

3.3 Load Designations 3-3

3.4 Limit States 3-4

3.5 Load Factors and Load Combinations 3-5

 3.5.1 Load Factors for Substructure 3-6

3.6 Loads and Load Factors for Construction 3-7

3.7 Load Factors for Post-tensioning 3-8

 3.7.1 Post-tensioning Effects from Superstructure 3-8

 3.7.2 Secondary Forces from Post-tensioning, PS 3-8

3.8 Permanent Loads 3-9

 3.8.1 Deck Overlay Requirement 3-9

 3.8.2 Distribution of Permanent Loads 3-9

3.9 Live Loads 3-10

 3.9.1 Design Live Load 3-10

 3.9.2 Loading for Live Load Deflection Evaluation 3-10

 3.9.3 Distribution to Superstructure 3-10

 3.9.3.A Multi Girder Superstructure 3-10

 3.9.3.B Concrete Box Girders 3-11

 3.9.3.C Multiple Presence Factors 3-11

 3.9.3.D Distribution to Substructure 3-11

 3.9.3.E Distribution to Crossbeam 3-11

 3.9.4 Bridge Load Rating 3-12

3.10 Pedestrian Loads 3-13

3.11 Wind Loads 3-14

 3.11.1 Wind Load to Superstructure 3-14

 3.11.2 Wind Load to Substructure 3-14

 3.11.3 Wind on Noise Walls 3-14

3.12 Loads on Buried Structures 3-15

3.13 Earthquake Effects 3-16

3.14 Substructure, Scour and Earth Pressure 3-17

3.15 Force Effects Due to Superimposed Deformations 3-18

3.16	Other Loads	3-19
3.16.1	Buoyancy	3-19
3.16.2	Collision Force on Bridge Substructure	3-19
3.16.3	Collision Force on Traffic Barrier	3-19
3.16.4	Force from Stream Current, Floating Ice, and Drift	3-19
3.16.5	Ice Load	3-19
3.16.6	Uniform Temperature Load	3-19
3.16.7	Vehicular Collision Force: CT	3-19
3.16.8	Bridges Subjected to Tsunami Effects	3-20
3.99	References	3-22

Chapter 4 Seismic Design and Retrofit

4.1	General	4-1
4.1.1	Expected Bridge Seismic Performance	4-2
4.1.2	Expected Post-earthquake Service Levels	4-2
4.1.3	Expected Post-earthquake Damage States	4-3
4.2	WSDOT Additions and Modifications to AASHTO <i>Guide Specifications for LRFD Seismic Bridge Design (SEISMIC)</i>	4-4
4.2.1	Definitions	4-4
4.2.2	Earthquake Resisting Systems (ERS) Requirements for Seismic Design Categories (SDCs) C and D	4-4
4.2.3	Seismic Ground Shaking Hazard	4-9
4.2.3.A	Site Coefficients	4-10
4.2.4	Selection of Seismic Design Category (SDC)	4-10
4.2.5	Temporary and Staged Construction	4-11
4.2.6	Load and Resistance Factors	4-11
4.2.7	Balanced Stiffness Requirements and Balanced Frame Geometry Recommendation	4-11
4.2.8	Selection of Analysis Procedure to Determine Seismic Demand	4-11
4.2.9	Member Ductility Requirement for SDCs C and D	4-11
4.2.10	Longitudinal Restrainers	4-11
4.2.11	Abutments	4-12
4.2.12	Foundation – General	4-16
4.2.13	Foundation – Spread Footing	4-16
4.2.14	Procedure 3: Nonlinear Time History Method	4-16
4.2.15	I_{eff} for Box Girder Superstructure	4-16
4.2.16	Foundation Rocking	4-16
4.2.17	Drilled Shafts	4-16
4.2.18	Longitudinal Direction Requirements	4-17
4.2.19	Liquefaction Design Requirements	4-17
4.2.20	Reinforcing Steel	4-17
4.2.21	Concrete Modeling	4-18
4.2.22	Expected Nominal Moment Capacity	4-18
4.2.23	Interlocking Bar Size	4-18
4.2.24	Splicing of Longitudinal Reinforcement in Columns Subject to Ductility Demands for SDCs C and D	4-18
4.2.25	Development Length for Column Bars Extended into Oversized Pile Shafts for SDCs C and D	4-18
4.2.26	Lateral Confinement for Oversized Pile Shaft for SDCs C and D	4-18
4.2.27	Lateral Confinement for Non-Oversized Strengthened Pile Shaft for SDCs C and D	4-18
4.2.28	Requirements for Capacity Protected Members	4-19

4.2.29	Superstructure Capacity Design for Transverse Direction (Integral Bent Cap) for SDCs C and D	4-19
4.2.30	Superstructure Design for Non Integral Bent Caps for SDCs B, C, and D	4-19
4.2.31	Joint Proportioning	4-19
4.2.32	Cast-in-Place and Precast Concrete Piles	4-20
4.2.33	Seismic Resiliency using Innovative Materials and Construction	4-20
4.3	Seismic Design Requirements for Bridge Modifications and Widening Projects	4-21
4.3.1	General	4-21
4.3.2	Bridge Widening Project Classification	4-21
4.3.2.A	Minor Modification and Widening Projects	4-21
4.3.2.B	Major Modifications and Widening Projects	4-21
4.3.3	Seismic Design Requirements Bridge Widening Projects	4-22
4.3.4	Scoping for Bridge Widening and Liquefaction Mitigation.	4-24
4.3.5	Design and Detailing Considerations	4-24
4.4	Seismic Retrofitting of Existing Ordinary Bridges	4-26
4.4.1	Seismic Analysis Requirements	4-26
4.4.2	Seismic Retrofit Design.	4-27
4.4.3	Computer Analysis Verification	4-27
4.4.4	Earthquake Restrainers	4-27
4.4.5	Isolation Bearings	4-27
4.5	Seismic Design Requirements for Retaining Walls and Buried Structure	4-28
4.5.1	Seismic Design of Retaining Walls	4-28
4.5.2	Seismic Design of Buried Structure	4-28
4.99	References	4-29

Chapter 5 Concrete Structures

5.1	Materials	5-2
5.1.1	Concrete	5-2
5.1.1.A	Strength of Concrete	5-2
5.1.1.A.1	CIP Concrete Bridges	5-2
5.1.1.A.2	Prestressed Concrete Girders	5-2
5.1.1.B	Classes of Concrete	5-2
5.1.1.B.1	Class 3000	5-2
5.1.1.B.2	Class 4000	5-2
5.1.1.B.3	Class 4000A	5-2
5.1.1.B.4	Class 4000D	5-2
5.1.1.B.5	Class 4000P and 5000P	5-2
5.1.1.B.6	Class 4000W	5-3
5.1.1.B.7	Class 5000 or Higher	5-3
5.1.1.C	Relative Compressive Concrete Strength	5-3
5.1.1.D	Modulus of Elasticity	5-4
5.1.1.E	Shrinkage and Creep	5-4
5.1.1.F	Shrinkage	5-5
5.1.1.G	Grout	5-5
5.1.1.H	Mass Concrete	5-5
5.1.1.I	Self-Consolidating Concrete (SCC)	5-6
5.1.1.J	Shotcrete	5-6
5.1.1.K	Lightweight Aggregate Concrete	5-7
5.1.1.L	Concrete Cover to Reinforcement	5-8
5.1.1.L.1	Precast Prestressed Concrete Girders	5-8
5.1.1.L.2	Concrete Exposed to Salt/Seawater	5-8
5.1.1.M	Ultra-High Performance Concrete (UHPC)	5-8
5.1.2	Reinforcing Steel	5-9
5.1.2.A	Types and Grades	5-9
5.1.2.A.1	Corrosion Resistant Reinforcement	5-9
5.1.2.B	Sizes	5-10
5.1.2.C	Development	5-10
5.1.2.C.1	Tension Development Length	5-10
5.1.2.C.2	Compression Development Length	5-10
5.1.2.C.3	Tension Development Length of Standard Hooks	5-10
5.1.2.D	Splices	5-11
5.1.2.D.1	Tension Lap Splices	5-11
5.1.2.D.2	Compression Lap Splices	5-11
5.1.2.D.3	Mechanical Splices	5-11
5.1.2.D.4	Welded Splices	5-11
5.1.2.E	Hooks and Bends	5-11

5.1.2.F	Fabrication Lengths	5-12
5.1.2.G	Placement	5-12
5.1.2.H	Joint and Corner Details	5-13
5.1.2.H.1	T-Joint	5-13
5.1.2.H.2	“Normal” Right Corners	5-13
5.1.2.H.3	Right or Obtuse Angle Corners	5-13
5.1.2.I	Welded Wire Reinforcement	5-14
5.1.2.J	Headed Steel Reinforcing Bars	5-14
5.1.3	Prestressing Steel	5-14
5.1.3.A	General	5-14
5.1.3.B	Stress Limits	5-15
5.1.3.C	Prestressing Strands	5-15
5.1.3.C.1	Straight Strands	5-15
5.1.3.C.2	Harped Strands	5-15
5.1.3.C.3	Temporary Strands	5-15
5.1.3.D	Development of Prestressing Strand	5-16
5.1.3.D.1	General	5-16
5.1.3.D.2	Partially Debonded Strands	5-16
5.1.3.D.3	Strand Development Outside of Prestressed Concrete Girders	5-16
5.1.4	Prestress Losses	5-22
5.1.4.A	Instantaneous Losses	5-22
5.1.4.A.1	Elastic Shortening of Concrete	5-22
5.1.4.A.2	Anchorage Set Loss	5-22
5.1.4.A.3	Friction Losses	5-23
5.1.4.B	Approximate Estimate of Time-Dependent Losses	5-23
5.1.4.C	Refined Estimates of Time-Dependent Losses	5-23
5.1.4.D	Total Effective Prestress	5-24
5.1.4.E	Temporary Losses	5-25
5.1.4.E.1	Lifting of Girders From Casting Beds	5-25
5.1.4.E.2	Transportation	5-25
5.1.4.E.3	Erection	5-25
5.1.4.E.4	Final Configuration	5-25
5.1.5	Post-tensioning Systems	5-26
5.2	Design Considerations	5-27
5.2.1	Service and Fatigue Limit States	5-27
5.2.1.A	General	5-27
5.2.1.B	Control of Cracking	5-27
5.2.1.C	Stress Limits in Prestressed Concrete Members	5-27
5.2.2	Strength-Limit State	5-29
5.2.2.A	Flexure	5-29
5.2.2.A.1	Flexural Design of Nonprestressed Singly-Reinforced Rectangular Beams	5-30

5.2.2.B	Shear	5-30
5.2.2.C	Interface Shear	5-31
5.2.2.C.1	Interface Shear Between Deck Slab and Girder	5-32
5.2.2.C.2	Interface Shear Friction at Girder End	5-32
5.2.2.D	Shear and Torsion	5-33
5.2.3	Strut-and-Tie Model	5-33
5.2.4	Deflection and Camber	5-34
5.2.4.A	General	5-34
5.2.4.B	Deflection Calculation for Prestressed Concrete Girders	5-34
5.2.4.B.1	Elastic Deflection Due to Release of Prestress	5-35
5.2.4.B.2	Creep Deflection Before Cutting Temporary Strands	5-35
5.2.4.B.3	Deflection Due to Cutting of Temporary Strands	5-35
5.2.4.B.4	Diaphragm Load Deflection	5-35
5.2.4.B.5	Creep Deflection After Casting Diaphragms	5-35
5.2.4.B.6	Deck Slab Load Deflection	5-35
5.2.4.B.7	Superimposed Dead Load Deflection	5-35
5.2.4.B.8	Final Camber	5-35
5.2.4.C	Pre-camber	5-36
5.2.5	Construction Joints	5-36
5.2.5.A	Types of Joints	5-36
5.2.5.B	Shear Keys	5-36
5.2.6	Inspection Access and Lighting	5-37
5.2.6.A	Inspection Access	5-37
5.2.6.B	Access Hatch, Air Vent Holes and Inspection Lighting	5-37
5.3	Reinforced Concrete Box Girder Bridges	5-40
5.3.1	Box Girder Basic Geometries	5-40
5.3.1.A	Web Spacing	5-40
5.3.1.B	Basic Dimensions	5-40
5.3.1.B.1	Top Slab Thickness, T1 (includes ½ wearing surface)	5-40
5.3.1.B.2	Bottom Slab Thickness, T2	5-41
5.3.1.B.3	Girder Stem (Web) Thickness, T3	5-41
5.3.1.B.4	Intermediate Diaphragm Thickness, T4 and Diaphragm Spacing	5-41
5.3.1.C	Construction Considerations	5-42
5.3.1.D	Load Distribution	5-42
5.3.1.D.1	Unit Design	5-42
5.3.1.D.2	Dead Loads	5-42
5.3.1.D.3	Live Load	5-42
5.3.2	Reinforcement	5-45
5.3.2.A	Top Slab Reinforcement	5-45
5.3.2.A.1	Near Center of Span	5-45
5.3.2.A.2	Near Intermediate Piers	5-45
5.3.2.A.3	Bar Patterns	5-45

5.3.2.B	Bottom Slab Reinforcement	5-46
5.3.2.B.1	Near Center of Span	5-46
5.3.2.B.2	Near Intermediate Piers	5-47
5.3.2.B.3	Bar Patterns	5-47
5.3.2.C	Web Reinforcement.	5-47
5.3.2.C.1	Vertical Stirrups.	5-47
5.3.2.C.2	Web Longitudinal Reinforcement	5-48
5.3.2.D	Intermediate Diaphragm	5-48
5.3.3	Crossbeam	5-52
5.3.3.A	General	5-52
5.3.3.B	Basic Geometry.	5-52
5.3.3.C	Loads.	5-52
5.3.3.D	Reinforcement Design and Details	5-52
5.3.3.D.1	Top Reinforcement	5-55
5.3.3.D.2	Skin Reinforcement	5-55
5.3.4	End Diaphragm.	5-55
5.3.4.A	Basic Geometry.	5-55
5.3.4.B	Reinforcing Steel Details.	5-57
5.3.5	Dead Load Deflection and Camber.	5-57
5.3.6	Thermal Effects.	5-58
5.3.6.A	Effective Bridge Temperature and Movement	5-58
5.3.6.B	Differential Temperature	5-58
5.3.7	Hinges.	5-58
5.3.8	Drain Holes	5-58
5.4	Hinges and Inverted T-Beam Pier Caps	5-60
5.5	Bridge Widening	5-62
5.5.1	Review of Existing Structures	5-62
5.5.1.A	General	5-62
5.5.1.B	Original Contract Plans and Special Provisions	5-62
5.5.1.C	Original Calculations	5-62
5.5.1.D	Final Records	5-62
5.5.2	Analysis and Design Criteria.	5-63
5.5.2.A	General	5-63
5.5.2.A.1	Appearance	5-63
5.5.2.A.2	Materials	5-63
5.5.2.A.3	Load Distribution and Construction Sequence	5-63
5.5.2.A.4	Specifications	5-63
5.5.2.A.5	Geometrical Constraints	5-63
5.5.2.A.6	Overlay	5-63
5.5.2.A.7	Strength of the Existing Structure	5-64
5.5.2.A.8	Special Considerations	5-64
5.5.2.B	Seismic Design Criteria for Bridge Widening	5-64

5.5.2.C	Substructure	5-65
5.5.2.C.1	Selection of Foundation	5-65
5.5.2.C.2	Scour and Drift	5-65
5.5.2.D	Superstructure.	5-65
5.5.2.D.1	Camber.	5-65
5.5.2.D.2	Closure Strip.	5-65
5.5.2.D.3	Stress Levels and Deflections in Existing Structures	5-66
5.5.2.E	Stability of Widening	5-66
5.5.3	Removing Portions of the Existing Structure	5-66
5.5.4	Attachment of Widening to Existing Structure.	5-67
5.5.4.A	General	5-67
5.5.4.A.1	Lap and Mechanical Splices	5-67
5.5.4.A.2	Welding Reinforcement	5-67
5.5.4.A.3	Drilling Into Existing Structure.	5-67
5.5.4.A.4	Dowelling Reinforcing Bars Into the Existing Structure . .	5-67
5.5.4.A.5	Shear Transfer Across a Dowelled Joint.	5-69
5.5.4.A.6	Preparation of Existing Surfaces for Concreting.	5-69
5.5.4.A.7	Control of Shrinkage and Deflection on Connecting Reinforcement	5-69
5.5.4.A.8	Post-tensioning.	5-69
5.5.4.B	Connection Details	5-70
5.5.4.B.1	Box Girder Bridges	5-70
5.5.4.B.2	Flat Slab Bridges	5-76
5.5.4.B.3	T-Beam Bridges	5-77
5.5.4.B.4	Prestressed Concrete Girder Bridges.	5-78
5.5.5	Expansion Joints.	5-79
5.5.6	Possible Future Widening for Current Designs.	5-80
5.5.7	Bridge Widening Falsework	5-80
5.6	Prestressed Concrete Girder Superstructures	5-81
5.6.1	WSDOT Standard Prestressed Concrete Girder Types	5-81
5.6.2	Design Criteria	5-84
5.6.2.A	Support Conditions	5-85
5.6.2.B	Composite Action	5-85
5.6.2.B.1	General.	5-85
5.6.2.B.2	Load Application	5-85
5.6.2.B.3	Composite Section Properties	5-85
5.6.2.B.4	Slenderness Ratio	5-85
5.6.2.C	Design Procedure	5-87
5.6.2.C.1	General.	5-87
5.6.2.C.2	Stress Conditions	5-87
5.6.2.D	Standard Strand Locations	5-87

5.6.2.E	Girder End Types	5-89
5.6.2.E.1	End Type A	5-89
5.6.2.E.2	End Type B	5-91
5.6.2.E.3	End Type C	5-92
5.6.2.E.4	End Type D	5-94
5.6.2.F	Splitting Resistance in End Regions of Prestressed Concrete Girders. .	5-95
5.6.2.G	Confinement Reinforcement in End Regions of Prestressed Concrete Girders.	5-95
5.6.2.H	Girder Stirrups.	5-95
5.6.2.I	Section Properties.	5-95
5.6.3	Fabrication and Handling	5-97
5.6.3.A	Shop Plans	5-97
5.6.3.B	Special Problems for Fabricators	5-97
5.6.3.B.1	Strand Tensioning.	5-97
5.6.3.B.2	Hold Down Forces	5-97
5.6.3.B.3	Numbers of Strands	5-97
5.6.3.C	Handling of Prestressed Concrete Girders	5-97
5.6.3.C.1	In-Plant Handling	5-97
5.6.3.C.2	Lateral Stability During Handling	5-97
5.6.3.D	Shipping Prestressed Concrete Girders	5-98
5.6.3.D.1	General.	5-98
5.6.3.D.2	Mode of Transportation.	5-98
5.6.3.D.3	Weight Limitations	5-99
5.6.3.D.4	Support Locations.	5-99
5.6.3.D.5	Height Limitations	5-99
5.6.3.D.6	Lateral Stability During Shipping.	5-99
5.6.3.E	Erection and Bridge Deck Construction	5-100
5.6.3.F	Construction Sequence for Multi-Span Prestressed Concrete Girder Bridges.	5-101
5.6.4	Superstructure Optimization	5-101
5.6.4.A	Girder Selection.	5-101
5.6.4.A.1	Girder Series Selection.	5-101
5.6.4.A.2	Girder Concrete Strength	5-101
5.6.4.A.3	Girder Spacing	5-101
5.6.4.B	Bridge Deck Cantilevers	5-102
5.6.4.B.1	Appearance	5-102
5.6.4.B.2	Economy.	5-102
5.6.4.B.3	Bridge Deck Strength	5-102
5.6.4.B.4	Drainage	5-102
5.6.4.B.5	Bridge Curvature.	5-103

5.6.4.C	Diaphragm Requirements	5-103
5.6.4.C.1	General	5-103
5.6.4.C.2	Design	5-103
5.6.4.C.3	Geometry	5-103
5.6.4.C.4	Full or Partial Depth Intermediate Diaphragms	5-104
5.6.4.C.5	Tub Girder Intermediate Diaphragms	5-104
5.6.4.D	Skew Effects	5-104
5.6.4.D.1	Analysis	5-104
5.6.4.D.2	Detailing	5-105
5.6.4.E	Grade and Cross Slope Effects	5-106
5.6.4.F	Curve Effect and Flare Effect	5-106
5.6.4.G	Girder Pad Reinforcement	5-106
5.6.5	Repair of Damaged Prestressed Concrete Girders at Fabrication	5-106
5.6.6	Repair of Damaged Prestressed Concrete Girders in Existing Bridges	5-107
5.6.6.A	General	5-107
5.6.6.B	Repair Procedure	5-107
5.6.6.B.1	Minor Damage	5-107
5.6.6.B.2	Moderate Damage	5-107
5.6.6.B.3	Severe Damage	5-108
5.6.6.B.4	Repair vs. Replacement of Damaged Girder	5-109
5.6.6.C	Miscellaneous References	5-111
5.6.7	Deck Girders	5-111
5.6.7.A	General	5-111
5.6.7.B	Slab Girders	5-112
5.6.7.C	Double-Tee and Ribbed Deck Girders	5-112
5.6.7.D	Deck Bulb-Tee Girders	5-112
5.6.7.E	Wide Flange Deck Girders	5-113
5.6.7.F	Wide Flange Thin Deck Girders	5-114
5.6.8	Prestressed Concrete Tub Girders	5-114
5.6.8.A	General	5-114
5.6.8.B	Curved Tub Girders	5-114
5.6.9	Prestressed Concrete Girder Checking Requirement	5-115
5.6.10	Review of Shop Plans for Pre-tensioned Girders	5-115
5.7	Bridge Decks	5-116
5.7.1	Bridge Deck Requirements	5-116
5.7.1.A	Minimum Bridge Deck Thickness	5-116
5.7.1.B	Computation of Bridge Deck Strength	5-116
5.7.1.C	Computation of "A" Dimension	5-117
5.7.1.D	Staged Construction	5-117

5.7.2	Bridge Deck Reinforcement	5-117
5.7.2.A	Transverse Reinforcement	5-117
5.7.2.B	Longitudinal Reinforcement.	5-118
5.7.2.B.1	Simple Spans	5-118
5.7.2.B.2	Continuous Spans	5-119
5.7.2.C	Distribution of Flexural Reinforcement	5-119
5.7.2.D	Bar Patterns	5-120
5.7.2.E	Concrete Bridge Deck Design and Detailing	5-121
5.7.3	Stay-In-Place Deck Panels	5-122
5.7.3.A	General	5-122
5.7.3.B	Design Criteria.	5-122
5.7.3.C	Limitations on SIP Deck Panels	5-122
5.7.4	Bridge Deck Protection	5-123
5.7.4.A	Deck Protection Systems	5-123
5.7.4.A.1	Type 1 Protection System.	5-123
5.7.4.A.2	Type 2 Protection System.	5-124
5.7.4.A.3	Type 3 Protection System.	5-126
5.7.4.A.4	Type 4 Protection System.	5-127
5.7.4.A.5	Type 5 Protection System.	5-127
5.7.4.B	Existing Bridge Deck Widening	5-128
5.7.4.B.1	Rebar	5-128
5.7.4.B.2	Concrete Decks	5-128
5.7.4.B.3	Concrete Overlays	5-128
5.7.4.B.4	HMA Overlays.	5-129
5.7.4.B.5	Small Width Widening.	5-129
5.7.4.B.6	Expansion Joints.	5-129
5.7.4.C	Bridge Deck Overlays	5-129
5.7.4.C.1	Surface Preparation	5-130
5.7.4.C.2	Existing Structure Evaluation	5-130
5.7.4.C.3	Deck Repair	5-131
5.7.5	HMA Paving on Bridge Decks.	5-131
5.7.5.A	Design Responsibilities	5-131
5.7.5.B	Design Considerations	5-132
5.7.5.B.1	HMA Depth	5-132
5.7.5.B.2	Grade Controlled Structures.	5-132
5.7.5.B.3	Grade Transitions	5-133
5.7.5.B.4	Full Removal.	5-133
5.7.5.B.5	Bare Deck HMA	5-133
5.7.5.B.6	Bridge Transverse Joint Seals	5-134
5.7.5.B.7	Bituminous Surface Treatments (BST).	5-134
5.7.5.B.8	Culverts and Other Structures	5-135
5.7.5.B.9	Paving Equipment Load Restrictions	5-135
5.7.5.B.10	Plans Preparation	5-135

5.8	Cast-in-place Post-Tensioned Bridges	5-136
5.8.1	Design Parameters	5-136
5.8.1.A	General	5-136
5.8.1.B	Bridge Types	5-136
5.8.1.B.1	Slab Bridge	5-136
5.8.1.B.2	T-Beam Bridge	5-137
5.8.1.B.3	Box Girder Bridge	5-137
5.8.1.C	Strand and Tendon Arrangements	5-137
5.8.1.D	Layout of Anchorages and End Blocks	5-139
5.8.1.E	Superstructure Shortening	5-142
5.8.1.F	Effects of Curved Tendons	5-142
5.8.1.G	Edge Tension Forces	5-143
5.8.2	Analysis	5-143
5.8.2.A	General	5-143
5.8.2.B	Section Properties	5-144
5.8.2.C	Preliminary Stress Check	5-144
5.8.2.D	Camber	5-145
5.8.2.E	Expansion Bearing Offsets	5-145
5.8.3	Post-tensioning	5-145
5.8.3.A	Tendon Layout	5-145
5.8.3.B	Prestress Losses	5-146
5.8.3.C	Jacking End	5-146
5.8.3.D	Steel Stress Curve	5-147
5.8.3.E	Flexural Stress in Concrete	5-148
5.8.3.F	Prestress Moment Curves	5-149
5.8.3.F.1	Single-Span Bridges, Simply Supported	5-149
5.8.3.F.2	Multispan Continuous Bridges	5-149
5.8.3.G	Partial prestressing	5-149
5.8.4	Shear and Anchorages	5-149
5.8.4.A	Shear Capacity	5-149
5.8.4.B	Horizontal Shear	5-150
5.8.4.C	End Block Stresses	5-150
5.8.5	Temperature Effects	5-150
5.8.6	Construction	5-151
5.8.6.A	General	5-151
5.8.6.B	Contract Plans	5-151
5.8.6.C	Shop Plans	5-151
5.8.6.D	Review of Post-tensioning Installation Drawings	5-151
5.8.6.E	During Construction	5-152
5.8.7	Post-tensioning Notes Contract Plans	5-152
5.8.7.A	Plan Details	5-152
5.8.7.B	Post-tensioning Notes	5-153

5.9	Spliced Prestressed Concrete Girders	5-154
5.9.1	Definitions	5-154
5.9.2	WSDOT Criteria for Use of Spliced Girders	5-154
5.9.3	Girder Segment Design	5-155
5.9.3.A	Design Considerations	5-155
5.9.3.B	Post-tensioning	5-155
5.9.4	Joints Between Segments	5-156
5.9.4.A	General	5-156
5.9.4.B	Location of Closure Joints	5-156
5.9.4.C	Details of Closure Joints	5-157
5.9.4.D	Joint Design	5-157
5.9.5	Review of Shop Plans for Spliced Prestressed Concrete Girders	5-160
5.9.6	Post-tensioning Notes — Spliced Prestressed Concrete Girders	5-160
5.10	Segmental Bridges	5-161
5.10.1	Cross Section Dimensions	5-161
5.11	Bridge Standard Drawings	5-162
5.12	Appendices	5-166
Appendix 5.1-A1	Standard Hooks	5-169
Appendix 5.1-A2	Minimum Reinforcement Clearance and Spacing for Beams and Columns	5-170
Appendix 5.1-A3	Reinforcing Bar Properties	5-171
Appendix 5.1-A4	Tension Development Length of Deformed Bars	5-172
Appendix 5.1-A5	Compression Development Length and Minimum Lap Splice of Grade 60 Bars	5-175
Appendix 5.1-A6	Tension Development Length of 90° and 180° Standard Hooks ...	5-176
Appendix 5.1-A7	Tension Lap Splice Lengths of Grade 60 Bars – Class B	5-178
Appendix 5.1-A8	Prestressing Strand Properties and Development Length	5-181
Appendix 5.2-A1	Working Stress Design	5-182
Appendix 5.2-A2	Working Stress Design	5-183
Appendix 5.2-A3	Working Stress Design	5-184
Appendix 5.3-A1	Positive Moment Reinforcement	5-185
Appendix 5.3-A2	Negative Moment Reinforcement	5-186
Appendix 5.3-A3	Adjusted Negative Moment Case I (Design for M at Face of Support)	5-187
Appendix 5.3-A4	Adjusted Negative Moment Case II (Design for M at 1/4 Point) ...	5-188
Appendix 5.3-A5	Cast-In-Place Deck Slab Design for Positive Moment Regions $f'_c = 4.0$ ksi	5-189
Appendix 5.3-A6	Cast-In-Place Deck Slab Design for Negative Moment Regions $f'_c = 4.0$ ksi	5-190
Appendix 5.3-A7	Slab Overhang Design-Interior Barrier Segment	5-191
Appendix 5.3-A8	Slab Overhang Design-End Barrier Segment	5-192

Appendix 5.6-A1-1 Span Capability of W Girders 5-193

Appendix 5.6-A1-2 Span Capability of WF Girders 5-194

Appendix 5.6-A1-3 Span Capability of Deck Bulb Tee Girders 5-196

Appendix 5.6-A1-4 Span Capability of WF Thin Deck Girders. 5-197

Appendix 5.6-A1-5 Span Capability of WF Deck Girders. 5-198

Appendix 5.6-A1-6 Span Capability of Trapezoidal Tub Girders without Top Flange. 5-199

Appendix 5.6-A1-7 Span Capability of Trapezoidal Tub Girders with Top Flange 5-200

Appendix 5.6-A1-8 Span Capability of Post-tensioned Spliced I-Girders 5-201

Appendix 5.6-A1-9 Span Capability of Post-tensioned Spliced Tub Girders 5-203

Appendix 5.6-A1-10 Span Capability of WF Girders with Lightweight Concrete. 5-205

Chapter 6 **Structural Steel**

6.0	Structural Steel	6-1
6.0.1	Introduction	6-1
6.0.2	Special Requirements for Steel Bridge Rehabilitation or Modification	6-1
6.0.3	Retrofit of Low Vertical Clearance Truss Portal and Sway Members	6-1
6.1	Design Considerations	6-6
6.1.1	Codes, Specification, and Standards	6-6
6.1.2	WSDOT Steel Bridge Practice	6-7
6.1.3	Preliminary Girder Proportioning	6-8
6.1.4	Estimating Structural Steel Weights	6-9
6.1.5	Bridge Steels	6-10
6.1.6	Plate Sizes	6-11
6.1.7	Girder Segment Sizes	6-11
6.1.8	Computer Programs	6-12
6.1.9	Fasteners	6-12
6.1.9.A	ASTM F 3125 GR A325 & GR F1852	6-13
6.1.9.B	ASTM A449	6-13
6.1.9.C	F1554 – Grade 105	6-13
6.1.9.D	ASTM F 3125 GR A490 & GR F2280	6-13
6.1.9.E	A354–Grade BD	6-13
6.1.10	Bending Steel	6-14
6.2	Girder Bridges	6-15
6.2.1	General	6-15
6.2.2	I-Girders	6-15
6.2.3	Tub or Box Girders	6-16
6.2.4	Fracture Critical Superstructures	6-17
6.3	Design of I-Girders	6-18
6.3.1	Limit States for AASHTO LRFD Bridge Design Specifications	6-18
6.3.2	Composite Section	6-18
6.3.3	Flanges	6-18
6.3.4	Webs	6-19
6.3.5	Transverse Stiffeners	6-19
6.3.6	Longitudinal Stiffeners	6-20
6.3.7	Bearing Stiffeners	6-20
6.3.8	Cross Frames	6-20
6.3.9	Bottom Laterals	6-23
6.3.10	Bolted Field Splice for Girders	6-24
6.3.11	Camber	6-25
6.3.12	Bridge Deck Placement Sequence	6-27
6.3.13	Bridge Bearings for Steel Girders	6-27

6.3.14	Surface Roughness and Hardness	6-27
6.3.15	Welding	6-29
6.3.16	Shop Assembly	6-30
6.4	Plan Details	6-31
6.4.1	General	6-31
6.4.2	Structural Steel Notes	6-31
6.4.3	Framing Plan.	6-31
6.4.4	Girder Elevation	6-32
6.4.5	Typical Girder Details	6-32
6.4.6	Cross Frame Details	6-32
6.4.7	Camber Diagram and Bearing Stiffener Rotation	6-33
6.4.8	Bridge Deck	6-33
6.4.9	Handrail Details, Inspection Lighting, and Access	6-33
6.4.10	Box Girder Details.	6-34
6.5	Shop Plan Review.	6-36
6.6	Painting of Existing Steel Bridges	6-37
6.6.1	General	6-37
6.6.2	Vertical Analysis	6-38
6.6.3	Horizontal Analysis	6-39
6.6.4	Special Considerations	6-41
6.6.4.A	Coast Guard	6-41
6.6.4.B	Moveable Spans	6-41
6.6.4.C	Traffic Control	6-42
6.6.4.D	Review of Construction Submittals	6-42
6.6.4.E	Structural Steel Repairs	6-42
6.6.5	Quantities and Estimates	6-43
6.7	Corrosion of Steel Foundations and Buried Structures	6-44
6.7.1	Corrosion of Steel Foundations	6-44
6.7.2	Corrosion and Abrasion of Metal Buried Structures	6-45
6.7.2.A	Corrosion.	6-46
6.7.2.B	Steel Structures.	6-46
6.7.2.C	Aluminum Alloy Structures	6-47
6.7.2.D	Alternative Coatings and Mitigation for De-icing Salts	6-49
6.7.2.E	Abrasion	6-49
6.8	Bridge Standard Drawings.	6-51
6.99	References	6-52

Chapter 7 Substructure Design

7.1	General Substructure Considerations	7-1
7.1.1	Foundation Design Process	7-1
7.1.1.A	Scoping Level Design	7-1
7.1.1.B	Develop Site Data and Preliminary Bridge Plan	7-1
7.1.1.C	Preliminary Foundation Design	7-2
7.1.1.D	Structural Analysis and Modeling	7-2
7.1.1.E	Final Foundation Design	7-3
7.1.2	Foundation Design Limit States	7-3
7.1.3	Seismic Design	7-3
7.1.4	Substructure and Foundation Loads	7-3
7.1.5	Concrete Class for Substructure	7-6
7.1.6	Foundation Seals	7-6
7.1.6.A	General Seal Criteria	7-7
7.1.6.A.1	Seal Vent Elevation	7-7
7.1.6.A.2	Scour	7-7
7.1.6.B	Spread Footing Seals	7-7
7.1.6.B.1	When a Seal is Required During Construction	7-7
7.1.6.B.2	When a Seal May Not Be Required for Construction	7-7
7.1.6.C	Deep Foundation Seals	7-8
7.1.7	Scour Requirements	7-8
7.1.7.A	Shallow Foundations	7-10
7.1.7.B	Deep Foundations	7-10
7.1.7.C	Walls Adjacent to Structures	7-12
7.1.7.D	Existing Structures	7-12
7.1.7.E	Buried Structures	7-12
7.2	Foundation Modeling for Seismic Loads	7-13
7.2.1	General	7-13
7.2.2	Substructure Elastic Dynamic Analysis Procedure	7-13
7.2.3	Bridge Model Section Properties	7-14
7.2.3.A	Cracked Properties for Columns	7-14
7.2.3.B	Shaft Properties	7-14
7.2.3.C	Cast-in-Place Pile Properties	7-15
7.2.4	Bridge Model Verification	7-15
7.2.5	Deep Foundation Modeling Methods	7-16
7.2.5.A	Method I – Equivalent Cantilever Column	7-16
7.2.5.B	Method II – Equivalent Base Springs	7-16
7.2.5.C	Method III – Non-Linear Soil Springs	7-16
7.2.5.D	Spring Location (Method II)	7-17
7.2.5.E	Boundary Conditions (Method II)	7-17
7.2.5.F	Spring Calculation (Method II)	7-18
7.2.5.G	Matrix Coordinate Systems (Method II)	7-18
7.2.5.H	Matrix Coefficient Definitions (Method II)	7-19

7.2.5.I	Group Effects	7-20
7.2.5.J	Shaft Caps and Pile Footings	7-20
7.2.6	Lateral Analysis of Piles and Shafts	7-20
7.2.6.A	Determination of Tip Elevations	7-20
7.2.6.B	Pile and Shaft Design for Lateral Loads	7-23
7.2.7	Spread Footing Modeling	7-24
7.3	Column Design	7-27
7.3.1	General Design Considerations	7-27
7.3.2	Slenderness Effects	7-27
7.3.2.A	Moment Magnification Method	7-28
7.3.2.B	Second-Order Analysis	7-29
7.3.2.B.1	Design Methods for a Second-Order Analysis	7-29
7.3.2.B.2	Applying Factored Loads	7-29
7.3.2.B.3	Member Properties	7-29
7.3.3	Shear Design	7-30
7.3.4	Column Silos	7-30
7.3.4.A	General Design and Detailing Requirements	7-30
7.3.4.B	Column Silos Formed From Extending Shaft Casing	7-30
7.3.4.C	Column Silos Formed by Other Methods	7-30
7.3.4.D	Column Silo Covers and Access Hatches	7-31
7.3.5	Column Reinforcement	7-32
7.3.5.A	Reinforcing Bar Material	7-32
7.3.5.B	Longitudinal Reinforcement	7-32
7.3.5.C	Longitudinal Splices	7-32
7.3.5.D	Longitudinal Development	7-33
7.3.5.D.1	Crossbeams	7-33
7.3.5.D.2	Footings	7-35
7.3.5.D.3	Shafts	7-36
7.3.5.E	Transverse Reinforcement	7-37
7.3.5.F	Spiral Splices and Hoops	7-40
7.3.6	Column and Wall Pier Hinges	7-42
7.3.7	Reduced Column Section	7-43
7.3.7.A	Inner Concrete Column	7-44
7.3.7.A.1	Longitudinal Reinforcement	7-44
7.3.7.A.2	Transverse Reinforcement	7-45
7.3.7.A.3	Analytical Plastic Hinge Region	7-45
7.3.7.B	Outer Concrete Column	7-45
7.3.7.C	Gap in Concrete at Reduced Column Section	7-46
7.4	Crossbeams	7-47
7.4.1	General Design	7-47
7.4.1.A	Stage I Design	7-47
7.4.1.B	Stage II Design	7-48
7.4.1.C	Other Crossbeam Types	7-49

7.5	Abutment Design and Details	7-50
7.5.1	General	7-50
7.5.1.A	Abutment Types	7-50
7.5.1.A.1	Stub Abutments	7-50
7.5.1.A.2	Cantilever Abutments	7-51
7.5.1.A.3	Rigid Frame Abutments	7-51
7.5.1.A.4	Bent-Type Abutments	7-52
7.5.1.A.5	Isolated Abutments	7-53
7.5.2	Abutments Supported By Mechanically-Stabilized Earth Walls	7-54
7.5.2.A	Single-span Bridges with Precast Slab Superstructures Supported Directly on Reinforced Soil	7-55
7.5.2.B	Bridges with spread footing abutments supported by a geosynthetic wall or SE wall.	7-58
7.5.3	Embankment at Abutments.	7-59
7.5.4	Abutment Loading.	7-60
7.5.4.A	Dead Load - DC	7-60
7.5.4.B	Live Load - LL	7-60
7.5.4.C	Earth Pressure - EH, EV	7-60
7.5.4.D	Earthquake Load - EQ	7-60
7.5.4.E	Bearing Forces - TU	7-60
7.5.5	Temporary Construction Load Cases	7-61
7.5.5.A	Superstructure Built after Backfill at Abutment	7-61
7.5.5.B	Wing Wall Overturning	7-61
7.5.6	Abutment Bearings and Girder Stops	7-61
7.5.6.A	Abutment Bearings	7-61
7.5.6.B	Bearing Seats	7-62
7.5.6.C	Transverse Girder Stops	7-62
7.5.7	Abutment Expansion Joints	7-63
7.5.8	Open Joint Details.	7-63
7.5.9	Construction Joints	7-65
7.5.10	Abutment Wall Design	7-65
7.5.10.A	General	7-65
7.5.10.B	Temperature and Shrinkage Reinforcement	7-65
7.5.10.C	Cross Ties	7-66
7.5.11	Drainage and Backfilling.	7-67
7.6	Abutment Wing Walls and Curtain Walls	7-69
7.6.1	Traffic Barrier Loads	7-69
7.6.2	Wing Wall Design	7-69
7.6.3	Wing Wall Detailing	7-69
7.7	Footing Design	7-70
7.7.1	General Footing Criteria	7-70
7.7.1.A	Minimum Cover and Footing Depth.	7-70
7.7.1.B	Pedestals.	7-71

7.7.2	Loads and Load Factors	7-71
7.7.3	Geotechnical Report Summary	7-72
7.7.3.A	Bearing Resistance - Service, Strength, and Extreme Event Limit States	7-72
7.7.3.B	Sliding Resistance - Strength and Extreme Event Limit States.	7-72
7.7.3.C	Foundation Springs - Extreme Event Limit States.	7-72
7.7.4	Spread Footing Design	7-73
7.7.4.A	Abutment Spread Footing Force Diagram.	7-73
7.7.4.B	Bearing Stress.	7-74
7.7.4.C	Failure By Sliding	7-76
7.7.4.D	Overturning Stability	7-76
7.7.4.E	Footing Settlement	7-76
7.7.4.F	Concrete Design	7-77
7.7.4.F.1	Footing Thickness and Shear	7-77
7.7.4.F.2	Footing Force Distribution.	7-77
7.7.4.F.3	Vertical Reinforcement (Column or Wall)	7-77
7.7.4.F.4	Bottom Reinforcement	7-77
7.7.4.F.5	Top Reinforcement	7-78
7.7.4.F.6	Shrinkage and Temperature Reinforcement.	7-78
7.7.5	Pile-Supported Footing Design	7-78
7.7.5.A	Pile Embedment, Clearance, and Rebar Mat Location	7-79
7.7.5.B	Concrete Design	7-79
7.8	Shafts	7-80
7.8.1	Axial Resistance	7-80
7.8.1.A	Embankment Consolidation Downdrag	7-82
7.8.1.B	Seismic Liquefaction Downdrag	7-82
7.8.1.C	Scour.	7-82
7.8.1.D	Axial Resistance Group Reduction Factors.	7-83
7.8.2	Structural Design and Detailing	7-84
7.9	Piles and Piling	7-92
7.9.1	Pile Types	7-92
7.9.1.A	Cast-in-place Concrete Piles.	7-92
7.9.1.B	Structural Steel Pipe Piles.	7-92
7.9.1.C	Steel H Piles	7-92
7.9.1.D	Timber Piles	7-92
7.9.1.E	Steel Sheet Piles.	7-92
7.9.2	Single Pile Axial Resistance	7-93
7.9.3	Block Failure	7-94
7.9.4	Pile Uplift	7-94
7.9.5	Pile Spacing	7-94
7.9.6	Structural Design and Detailing of CIP Concrete Piles.	7-94
7.9.7	Pile Splices	7-95

7.9.8	Pile Lateral Design	7-96
7.9.9	Battered Piles	7-96
7.9.10	Pile Tip Elevations and Quantities	7-96
7.9.11	Plan Pile Resistance	7-97
7.10	Concrete-Filled Steel Tubes	7-98
7.10.1	Scope	7-98
7.10.2	Design Requirements	7-99
7.10.2.A	Materials	7-99
7.10.2.B	Limit States	7-99
7.10.2.C	General Dimensions	7-100
7.10.2.D	Stiffness	7-100
7.10.2.E	Flexure and Axial Resistance	7-100
7.10.2.F	Stability Considerations for Unbraced or Partially-braced Members ..	7-103
7.10.2.G	Shear Resistance	7-103
7.10.2.H	Corrosion	7-103
7.10.2.I	Side resistance	7-103
7.10.3	CFST-to-Cap Annular Ring Connections	7-103
7.10.3.A	Annular Ring	7-104
7.10.3.B	Embedment	7-106
7.10.3.C	Punching Shear	7-106
7.10.3.D	Pile Cap and/or Cap Beam Reinforcement	7-106
7.10.4	CFST-to-Cap Reinforced Concrete Connections	7-108
7.10.4.A	CFST Requirements	7-108
7.10.4.B	Embedment and Concrete Cover	7-109
7.10.4.C	Pile Cap and/or Cap Beam Reinforcement	7-110
7.10.5	RCFST-to-Column and CFST-to Column Connections	7-110
7.10.6	Partially-filled CFST	7-112
7.10.7	Construction Requirements	7-112
7.10.8	Notation	7-113
7.11	Bridge Standard Drawings	7-115
7.12	Appendices	7-116
Appendix 7.3-A2	Noncontact Lap Splice Length Column to Shaft Connections	7-117
Appendix 7-B1	Linear Spring Calculation Method II (Technique I)	7-119
Appendix 7-B2	Pile Footing Matrix Example Method II (Technique I)	7-124
Appendix 7-B3	Non-Linear Springs Method III	7-127
7.99	References	7-129

Chapter 8 Walls and Buried Structures

8.1 Retaining Walls 8-1

8.1.1 General 8-1

8.1.2 Common Types of Retaining Walls 8-2

8.1.2.A Preapproved Proprietary Walls 8-2

8.1.2.A.1 Structural Earth Walls (SE) 8-2

8.1.2.A.2 Other Proprietary Walls 8-3

8.1.2.B Geosynthetic Wrapped Face Walls 8-3

8.1.2.C Reinforced Concrete Walls 8-3

8.1.2.D Soldier Pile Walls and Soldier Pile Tieback Walls 8-3

8.1.2.E Soil Nail Walls 8-3

8.1.3 General Design Considerations 8-4

8.1.4 Design of Reinforced Concrete Retaining Walls 8-4

8.1.4.A Standard Reinforced Concrete Retaining Walls 8-4

8.1.4.A.1 Standard Cast-In-Place Reinforced Concrete Retaining Wall Types 1 through 8 8-4

8.1.4.A.2 Standard Precast Reinforced Concrete Retaining Wall ... 8-5

8.1.4.B Non-Standard Reinforced Concrete Retaining Walls 8-6

8.1.4.B.1 Bearing Resistance, Eccentricity, and Sliding Stability ... 8-7

8.1.4.B.2 Application of Lateral Loads 8-7

8.1.4.B.3 Application of Collision Loads 8-7

8.1.4.B.4 Wall Footing Structural Design 8-7

8.1.4.B.5 Wall Stem Structural Design 8-8

8.1.5 Design of Cantilever Soldier Pile and Soldier Pile Tieback Walls 8-10

8.1.5.A Ground Anchors (Tiebacks) 8-10

8.1.5.B Design of Soldier Pile (discrete vertical elements) 8-11

8.1.5.B.1 Application of Lateral Loads 8-11

8.1.5.B.2 Determining Depth of Pile Embedment 8-11

8.1.5.B.3 Soldier Pile Shaft Backfill 8-11

8.1.5.C Design of Lagging 8-12

8.1.5.C.1 Temporary Timber Lagging 8-12

8.1.5.C.2 Permanent Lagging 8-12

8.1.5.D Design of Fascia Panels 8-13

8.1.6 Design of Structural Earth Walls 8-13

8.1.6.A Preapproved Proprietary Structural Earth Walls 8-14

8.1.6.B Non-Preapproved Proprietary Structural Earth Walls 8-14

8.1.7 Design of Geosynthetic Walls 8-14

8.1.7.A Standard Geosynthetic Wrapped Face Walls 8-14

8.1.7.B Non-Standard Geosynthetic Walls 8-14

8.1.8 Design of Soil Nail Walls 8-15

8.1.9 Design of Shaft Walls 8-15

8.1.10	Scour of Retaining Walls	8-15
8.1.11	Miscellaneous Items	8-18
8.1.11.A	Architectural Finishes and Top of Wall Profile	8-18
8.1.11.B	Worker Fall Protection	8-18
8.1.11.C	Pedestrian and Bicycle Railings for Fall Protection	8-18
8.1.11.D	Drainage	8-18
8.1.11.E	Expansion, Contraction and Construction Joints	8-19
8.1.11.E.1	Expansion Joints	8-19
8.1.11.E.2	Contraction Joints	8-20
8.1.11.E.3	Construction Joints	8-20
8.1.11.F	Detailing of Standard Reinforced Concrete Retaining Walls	8-20
8.1.11.G	Embankment Widening at End of Wall	8-20
8.1.11.H	Wall Face Embedment	8-20
8.2	Noise Barrier Walls	8-21
8.2.1	General	8-21
8.2.2	Loads	8-21
8.2.3	Design	8-22
8.2.3.A	Standard Plan Noise Barrier Walls	8-22
8.2.3.B	Non-Standard Noise Barrier Walls	8-24
8.3	Buried Structures	8-25
8.3.1	General Policy	8-25
8.3.2	WSDOT Templates and Standard Plans	8-26
8.3.2.A	Buried Structure Templates	8-26
8.3.2.B	Buried Structure Standard Plans	8-26
8.3.3	General Design Requirements	8-27
8.3.3.A	Design Delivery Methods	8-27
8.3.3.A.1	Contractor Supplied Design	8-27
8.3.3.A.2	Agency Supplied Design	8-27
8.3.3.A.3	Design Build	8-28
8.3.3.B	Application of Loads	8-28
8.3.3.B.1	Live Load, LL	8-28
8.3.3.C	Deck Protection and Approach Slabs	8-29
8.3.3.D	Buried Structure Foundation Design	8-29
8.3.3.E	Buried Structure Wingwall and Headwall Design	8-29
8.3.3.F	Worker, Pedestrian and Bicycle Fall Protection	8-30
8.3.3.G	W-Beam Guardrail on Buried Structures (TL-3)	8-30
8.3.3.H	Buried Structure Seismic Design	8-30
8.3.3.H.1	Seismic Loading Effects	8-31
8.3.3.H.2	Load Combinations for Transient Seismic Motion	8-32
8.3.3.H.3	Attenuation of Peak Ground Motion Parameters	8-32
8.3.3.I	Load Rating	8-33
8.3.3.J	Usage of Buried Structure Design Software and/or Spreadsheets	8-33

	8.3.3.K	Buried Structure Standard Plans	8-34
	8.3.3.K.1	Split Boxes Structures	8-37
	8.3.3.K.2	Three-Sided Structures	8-38
8.3.4	Materials		8-39
	8.3.4.A	Concrete	8-39
	8.3.4.B	Reinforcing Steel	8-39
	8.3.4.C	Bedding and Leveling Material	8-39
	8.3.4.C.1	Precast Reinforced Concrete Buried Structure – Three-Sided	8-39
	8.3.4.C.2	Precast Reinforced Concrete Buried Structure – Split Box	8-39
	8.3.4.C.3	Precast Reinforced Concrete Retaining Walls (Wingwalls)	8-40
	8.3.4.D	Joint Sealant and External Sealing Bands	8-40
	8.3.4.E	Corrosion	8-40
	8.3.4.E.1	Metal Structural Plate Structures	8-40
	8.3.4.E.2	Concrete Structures	8-40
8.3.5	Limit States and Design Methodologies		8-40
	8.3.5.A	Service Limit State	8-40
	8.3.5.A.1	Total and Differential Settlement	8-40
	8.3.5.A.2	Deflection and Shear Transfer	8-41
	8.3.5.A.3	Control of Cracking	8-41
	8.3.5.B	Strength Limit State	8-41
	8.3.5.C	Extreme Limit State	8-41
	8.3.5.D	Boundary Conditions	8-42
	8.3.5.E	Structural Modeling	8-42
	8.3.5.E.1	Three-Sided Structures	8-42
	8.3.5.E.2	Split Box Structures	8-42
	8.3.5.E.3	Split Box ~ Slab Structures	8-44
8.3.6	Provisions for Structure Type		8-44
	8.3.6.A	Concrete Box and Split Box Structures	8-44
	8.3.6.A.1	Precast Geometric Limitations	8-44
	8.3.6.A.2	Distribution of Live Load through Earth Fill	8-46
	8.3.6.A.3	Joint Design and Details	8-46
	8.3.6.B	Concrete Three-Sided Structures	8-47
	8.3.6.B.1	Precast Geometric Limitations	8-47
	8.3.6.B.2	Distribution of Live Load through Earth Fill	8-48
	8.3.6.B.3	Joint Design and Details	8-48
	8.3.6.C	Design of Metal Structural Plate Structures	8-48
8.3.7	Design of Detention Vaults		8-49
8.3.8	Design of Tunnels		8-51
8.4	Bridge Standard Drawings		8-53
8.5	Appendices		8-55
8.99	References		8-56
	Appendix 8.1-A1	Summary of Design Specification Requirements for Walls	8-58

Chapter 9 *Bearings and Expansion Joints*

9.1	Expansion Joints	9-1
9.1.1	General Considerations	9-1
9.1.1.A	Concrete Bridges	9-2
9.1.1.B	Steel Bridges	9-2
9.1.2	General Design Criteria	9-3
9.1.2.A	Shrinkage Effects	9-3
9.1.2.B	Thermal Effects	9-3
9.1.3	Small Movement Range Joints	9-5
9.1.3.A	Compression Seals	9-5
9.1.3.B	Rapid-Cure Silicone Sealants	9-6
9.1.3.C	Asphaltic Plug Joints	9-8
9.1.3.D	Headers	9-9
9.1.3.E	Bridge Paving Joint Seals	9-9
9.1.4	Medium Movement Range Joints	9-9
9.1.4.A	Steel Sliding Plate Joints	9-9
9.1.4.B	Strip Seal Joints	9-10
9.1.4.C	Bolt-down Panel Joints	9-11
9.1.5	Large Movement Range Joints	9-12
9.1.5.A	Steel Finger Joints	9-12
9.1.5.B	Modular Expansion Joints	9-13
9.1.5.B.1	Operational Characteristics	9-13
9.1.5.B.2	Movement Design	9-15
9.1.5.B.3	Review of Shop Drawings and Structural Design Calculations	9-16
9.1.5.B.4	Construction Considerations	9-17
9.2	Bearings	9-18
9.2.1	General Considerations	9-18
9.2.2	Force Considerations	9-18
9.2.3	Movement Considerations	9-19
9.2.3.A	Elastomeric and Fabric Pad Bearings	9-19
9.2.3.B	HLMR Bearings	9-19
9.2.4	Detailing Considerations	9-19
9.2.5	Bearing Types	9-20
9.2.5.A	Elastomeric Bearings	9-20
9.2.5.B	Fabric Pad Sliding Bearings	9-22
9.2.5.B.1	Fabric Pad Design	9-23
9.2.5.B.2	PTFE	9-23
9.2.5.C	Pin Bearings	9-24
9.2.5.D	Rocker and Roller Type Bearings	9-24
9.2.5.E	Spherical Bearings	9-24
9.2.5.F	Disk Bearings	9-25

9.2.6	Miscellaneous Details	9-25
9.2.6.A	Temporary Support before Grouting Masonry Plate	9-25
9.2.6.A.1	Shim Packs	9-25
9.2.6.A.2	Two-step Grouting with Cast Sleeves	9-25
9.2.6.B	Anchor Bolts	9-26
9.2.7	Contract Drawing Representation	9-26
9.2.8	Shop Drawing Review	9-26
9.2.9	Bearing Replacement Considerations	9-26
9.3	Seismic Isolation Bearings	9-27
9.3.1	General Considerations	9-27
9.3.2	Suitability and Selection Considerations	9-27
9.3.3	General Design Criteria	9-28
9.3.4	Seismic Isolation Bearing Submittal Requirements	9-28
9.3.4.A	Shop Drawings	9-29
9.3.4.B	Bearing Materials and Fabrication	9-29
9.3.4.C	Paint	9-29
9.3.4.D	Bearing Specifications	9-29
9.3.4.E	Fabrication	9-29
9.3.5	Seismic Isolation Bearing Review Process	9-29
9.3.5.A	Design Calculations	9-30
9.3.5.B	Shop Drawings	9-30
9.3.6	Seismic Isolation Bearing Inspection	9-31
9.3.6.A	Fabrication Inspection	9-31
9.3.6.B	Field Inspection	9-31
9.4	Bridge Standard Drawings	9-32
9.4.1	Expansion Joints	9-32

Chapter 10 Signs, Barriers, Approach Slabs, and Utilities

10.1 Sign and Luminaire Supports 10-1

 10.1.1 Loads 10-1

 10.1.1.A General 10-1

 10.1.1.B Dead Loads. 10-1

 10.1.1.C Live Load. 10-1

 10.1.1.D Wind Loads 10-1

 10.1.1.E Fatigue Design 10-2

 10.1.1.F Ice and Snow Loads 10-2

 10.1.1.G Group Load Combinations 10-2

 10.1.1.H Impact Loads. 10-3

 10.1.2 Bridge Mounted Signs. 10-3

 10.1.2.A Vertical Clearance 10-3

 10.1.2.B Geometrics 10-4

 10.1.2.C Aesthetics 10-5

 10.1.2.D Sign Placement 10-5

 10.1.2.E Installation 10-6

 10.1.2.F Installing/Replacing New Sign on Existing Bracket Supports 10-6

 10.1.2.G Detailing 10-7

 10.1.3 Monotube Sign Structures Mounted on Bridges 10-7

 10.1.3.A Design Loads 10-7

 10.1.3.B Vertical Clearance 10-7

 10.1.3.C Geometrics 10-7

 10.1.4 Monotube Sign Structures 10-8

 10.1.4.A Sign Bridge Conventional Design 10-8

 10.1.4.B Cantilever Conventional Design 10-8

 10.1.4.C Balanced Cantilever Conventional Design 10-10

 10.1.4.D VMS Installation 10-10

 10.1.4.E Monotube Sheet Guidelines 10-11

 10.1.4.F Monotube Quantities 10-11

 10.1.5 Foundations 10-11

 10.1.5.A Monotube Sign Structure Foundation Types 10-11

 10.1.5.B Luminaire, Signal Standard, and Camera Pole Foundation Types 10-12

 10.1.5.C Foundation Design 10-12

 10.1.5.C.1 Monotube Sign Structures Foundation Type 1 Design 10-13

 10.1.5.C.2 Monotube Sign Structures Foundation Type 2 and 3 10-13

 10.1.5.C.3 Monotube Sign Structures Non-Conventional Design Foundations 10-13

 10.1.5.C.4 Signal Foundation Design. 10-13

 10.1.5.D Foundation Quantities 10-14

10.2	Bridge Traffic Barriers	10-15
10.2.1	General Guidelines	10-15
10.2.2	Bridge Railing Test Levels	10-16
10.2.3	Available WSDOT Designs	10-16
10.2.3.A	Service Level 1 (SL-1) Weak Post Guardrail (TL-2)	10-16
10.2.3.B	Texas T-411 Aesthetic Concrete Baluster (TL-2)	10-17
10.2.3.C	Traffic Barrier – 32" F-Shape (TL-3)	10-17
10.2.3.D	Traffic Barrier – 34" Single Slope (TL-3)	10-18
10.2.3.E	Oregon 3-Tube Curb Mounted Traffic Barrier (TL-4)	10-19
10.2.3.F	Traffic Barrier – 42" F-Shape (TL-4 and TL-5)	10-19
10.2.3.G	Traffic Barrier – 42" Single Slope (TL-4 and TL-5)	10-20
10.2.4	Design Criteria	10-20
10.2.4.A	Design Values	10-20
10.2.4.B	Geometry	10-21
10.2.4.C	Standard Detail Sheet Modifications	10-21
10.2.4.D	Miscellaneous Design Information	10-22
10.3	At Grade Concrete Barriers	10-24
10.3.1	Differential Grade Concrete Barriers	10-24
10.3.1.A	Differential Grade Concrete Barriers	10-24
10.3.2	Traffic Barrier Moment Slab	10-25
10.3.2.A	General	10-25
10.3.2.B	Guidelines for Moment Slab Design	10-26
10.3.2.B.1	Structural Capacity	10-26
10.3.2.B.2	Global Stability	10-26
10.3.2.B.3	Minimum and Maximum Dimensions	10-27
10.3.2.B.4	Sliding of the Barrier	10-27
10.3.2.B.5	Overturning of the Barrier	10-28
10.3.2.C	Guidelines for the Soil Reinforcement	10-28
10.3.2.D	Design of the Wall Panel	10-28
10.3.3	Precast Concrete Barrier	10-29
10.3.3.A	Concrete Barrier Type F and Type 2	10-29
10.3.3.B	Concrete Barrier Type F Narrow Base and Concrete Barrier Type 4	10-29
10.4	Bridge Traffic Barrier Rehabilitation	10-30
10.4.1	Policy	10-30
10.4.2	Guidelines	10-30
10.4.3	Design Criteria	10-30
10.4.4	WSDOT Bridge Inventory of Bridge Rails	10-31
10.4.5	Available Retrofit Designs	10-32
10.4.5.A	Washington Thrie Beam Retrofit of Concrete Balusters	10-32
10.4.5.B	Delaware Thrie Beam Guardrail	10-32
10.4.5.C	Concrete Parapet Retrofit	10-32
10.4.5.D	SL-1 Weak Post	10-32

10.4.6	Available Replacement Designs	10-32
10.4.6.A	Traffic Barrier – Shape F Retrofit.	10-32
10.5	Bridge Railing	10-33
10.5.1	Design.	10-33
10.5.2	Railing Types	10-33
10.5.2.A	Bridge Pedestrian Railing Type BP-10	10-33
10.5.2.B	Bridge Pedestrian Railing Type BP-22	10-33
10.5.2.C	Bridge Pedestrian Railing Type BP-12	10-33
10.5.2.D	Bridge Pedestrian Railing Type BP-54	10-34
10.5.2.E	Bridge Railing Type Snow Fence	10-34
10.5.2.F	Bridge Railing Type Chain Link Fence	10-34
10.6	Bridge Approach Slabs	10-35
10.6.1	Notes to Region for Preliminary Plan	10-36
10.6.2	Bridge Approach Slab Design Criteria	10-36
10.6.3	Bridge Approach Slab Detailing	10-36
10.6.4	Skewed Bridge Approach Slabs	10-37
10.6.5	Approach Anchors and Expansion Joints	10-39
10.6.6	Bridge Approach Slab Addition or Retrofit to Existing Bridges	10-39
10.6.7	Bridge Approach Slab Staging	10-41
10.7	Traffic Barrier on Bridge Approach Slabs	10-42
10.7.1	Bridge Approach Slab over Wing Walls, Cantilever Walls or Geosynthetic Walls.	10-42
10.7.2	Bridge Approach Slab over SE Walls	10-44
10.8	Utilities Installation on New and Existing Structures	10-45
10.8.1	General Concepts.	10-45
10.8.1.A	Responsibilities of the Utility Company	10-45
10.8.1.B	Confined Spaces.	10-45
10.8.1.C	Coating and Corrosion Protection	10-45
10.8.2	Utility Design Criteria	10-48
10.8.2.A	Utility Location.	10-48
10.8.2.B	Termination at the Bridge Ends	10-48
10.8.2.C	Utility Expansion	10-49
10.8.2.D	Utility Blockouts.	10-49
10.8.2.E	Gas Lines or Volatile Fluids.	10-49
10.8.2.F	Water Lines	10-49
10.8.2.G	Sewer Lines.	10-50
10.8.2.H	Electrical (Power and Communications)	10-50
10.8.3	Box/Tub Girder Bridges	10-50
10.8.4	Traffic Barrier Conduit.	10-51
10.8.5	Conduit Types	10-51

10.8.6	Utility Supports	10-51
10.8.6.A	Concrete Embedment	10-52
10.8.6.B	Pipe Hangers	10-52
10.8.6.C	Surface Mounting	10-52
10.9	Review Procedure for Utility Installations on Existing Structures	10-53
10.9.1	Utility Review Checklist	10-54
10.10	Anchors for Permanent Attachments	10-55
10.11	Drainage Design	10-56
10.11.1	Geometrics	10-56
10.11.2	Hydrology	10-56
10.11.3	On Bridge Systems	10-56
10.11.4	Construction	10-56
10.12	Bridge Security	10-57
10.12.1	General	10-57
10.12.2	Design	10-57
10.12.3	Design Criteria	10-58
10.13	Temporary Bridges	10-59
10.13.1	General	10-59
10.13.2	Design	10-59
10.13.2.A	One To Two Construction Season Temporary Bridges	10-59
10.13.2.B	Three To Five Construction Season Temporary Bridges	10-59
10.13.2.B.1	Design Requirements	10-59
10.13.2.B.2	Seismic Design Requirements	10-60
10.13.2.B.3	Deck Design Requirements	10-60
10.13.2.B.4	Superstructure Design Requirements	10-60
10.13.2.B.5	Foundation Design Requirements	10-60
10.13.3	NBI Requirements	10-61
10.13.4	Submittal Requirements	10-61
10.14	Bridge Standard Drawings	10-62
10.99	References	10-65

Chapter 11 Detailing Practice

11.1	Standard Office Practices	11-1
11.1.1	General	11-1
11.1.1.A	Purpose	11-1
11.1.1.B	Planning	11-1
11.1.1.C	Drawing Orientation and Layout Control	11-1
11.1.1.D	Annotation	11-2
11.1.1.D.1	Text and Labeling	11-2
11.1.1.D.2	Dimensioning	11-3
11.1.1.D.3	Callouts (See Figure 11.1.1-D6 below)	11-4
11.1.1.D.4	Key Notes (See Figure 11.1.1-D7 below)	11-5
11.1.1.E	Line Work	11-7
11.1.1.F	Scale	11-8
11.1.1.G	Graphic Symbols	11-8
11.1.1.H	Structural Sections, Views and Details	11-9
11.1.1.I	Revisions	11-10
11.1.1.J	Title Block	11-11
11.1.1.K	Reinforcement Detailing	11-12
11.1.2	Bridge Office Standard Drawings and Office Examples	11-14
11.1.2.A	General	11-14
11.1.2.B	Use of Standards	11-14
11.1.2.C	Maintenance of Standard Drawings	11-14
11.1.3	Typical Plan Set and Sheets	11-15
11.1.3.A	Plan Sheet Organization	11-15
11.1.3.B	Sheet Types	11-16
11.1.3.C	Sheet Contents	11-17
11.1.3.D	Wall Structure Sheets and Detailing Practices	11-22
11.1.3.D.1	Layout	11-22
11.1.3.D.2	Developed Elevation	11-22
11.1.3.D.3	Details	11-23
11.1.4	Electronic Plan Sharing Policy	11-23
11.1.5	Structural Steel	11-24
11.1.5.A	General	11-24
11.1.5.B	Bars	11-24
11.1.5.C	Plates	11-24
11.1.5.D	Strips	11-24
11.1.5.E	Labeling	11-24
11.1.6	Aluminum Section Designations	11-25
11.1.7	Abbreviations	11-26
11.1.7.A	General	11-26
11.1.7.B	List of abbreviations commonly used on bridge plan sheets:	11-26

11.2 Appendices	11-34
Appendix 11.2-A1 Dimensional Callout Example	11-35
Appendix 11.2-A2 Typical Details	11-36
Appendix 11.2-A3 Typical Section Callouts	11-37
Appendix 11.2-A4 Reinforcement Callout Examples	11-38

Chapter 12 Quantities, Costs, and Specifications

12.1	Quantities - General	12-1
12.1.1	Cost Estimating Quantities	12-1
12.1.1.A	Conceptual Stage	12-1
12.1.1.B	Preliminary Plan Stage	12-1
12.1.1.C	Design Stage	12-1
12.1.1.D	Final Contract Quantities	12-1
12.1.2	Not Included in Bridge Quantities List	12-1
12.2	Computation of Quantities	12-2
12.2.1	Responsibilities	12-2
12.2.1.A	Design Unit	12-2
12.2.1.B	Bridge Project Support Unit	12-2
12.2.2	Procedure for Computation	12-2
12.2.3	Data Source	12-3
12.2.4	Accuracy	12-3
12.2.4.A	Preliminary Quantities	12-3
12.2.4.B	Final Quantities	12-3
12.2.5	Excavation	12-3
12.2.5.A	Structure Excavation, Class A	12-3
12.2.5.B	Special Excavation	12-5
12.2.6	Shoring or Extra Excavation, Class A	12-6
12.2.7	Piling	12-8
12.2.8	Conduit Pipe	12-8
12.2.9	Private Utilities Attached To Bridge Structures	12-9
12.2.10	Drilled Shafts	12-9
12.3	Construction Costs	12-10
12.3.1	Introduction	12-10
12.3.2	Factors Affecting Costs	12-10
12.3.2.A	Type of Structure	12-10
12.3.2.B	Location of Project Site	12-10
12.3.2.C	Size of Project Contract	12-10
12.3.2.D	Foundation Requirements	12-10
12.3.2.E	Sequencing of Project	12-10
12.3.3	Development of Cost Estimates	12-11
12.3.3.A	Types	12-11
12.3.3.A.1	Prospectus and Project Summary Estimates	12-11
12.3.3.A.2	Preliminary Design Estimates	12-11
12.3.3.A.3	Estimate Updates During Design	12-11
12.3.3.A.4	Contract Estimates	12-11

12.3.3.B	Responsibilities	12-12
12.3.3.B.1	Bridge Project Support Unit	12-12
12.3.3.B.2	Designer	12-12
12.3.3.C	Documentation	12-12
12.3.3.D	Cost Data	12-12
12.3.3.D.1	General	12-12
12.3.3.D.2	Deck or Wall Face Area	12-12
12.3.3.D.3	Bridge Widening and New Bridges	12-13
12.3.3.D.4	Bridge Rail Replacement	12-13
12.3.3.D.5	Bridge Lengths With Unequal Wingwalls	12-13
12.3.3.D.6	Retaining Walls	12-13
12.4	Construction Specifications and Estimates	12-14
12.4.1	General	12-14
12.4.2	Definitions	12-14
12.4.2.A	<i>Standard Specifications</i>	12-14
12.4.2.B	Mandatory General Special Provisions	12-14
12.4.2.C	Special Provisions	12-14
12.4.2.D	Addendum	12-14
12.4.2.E	AD Copy	12-14
12.4.2.F	As defined in <i>Standard Specifications</i> Section 1-02.4	12-14
12.4.3	General Bridge S&E Process	12-15
12.4.3.A	Typical Reviews and Milestone Dates	12-15
12.4.3.B	Constructability Review Set Distribution	12-15
12.4.3.C	PS&E Review Set Distribution	12-16
12.4.4	Reviewing Bridge Plans	12-16
12.4.4.A	Job File	12-16
12.4.4.B	PS&E Check List (Form 230-037 and Appendix 12.4-A1)	12-16
12.4.4.C	Summary of Quantities (Form 230-031 and Appendix 12.2-A1)	12-17
12.4.4.D	Plans	12-17
12.4.4.E	Not Included in Bridge Quantities List (Form 230-038 and Appendix 12.1-A1)	12-17
12.4.4.F	Geotechnical Report	12-17
12.4.5	Preparing the Bridge Cost Estimates	12-17
12.4.5.A	General	12-17
12.4.5.B	Procedure	12-18
12.4.6	Preparing the Bridge Specifications	12-18
12.4.6.A	General	12-18
12.4.6.B	Procedure	12-18
12.4.7	Preparing the Bridge Working Day Schedule	12-19
12.4.7.A	General	12-19
12.4.7.B	Procedure	12-19

12.4.8	Reviewing Projects Prepared by Consultants	12-20
12.4.8.A	General	12-20
12.4.8.B	Procedure	12-20
12.4.9	Submitting the PS&E Package	12-20
12.4.9.A	General	12-20
12.4.10	PS&E Review Period and Turn-in for AD Copy	12-21
12.4.10.A	Description	12-21
12.4.10.B	Procedure	12-21
12.5	Appendices	12-22
Appendix 12.1-A1	Not Included In Bridge Quantities List	12-23
Appendix 12.2-A1	Bridge Quantities	12-24
Appendix 12.3-A1	Structural Estimating Aids Construction Costs	12-29
Appendix 12.3-A2	Structural Estimating Aids Construction Costs	12-31
Appendix 12.3-A3	Structural Estimating Aids Construction Costs	12-33
Appendix 12.3-A4	Structural Estimating Aids Construction Costs	12-35
Appendix 12.3-B1	Cost Estimate Summary	12-36
Appendix 12.4-A1	Special Provisions Checklist	12-37
Appendix 12.4-A2	Structural Estimating Aids Construction Time Rates	12-42
Appendix 12.4-B1	Construction Working Day Schedule	12-44

Chapter 13 Bridge Load Rating

13.1	General	13-1
13.1.1	LRFR Method per the MBE	13-2
13.1.1.A	Rating Equation	13-2
13.1.1.B	Condition Factor (ϕ_{C_c})	13-2
13.1.1.C	System Factor (ϕ_s)	13-3
13.1.1.D	Dead and Live Load Factors	13-3
13.1.1.E	Live Load Factors for Legal and Permit Loads	13-3
13.1.2	Load Factor Method (LFR)	13-5
13.1.2.A	Ultimate Method (LFR)	13-5
13.1.2.A.1	Rating Equation	13-5
13.1.2.B	Dead and Live Load Factors	13-5
13.1.2.C	Impact (IM)	13-5
13.1.2.D	Resistance Factors (LFR) Method	13-6
13.1.2.E	Service Method (LFR)	13-7
13.1.2.F	Inventory Rating	13-7
13.1.2.G	Operating Rating	13-7
13.1.3	Allowable Stress Method (ASD)	13-7
13.1.4	Live Loads	13-8
13.1.5	Rating Trucks	13-8
13.1.5.A	Design Trucks	13-8
13.1.5.B	Legal Trucks	13-9
13.1.5.C	Overload Trucks	13-10
13.1.5.D	Emergency Vehicles	13-10
13.2	Special Rating Criteria	13-11
13.2.1	Dead Loads	13-11
13.2.2	Live Load Distribution Factors	13-11
13.2.3	Reinforced Concrete Structures	13-12
13.2.4	Prestressed Concrete Structures	13-12
13.2.5	Concrete Decks	13-12
13.2.6	Concrete Crossbeams	13-12
13.2.7	In-Span Hinges	13-12
13.2.8	Girder Structures	13-13
13.2.9	Box Girder Structures	13-13
13.2.10	Segmental Concrete Bridges	13-13
13.2.11	Concrete Slab Structures	13-13
13.2.12	Steel Structures	13-13
13.2.13	Steel Floor Systems	13-13
13.2.14	Steel Truss Structures	13-13
13.2.15	Timber Structures	13-14
13.2.16	Widened or Rehabilitated Structures	13-14

13.2.17	Buried Structures	13-14
13.2.18	Overloads	13-15
13.2.19	Specialized Hauling Vehicles (SHVs)	13-15
13.3	Load Rating Software	13-17
13.4	Load Rating Reports	13-18
13.5	Structure Posting	13-19
13.6	Appendices	13-20
	Appendix 13.6-A1 LFR Bridge Rating Summary	13-21
	Appendix 13.6-A2 LRFR Bridge Rating Summary	13-22
13.99	References	13-23

Chapter 14 Accelerated and Innovative Bridge Construction

14.1	Introduction	14-1
14.1.1	General	14-1
14.1.2	ABC Methods	14-2
14.2	Application of ABC	14-3
14.2.1	Economics of ABC	14-3
14.2.2	Practical Applications	14-3
14.2.3	Prefabricated Bridge Elements and Systems	14-4
14.2.3.A	Prefabricated Bridge Elements	14-4
14.2.3.B	Prefabricated Systems	14-5
14.2.4	Project Delivery Methods	14-5
14.2.5	Decision Making Tools	14-5
14.3	Structural Systems	14-8
14.3.1	Precast Bent System Design for High Seismic Regions	14-8
14.3.1.A	Description of System	14-9
14.3.1.B	Design Philosophy	14-10
14.3.1.C	Design Provisions	14-10
14.3.1.C.1	Socket-Type Footing Connections	14-10
14.3.1.C.2	Drilled Shaft	14-10
14.3.1.C.3	Precast Column	14-10
14.3.1.D	Geometry and General Requirements	14-11
14.3.2	Geosynthetic Reinforced Soil Integrated Bridge System	14-11
14.3.3	Precast Decks	14-11
14.3.4	Link Slabs	14-11
14.4	Innovative Bridge Construction	14-12
14.4.1	Self-Centering Columns	14-12
14.4.2	Shape Memory Alloy	14-13
14.5	Shipping, Handling and Erection	14-15
14.5.1	Lifting Devices	14-15
14.5.2	Handling, Storage and Shipping	14-15
14.5.3	Tolerances	14-16
14.5.4	Assembly Plans	14-16
14.5.5	Element Sizes	14-17
14.6	Installation Method Options	14-18
14.6.1	Lateral Slide Systems	14-18
14.6.2	Self-Propelled Modular Transporter Systems	14-18
14.7	Examples of Accelerated and Innovative Bridge Construction	14-19

Chapter 15 Structural Design Requirements for Design-Build Contracts

15.1	Manual Description	15-1
15.1.1	Purpose	15-1
15.1.2	Specifications	15-1
15.2	Bridge Configuration Criteria	15-2
15.2.1	General	15-2
15.2.1.A	Structure Conceptual Plan	15-2
15.2.1.B	Bridge Redundancy	15-2
15.2.1.C	Bridge Deck Drainage	15-2
15.2.2	Railroad Crossings	15-2
15.2.2.A	Clearances	15-2
15.2.2.B	Crash Walls	15-2
15.2.2.C	Substructure	15-3
15.2.3	Temporary Bridges	15-3
15.2.4	Inspection and Maintenance Access	15-3
15.2.4.A	General	15-3
15.2.4.B	Bearings	15-3
15.2.4.C	Safety Cables, Handrails, and Anchors	15-3
15.2.4.D	Abutment Slopes	15-3
15.2.4.E	Access and Lighting	15-3
15.2.5	Bridge Types	15-4
15.2.6	Aesthetic Design Elements	15-4
15.2.7	Architectural Design Standards	15-5
15.2.8	Methods	15-5
15.2.9	Design-Builder Urban Design Team	15-5
15.2.10	Analysis and Design Criteria for Structural Widening and Modifications	15-6
15.2.11	Bridge Security	15-6
15.2.11.A	General	15-6
15.2.11.B	Natural Surveillance and Territorial Reinforcement	15-7
15.2.11.C	Hard Armoring	15-7
15.3	Load Criteria	15-8
15.3.1	Scope	15-8
15.3.2	Load Factors and Load Combinations	15-8
15.3.3	Permanent Loads	15-8
15.3.3.A	Future Deck Overlay Requirement	15-8
15.3.4	Live Loads	15-9
15.3.4.A	Design Live Load	15-9
15.3.4.B	Live Load Deflection Evaluation	15-9

15.3.4.C	Distribution to Superstructure	15-9
15.3.4.C.1	Cross sections a, b, c, e, k, and also i and j if sufficiently connected to act as a unit from LRFD-BDS Table 4.6.2.2.1-1	15-9
15.3.4.C.2	Cross section Type d from LRFD-BDS Table 4.6.2.2.1-1	15-10
15.3.4.C.3	Distribution to Substructure	15-10
15.3.4.C.4	Distribution to Crossbeam	15-10
15.3.5	Noise Barrier Walls	15-10
15.4	Seismic Design and Retrofit	15-11
15.4.1	General	15-11
15.4.2	WSDOT Additions and Modifications to AASHTO Guide Specifications for LRFD Seismic Bridge Design	15-11
15.4.2.A	Definitions	15-11
15.4.2.B	Earthquake Resisting Systems (ERS) Requirements for Seismic Design Categories (SDCs) C and D	15-12
15.4.2.C	Seismic Ground Shaking Hazard	15-13
15.4.2.D	Selection of Seismic Design Category (SDC)	15-13
15.4.2.E	Temporary and Staged Construction	15-14
15.4.2.F	Load and Resistance Factors	15-14
15.4.2.G	Balanced Stiffness Requirements and Balanced Frame Geometry Recommendation	15-14
15.4.2.H	Selection of Analysis Procedure to Determine Seismic Demand	15-14
15.4.2.I	Member Ductility Requirement for SDCs C and D	15-14
15.4.2.J	Longitudinal Restrainers	15-14
15.4.2.K	Abutments	15-15
15.4.2.K.1	4.2.11.1 - General	15-15
15.4.2.K.2	4.2.11.2 - Longitudinal Direction	15-15
15.4.2.K.3	4.2.11.2.1 - Abutment Stiffness and Passive Pressure Estimate	15-16
15.4.2.K.4	4.2.11.2.2 - Calculation of Best Estimate Passive Pressure Pp	15-16
15.4.2.K.5	4.2.11.2.3 - Calculation of Passive Soil Stiffness	15-17
15.4.2.K.6	4.2.11.3 - Transverse Direction	15-17
15.4.2.K.7	4.2.11.4 - Curved and Skewed Bridges	15-18
15.4.2.L	Foundation – General	15-18
15.4.2.M	Foundation – Spread Footing	15-18
15.4.2.N	Procedure 3: Nonlinear Time History Method	15-18
15.4.2.O	I_{eff} for Box Girder Superstructure	15-18
15.4.2.P	Foundation Rocking	15-18
15.4.2.Q	Drilled Shafts	15-18
15.4.2.R	Longitudinal Direction Requirements	15-19
15.4.2.S	Liquefaction Design Requirements	15-19
15.4.2.T	Reinforcing Steel	15-19
15.4.2.U	Concrete Modeling	15-19

15.4.2.V	Expected Nominal Moment Capacity	15-19
15.4.2.W	Interlocking Bar Size	15-19
15.4.2.X	Splicing of Longitudinal Reinforcement in Columns Subject to Ductility Demands for SDCs C and D.	15-20
15.4.2.Y	Development Length for Column Bars Extended into Oversized Pile Shafts for SDCs C and D	15-20
15.4.2.Z	Lateral Confinement for Oversized Pile Shaft for SDCs C and D	15-20
15.4.2.AA	Lateral Confinement for Non-Oversized Strengthened Pile Shaft for SDCs C and D.	15-20
15.4.2.AB	Requirements for Capacity Protected Members	15-20
15.4.2.AC	Superstructure Capacity Design for Transverse Direction (Integral Bent Cap) for SDCs C and D	15-21
15.4.2.AD	Superstructure Design for Non Integral Bent Caps for SDCs B, C, and D.	15-21
15.4.2.AE	Integral Bent Cap Joint Shear Design.	15-21
15.4.2.AF	Cast-in-Place and Precast Concrete Piles	15-21
15.4.2.AG	Seismic Resiliency using Innovative Materials and Construction	15-21
15.4.3	Seismic Design Requirements for Bridge Modifications and Widening Projects . . .	15-22
15.4.3.A	Seismic Analysis and Retrofit Policy	15-22
15.4.3.B	Design and Detailing Considerations	15-22
15.4.3.B.1	Support Length	15-22
15.4.3.B.2	Connections Between Existing and New Elements	15-22
15.4.3.B.3	Differential Settlement	15-22
15.4.3.B.4	Foundation Types	15-23
15.4.3.B.5	Existing Strutted Columns	15-23
15.4.3.B.6	Non Structural Element Stiffness	15-23
15.4.3.B.7	Isolation Bearings	15-23
15.4.4	Seismic Retrofitting of Existing Bridges	15-23
15.4.4.A	Seismic Analysis Requirements	15-24
15.4.4.B	Seismic Retrofit Design.	15-24
15.4.4.C	Earthquake Restrainers.	15-24
15.4.4.D	Isolation Bearings	15-24
15.5	Concrete Structures	15-25
15.5.1	General	15-25
15.5.2	Materials	15-25
15.5.2.A	Concrete	15-25
15.5.2.A.1	Cast-in-place (CIP) Concrete	15-25
15.5.2.A.2	Modulus of Elasticity.	15-25
15.5.2.A.3	Shrinkage and Creep	15-25
15.5.2.A.4	Grout.	15-25
15.5.2.A.5	Mass Concrete	15-26
15.5.2.A.6	Shotcrete	15-26
15.5.2.A.7	Lightweight Aggregate Concrete.	15-26

15.5.2.B	Reinforcing Steel	15-26
15.5.2.B.1	Grades	15-26
15.5.2.B.2	Compressive Development Length.	15-26
15.5.2.B.3	Splices	15-26
15.5.2.B.4	Welded Wire Reinforcement in Prestressed Concrete Girders,Walls, Barriers and Deck Panels	15-27
15.5.2.B.5	Reinforcing Bar Dowels and Resin Bonded Anchors . . .	15-27
15.5.2.C	Prestressing Steel	15-27
15.5.2.D	Post-Tensioning Systems	15-27
15.5.3	Design Considerations	15-28
15.5.3.A	Service and Fatigue Limit States.	15-28
15.5.3.B	Strength Limit State.	15-28
15.5.3.C	Post-Tensioning.	15-28
15.5.4	Superstructures.	15-28
15.5.4.A	Reinforced Concrete Superstructures.	15-28
15.5.4.B	Box Girder Superstructures.	15-28
15.5.4.B.1	Intermediate Diaphragms for Curved Concrete Box Girder Bridges.	15-28
15.5.4.B.2	Temperature Effects	15-29
15.5.4.B.3	Drains	15-29
15.5.4.C	Prestressed Concrete Girder Superstructures	15-29
15.5.4.C.1	WSDOT Standard Girder Types and Construction Sequences	15-29
15.5.4.C.2	Superstructure Continuity	15-29
15.5.4.C.3	Continuous Structure Configuration	15-29
15.5.4.C.4	Girder Ends.	15-29
15.5.4.C.5	Diaphragms	15-30
15.5.4.C.6	Barrier and Sidewalk Load Distribution.	15-30
15.5.4.C.7	Composite Action	15-30
15.5.4.C.8	Dead Loads	15-30
15.5.4.C.9	Girder Stirrups	15-30
15.5.4.C.10	Transformed Section Properties	15-30
15.5.4.C.11	Deck Shrinkage	15-31
15.5.4.C.12	Deck Girder Superstructures	15-31
15.5.4.C.13	Slab Girders	15-31
15.5.4.C.14	Deck Bulb-Tee Girders	15-31
15.5.4.C.15	Wide Flange Deck Girders	15-31
15.5.4.C.16	Wide Flange Thin Deck Girders	15-31
15.5.4.C.17	Tub Girders.	15-31
15.5.4.C.18	Spliced Prestressed Concrete Girders	15-32
15.5.5	Concrete Bridge Decks.	15-32
15.5.5.A	Bridge Deck Requirements	15-32
15.5.5.B	Bridge Deck Reinforcement	15-32
15.5.5.C	Stay-in-Place (SIP) Deck Panels.	15-33
15.5.5.D	Bridge Deck Protection	15-33
15.5.5.E	Bridge Deck HMA Paving	15-33

15.6	Steel Structures	15-34
15.6.1	Design Considerations	15-34
15.6.1.A	Codes, Specification, and Standards	15-34
15.6.1.B	WSDOT Steel Bridge Practice	15-34
15.6.1.C	Preliminary Girder Proportioning	15-34
15.6.1.D	Bridge Steels	15-35
15.6.1.E	Plate Sizes	15-35
15.6.1.F	Fasteners	15-35
15.6.2	Girder Bridges	15-35
15.6.2.A	Tub or Box Girders	15-35
15.6.2.B	Fracture Critical Superstructures	15-36
15.6.3	Design of I-Girders	15-36
15.6.3.A	Limit States for LRFD-BDS	15-36
15.6.3.B	Composite Section	15-37
15.6.3.C	Flanges	15-37
15.6.3.D	Webs	15-37
15.6.3.E	Transverse Stiffeners	15-37
15.6.3.F	Longitudinal Stiffeners	15-38
15.6.3.G	Bearing Stiffeners	15-38
15.6.3.H	Cross Frames	15-38
15.6.3.I	Bottom Laterals	15-38
15.6.3.J	Bolted Field Splice for Girders	15-38
15.6.3.K	Camber	15-39
15.6.3.L	Bridge Deck Placement Sequence	15-40
15.6.3.M	Bridge Bearings for Steel Girders	15-40
15.6.3.N	Surface Roughness and Hardness	15-40
15.6.3.O	Welding	15-40
15.6.3.P	Shop Assembly	15-40
15.6.4	Plan Details	15-41
15.6.4.A	General	15-41
15.6.4.B	Framing Plan	15-41
15.6.4.C	Girder Elevation	15-41
15.6.4.D	Typical Girder Details	15-41
15.6.4.E	Cross Frame Details	15-42
15.6.4.F	Camber Diagram and Bearing Stiffener Rotation	15-42
15.6.4.G	Bridge Deck	15-42
15.6.4.H	Handrail Details, Inspection Lighting, and Access	15-43
15.6.4.I	Box Girder Details	15-43
15.6.5	Painting of Existing Steel Bridges	15-43
15.6.6	Corrosion of Steel Foundations and Buired Structures	15-43

15.7	Substructure Design	15-44
15.7.1	General Substructure Considerations	15-44
15.7.1.A	Foundation Seals	15-44
15.7.1.B	Scour	15-44
15.7.1.C	Combination of Extreme Event Effects	15-44
15.7.1.C.1	Downdrag	15-44
15.7.1.C.2	Lateral Ground Displacement	15-44
15.7.1.C.3	Scour	15-44
15.7.2	Foundation Modeling for Seismic Loads	15-44
15.7.2.A	General	15-44
15.7.2.B	Bridge Model Section Properties	15-44
15.7.2.B.1	Cracked Properties for Columns	15-44
15.7.2.B.2	Shaft Properties	15-45
15.7.2.B.3	Cast-in-Place Pile Properties	15-45
15.7.2.C	Spread Footing Modeling Methods	15-45
15.7.2.D	Deep Foundation Modeling Methods	15-45
15.7.2.D.1	Group Effects	15-45
15.7.2.D.2	Shaft Caps and Pile Footings	15-45
15.7.2.E	Design of Deep Foundations for Lateral Forces	15-46
15.7.2.E.1	Determination of Tip Elevations	15-46
15.7.2.E.2	Design for Lateral Loads	15-46
15.7.3	Column Design	15-46
15.7.3.A	Shear Design	15-46
15.7.3.B	Column Silos	15-46
15.7.3.C	Longitudinal Reinforcement	15-46
15.7.3.D	Longitudinal Reinforcement Splices	15-46
15.7.3.E	Longitudinal Reinforcement Development	15-47
15.7.3.E.1	Crossbeams	15-47
15.7.3.E.2	Footings	15-47
15.7.3.E.3	Drilled Shafts	15-47
15.7.3.F	Transverse Reinforcement	15-47
15.7.3.F.1	General	15-47
15.7.3.F.2	Spiral Splices and Hoops	15-47
15.7.3.G	Reduced Column Section	15-48
15.7.4	Crossbeam	15-48
15.7.5	Abutment Design and Details	15-48
15.7.5.A	General	15-48
15.7.5.A.1	Bent-Type and Isolated Abutments	15-48
15.7.5.A.2	Abutments on Structural Earth (SE) Walls and Geosynthetic Walls	15-48

15.7.5.B	Embankment and Backfill	15-48
15.7.5.B.1	General Clearances	15-48
15.7.5.B.2	Abutments on SE Walls and Geosynthetic Walls	15-48
15.7.5.B.3	Drainage and Backfill	15-49
15.7.5.C	Abutment Loading	15-49
15.7.5.C.1	Earthquake Load	15-49
15.7.5.C.2	Bearing Forces	15-49
15.7.5.D	Abutment Details	15-49
15.7.5.D.1	Bearing Seats	15-49
15.7.5.D.2	Transverse Girder Stops	15-49
15.7.5.D.3	Abutment Walls	15-49
15.7.6	Abutment Wing Walls and Curtain Walls	15-50
15.7.7	Footing Design	15-50
15.7.7.A	General Footing Criteria	15-50
15.7.7.B	Spread Footing Design	15-50
15.7.7.B.1	Foundation Design	15-50
15.7.7.B.2	Structural Design	15-50
15.7.7.C	Pile-Supported Footing Design	15-50
15.7.7.C.1	Pile Embedment, Clearance, and Rebar Mat Location.	15-50
15.7.7.C.2	Concrete Design	15-51
15.7.8	Shafts	15-51
15.7.8.A	Axial Resistance	15-51
15.7.8.B	Structural Design and Detailing	15-51
15.7.9	Piles and Piling	15-52
15.7.9.A	Pile Types	15-52
15.7.9.B	Pile Groups	15-53
15.7.9.C	Battered Piles	15-53
15.7.9.D	Structural Design and Detailing of CIP Concrete Piles	15-53
15.7.9.E	Structural Steel Pipe Piles	15-53
15.7.9.F	Pile Resistance	15-53
15.7.10	Concrete-Filled Steel Tubes	15-53
15.7.10.A	Design Requirements	15-53
15.8	Walls and Buried Structures	15-54
15.8.1	Retaining Walls	15-54
15.8.1.A	General	15-54
15.8.1.B	Loads	15-54
15.8.1.C	Design of Reinforced Concrete Retaining Walls	15-54
15.8.1.D	Design of Cantilever Soldier Pile and Soldier Pile Tieback Walls	15-54
15.8.1.D.1	Ground Anchors (Tiebacks)	15-54
15.8.1.D.2	Design of Soldier Pile	15-54
15.8.1.D.3	Design of Lagging	15-54
15.8.1.D.4	Design of Fascia Panels	15-54

15.8.1.E	Design of Structural Earth Walls	15-54
15.8.1.E.1	Pre-approved Proprietary Structural Earth Walls	15-54
15.8.1.F	Design of Standard Plan Geosynthetic Walls	15-54
15.8.1.G	Design of Soil Nail Walls	15-54
15.8.1.H	Scour of Retaining Walls	15-54
15.8.1.I	Miscellaneous Items	15-54
15.8.2	Noise Barrier Walls	15-55
15.8.2.A	General	15-55
15.8.2.B	Loads.	15-55
15.8.2.C	Design	15-55
15.8.2.C.1	Standard Plan Noise Barrier Walls	15-55
15.8.2.C.2	Non-Standard Noise Barrier Walls	15-55
15.8.3	Buried Structures	15-55
15.8.3.A	General Policy.	15-55
15.8.3.B	General Design Requirements	15-55
15.8.3.C	Application of Loads	15-55
15.8.3.D	Scour.	15-56
15.8.3.E	Corrosion.	15-56
15.8.3.F	Worker, Pedestrian and Bicycle Fall Protection	15-56
15.8.3.G	W-Beam Guardrail on Buried Structures (TL-3)	15-56
15.8.3.H	Deflection	15-56
15.8.3.I	Control of Cracking	15-56
15.8.3.J	Joints.	15-56
15.8.3.K	Deck Protection and Approach Slabs	15-56
15.8.3.L	Metal Structural Plate Structures.	15-57
15.8.3.M	Design of Detention Vaults	15-57
15.8.3.N	Design of Tunnels	15-57
15.9	Bearings and Expansion Joints	15-58
15.9.1	Expansion Joints.	15-58
15.9.1.A	General Considerations.	15-58
15.9.1.A.1	Concrete Bridges	15-58
15.9.1.A.2	Steel Bridges	15-58
15.9.1.B	General Design Criteria.	15-58
15.9.1.B.1	Shrinkage Effects	15-59
15.9.1.B.2	Thermal Effects.	15-59
15.9.1.C	Small Movement Range Joints	15-60
15.9.1.C.1	Compression Seals.	15-60
15.9.1.C.2	Rapid-Cure Silicone Sealants	15-60
15.9.1.C.3	Asphaltic Plug Joints	15-60
15.9.1.C.4	Headers	15-60

15.9.1.D	Medium Movement Range Joints	15-61
15.9.1.D.1	Steel Sliding Plate Joints	15-61
15.9.1.D.2	Strip Seal Joints	15-61
15.9.1.D.3	Bolt-down Panel Joints	15-61
15.9.1.E	Large Movement Range Joints	15-61
15.9.1.E.1	Steel Finger Joints	15-61
15.9.1.E.2	Modular Expansion Joints	15-62
15.9.2	Bearings	15-63
15.9.2.A	General Considerations	15-63
15.9.2.B	Force Considerations	15-63
15.9.2.C	Movement Considerations	15-63
15.9.2.C.1	Elastomeric and Fabric Pad Bearings	15-63
15.9.2.C.2	HLMR Bearings	15-63
15.9.2.D	Detailing Considerations	15-64
15.9.2.E	Bearing Types	15-64
15.9.2.E.1	Elastomeric Bearings	15-64
15.9.2.E.2	Fabric Pad Sliding Bearings	15-65
15.9.2.E.3	Pin Bearings	15-66
15.9.2.E.4	Rocker and Roller Type Bearings	15-66
15.9.2.E.5	Spherical Bearings	15-66
15.9.2.E.6	Disc Bearings	15-66
15.9.2.E.7	Seismic Isolation Bearings	15-66
15.9.2.F	Miscellaneous Details	15-66
15.9.2.F.1	Temporary Support before Grouting Masonry Plate	15-66
15.9.2.F.2	Anchor Bolts	15-67
15.9.2.G	Contract Drawing Representation	15-67
15.9.2.H	Shop Drawing Review	15-67
15.9.2.I	Bearing Replacement Considerations	15-67
15.10	Signs, Barriers, Bridge Approach Slabs, and Utilities	15-68
15.10.1	Sign and Luminaire Supports	15-68
15.10.2	Bridge Traffic Barriers	15-68
15.10.2.A	General Guidelines and Policy	15-68
15.10.3	At Grade Concrete Barriers	15-68
15.10.3.A	Traffic Barrier Moment Slab Design Criteria	15-68
15.10.3.A.1	Structural Capacity	15-68
15.10.3.A.2	Global Stability	15-68
15.10.3.A.3	Geometry	15-68
15.10.3.A.4	Soil Reinforcement	15-68
15.10.3.A.5	Wall Panel	15-69
15.10.3.B	Precast Concrete Barrier	15-69

15.10.4	Bridge Traffic Barrier Rehabilitation	15-69
15.10.4.A	General Guidelines and Policy	15-69
15.10.4.A.1	Design Criteria	15-69
15.10.5	Bridge Railing	15-70
15.10.5.A	General Guidelines and Policy	15-70
15.10.6	Bridge Approach Slabs	15-70
15.10.6.A	Bridge Approach Slab Design Criteria.	15-70
15.10.6.B	Bridge Approach Slab Detailing.	15-71
15.10.6.C	Skewed Bridge Approach Slabs	15-71
15.10.6.D	Approach Anchors and Expansion Joints	15-71
15.10.6.E	Bridge Approach Slab Addition or Retrofit to Existing Bridges	15-71
15.10.6.F	Bridge Approach Slab Staging	15-72
15.10.7	Traffic Barrier on Bridge Approach Slabs	15-72
15.10.7.A	Bridge Approach Slab over Wing Walls, Cantilever Walls or Geosynthetic Walls	15-72
15.10.7.B	Bridge Approach Slab over SE Walls	15-72
15.10.8	Utilities Installation on New and Existing Structures.	15-72
15.10.8.A	General Concepts	15-72
15.10.8.A.1	Coating and Corrosion Protection.	15-72
15.10.8.B	Utility Design Criteria.	15-73
15.10.8.B.1	Utility Location	15-73
15.10.8.B.2	Termination at the Bridge Ends.	15-73
15.10.8.B.3	Utility Expansion	15-73
15.10.8.B.4	Utility Blockouts	15-73
15.10.8.B.5	Gas Lines or Volatile Fluids	15-73
15.10.8.B.6	Water Lines.	15-73
15.10.8.B.7	Sewer Lines	15-74
15.10.8.B.8	Electrical (Power and Communications).	15-74
15.10.8.C	Box/Tub Girder Bridges.	15-74
15.10.8.D	Traffic Barrier Conduit	15-74
15.10.8.E	Conduit Types	15-75
15.10.8.F	Utility Supports	15-75
15.10.8.F.1	Pipe Hangers	15-75
15.10.8.F.2	Surface Mounting	15-75
15.10.9	Review Procedure for Utility Installations on Existing Structures	15-75
15.10.10	Anchors for Permanent Attachments	15-76
15.10.11	Drainage Design	15-76
15.10.11.A	Geometrics	15-76
15.10.11.B	Hydrology	15-76
15.10.11.C	On Bridge Systems	15-76

15.11	Detailing Practices	15-77
15.11.1	Standard Practices	15-77
15.11.1.A	Drawing Orientation and Layout Control	15-77
15.11.1.B	Lettering	15-77
15.11.1.B.1	General	15-77
15.11.1.B.2	Dimensioning	15-77
15.11.1.C	Line Work	15-78
15.11.1.D	Scale	15-78
15.11.1.E	Graphic Symbols	15-78
15.11.1.F	Structural Sections, Views and Details	15-78
15.11.1.G	Miscellaneous	15-79
15.11.1.H	RFC Revisions	15-79
15.11.1.I	Title Block	15-79
15.11.1.J	Reinforcement Detailing	15-80
15.11.2	Bridge Office Standard Drawings and Office Examples	15-81
15.11.2.A	General	15-81
15.11.2.B	Use of Standards	15-81
15.11.3	Plan Sheets	15-81
15.11.3.A	Layout	15-81
15.11.3.B	General Notes/Construction Sequence	15-82
15.11.3.C	Footing Layout	15-82
15.11.3.D	Piles/Shfts	15-82
15.11.3.E	Abutment	15-82
15.11.3.F	Intermediate Piers/Bents	15-83
15.11.3.G	Bearing Details	15-83
15.11.3.H	Framing Plan	15-83
15.11.3.I	Typical Section	15-83
15.11.3.J	Girders/Diaphragms	15-83
15.11.3.K	Bridge Deck Reinforcement	15-83
15.11.3.L	Expansion Joints	15-83
15.11.3.M	Traffic Barrier	15-83
15.11.3.N	Bridge Approach Slab	15-83
15.11.3.O	Barlist	15-84
15.11.4	Structural Steel	15-84
15.11.4.A	General	15-84
15.11.4.B	Bars	15-84
15.11.4.C	Plates	15-84
15.11.4.D	Strips	15-84
15.11.4.E	Labeling	15-84
15.11.5	Aluminum Section Designations	15-85
15.11.6	Abbreviations	15-85

15.12 Bridge Load Rating 15-86

 15.12.1 General 15-86

 15.12.2 Load Rating Software 15-86

15.13 Appendices 15-87

 Appendix 15.2-A1 Conceptual Plan Checklist 15-88

15.99 References 15-89