



## Specifications

- Structure: (2) piece structure that is assembled on the job site with elastomeric roof coating over the seam
- Exterior Dimensions: 26'-6" Long x 22'-6" Wide x 10'-11" High with a 2" overhang at the top of the structure on all 4 walls. The roof is peaked for runoff.
- Interior (Finished Out) Dimensions: 25'-8" Long x 21'-8" Wide x 9'-1" High
- Design Loads: Roof Load: 65 psf; Floor Live Load: 250 psf; Wind Load: 110 MPH, Exp "C"; Seismic: Zone 4
- Insulation: R11 Roof, R11 Walls, R4 Floor
- Approximate Structure Weight of 149,000 lbs; each piece weighs 74,500 pounds

## Equipment List

- Finish: Exterior - Chamfered Painted Surface (Tan color); Interior - Insulation and white FRP with trim and cove; Floor - Standard VCT tile
- Door: 3070 18 ga door with 16 ga frame; door drip cap – 2 1/2" wide; lockset with changeable core
- Power - 200A, 1Ø, 120/240V
  - 200 A Exterior Disconnect Switch
  - 200A, 1Ø, 30 space Distribution Panel
  - 45K Peak Amp Surge Suppressor
  - (4) interior duplex receptacles, (1) exterior GFI receptacle
- HVAC: (2) 5 Ton, 1Ø HVAC units with 5Kw Heat Strip, no Economizer; Lead Lag Controller
- Controls: Telephone board and alarm block with intrusion, smoke, power failure, HVAC fail, and high/low temperature
- Lights: (12) interior fluorescent lights; Emergency exit fixture with dual flood lights; Exterior light with photocell and motion detector
- Other: (2) Smoke detectors; Fire extinguisher (10 lb CO2); Literature Holder; Tie Down Kit

## Optional Equipment

- Roof: Duralast Roof Membrane
- Door: 8"x48" Door Canopy for 3'-0"x7'-0" Door; Upgrade to 4'-0"x7'-0" door; Upgrade to 6'-0"x7'-0" door
- Power: 200A Generator Receptacle with 200A/2P Manual Transfer Switch; Upgrade to 200K peak amp Surge Suppressor, modular with partial failure alarm; Group(s) of (5) Twistlock Receptacles
- HVAC Upgrade: (2) 5 Ton HVAC with Economizer
- Cable Ladder: 20, 40, or 60 feet of 18 inch tubular cable ladder
- Grounding: Halo Grounding Terminating in (1) 1/4"x4"x20" Ground Bar
- Safety: First Aid Kit, Eye Wash Station, Battery Safety Kit



**Oldcastle** Precast®, Inc.

300 East Pecos Road (P.O. Box 3250)  
Chandler, AZ 85244  
Phone: 480-222-6200  
Fax: 480-222-6210  
rick.soltes@oldcastleprecast.com

## Precast Concrete Equipment Shelter Model 2327-S

Copyright: © 2005 **Oldcastle** Precast®, Inc.



**Oldcastle** Precast®, Inc.

27 Amlajack Road  
Newnan, GA 30265  
Phone: 770-251-8777  
Fax: 770-304-4640  
bob.entriken@oldcastleprecast.com