



## **NOTES**

- 1. Coat the pipe threads with asphalt after assembly.
- 2. All piping shall be galvanized steel.
- 3. Valve and piping to valve shall be 2" unless otherwise noted in the Contract.
- 4. Locate blowoff outlet near property corner if possible.



## **2 INCH BLOWOFF ASSEMBLY STANDARD PLAN B-90.20-00**

SHEET 1 OF 1 SHEET

APPROVED FOR PUBLICATION



