



SR 520 Bridge Replacement and HOV Program

Medina to SR 202: Eastside Transit and HOV Project

Night work begins again for N.E. Points Drive retaining wall

Nighttime truck haul starts November 19, runs through the end of 2012

Starting Monday, Nov. 19, crews start building a 1,500-foot-long retaining wall along the south side of Northeast Points Drive that will require them to haul in fill dirt at night. Crews will be working day and night shifts to complete this work as quickly as possible.

When will work take place?

- Daytime – 7 a.m. to 3 p.m., Monday through Friday
- Nighttime – 7 p.m. to 5 a.m., Monday through Thursday

How will I be affected?

- Construction noise – Nearby residents may hear back-up alarms, trucks, bulldozers, rollers and generators.
- Truck traffic – Up to seven trucks per hour will travel westward from Bellevue Way Northeast, unload fill dirt along the south side of Northeast Points Drive, then continue along a construction haul road to 92nd Avenue Northeast.

How will the wall be built?

During day shifts, crews will place dozens of concrete wall panels to form the retaining wall. At night, crews will unload the fill dirt and compact it with bulldozers and rollers. The retaining wall is scheduled to be complete by the end of 2012.

24-hour construction hotline

A 24-hour construction hotline is available for residents who wish to speak with a project representative at any time of the day or night.

- Call 425-998-5200

For more information or for questions and comments:

- Call the Construction Hotline: 425-998-5200
- E-mail Dan Galvin: dan.galvin@gcinc.com

Visit our website to learn more about the project and to sign up for e-mail updates

Please visit our construction update Web page to find out when work will happen near you

- www.wsdot.wa.gov/Projects/SR520Bridge/MedinaTo202

- www.wsdot.wa.gov/Projects/SR520Bridge/MedinaTo202/MedinatoSR202Construction



Conceptual rendering of the Northeast Points Drive wall



Note: This illustration represents the conceptual design, shared in 2010. The final wall will have a stamped concrete finish called Cascadian Stone (see inset). A 6- to 12-foot noise wall will be built between the regional bicycle/pedestrian path and the highway mainline.

Northeast Points Drive wall construction map



www.wsdot.wa.gov/projects/SR520Bridge/Medinato202

ADA Statement: Materials can be provided in alternative formats: large print, Braille, cassette tape, or on computer disk for people with disabilities by calling the Office of Equal Opportunity (OEO) at 360-705-7097. Persons who are deaf or hard of hearing may contact OEO through the Washington Relay Service at 7-1-1.

Title VI Information: WSDOT ensures full compliance with Title VI of the Civil Rights Act of 1964 by prohibiting discrimination against any person on the basis of race, color, national origin or sex in the provision of benefits and services resulting from its federally assisted programs and activities. For questions regarding WSDOT's Title VI Program, you may contact the Department's Title VI Coordinator at 360-705-7089.