Aviation Stormwater Design Manual:

Managing Wildlife Hazards Near Airports

M ##-##

October 2008

Environmental and Engineering Service Center

Persons with disabilities may request this information be prepared and supplied in alternate formats by calling the Washington State Department of Transportation Americans with Disabilities Act (ADA) Accommodation Hotline collect 206-389-2839. Persons with hearing impairments may access the Washington State Telecommunications Relay Service (TTY) at 1-800-833-6388, or Tele-Braille at 1-800-833-6385, or Voice at 1-800-833-6384, and ask to be connected to 360-705-7097.

The following statement is provided as required by Paragraph 429.a of Federal Aviation Administration (FAA) Order 5100.38, Airport Improvement Program (AIP) Handbook:

The preparation of this document was financed in part through a planning grant (AIP 3-53-0000-05) from the FAA as provided under Section 505 of the Airport and Airway Improvement Act of 1982. The contents do not necessarily reflect the official views or policy of the FAA. Acceptance of this report by the FAA does not in any way constitute a commitment on the part of the United States to participate in any development depicted therein; nor does it indicate that the proposed development is environmentally acceptable in accordance with appropriate public laws. In addition, this report was also partially funded by grants from Washington State. The report was developed through a joint effort with the Washington State Department of Transportation (WSDOT) Aviation Division and Environmental Services Office.

Note:

Some pages in this document have been intentionally skipped or blank pages inserted to ensure correct pagination and printing.

Table of Contents

Acknowledgements xiii

Executive Summary xv

Chapter 1. Introduction 1-1

1-1. Purpose of This Manual 1-1

1-2. How to Use This Manual 1-1

1-3. Basis for Manual Development 1-3

1-3.1. Scope of Manual 1-3

1-3.2. Airport Regulatory Issues 1-4

1-3.3. Overview of Federal and State Regulations Related to Stormwater Management at Airports 1-4

Federal Aviation Regulations 1-5

Clean Water Act, Section 404 Permits: Permit for Discharge of Dredge or Fill Material 1-5

Clean Water Act, Section 401 Water Quality Certifications 1-5

Clean Water Act, Section 402: National Pollutant Discharge Elimination System Permit 1-6

Endangered Species Act 1-6

Bald and Golden Eagle Protection Act 1-7

Washington Growth Management Act 1-7

Underground Injection Control Regulation 1-7

Sole Source Aquifer 1-8

1-3.4. Relationship of this Manual to Other Stormwater Programs 1-9

Minimum Requirements/Core Elements 1-9

Other Manuals and Permit Documents 1-10

Chapter 2. Airport Operations and Stormwater 2-13

2-1. Airport Operation Zones and Restrictions 2-13

2-1.1. Description of Airport Operation Zones and Guidelines 2-13

Restrictions on Off-Airport Land 2-14

Airspace Restrictions 2-14

2-1.2. Stormwater Facility Restrictions 2-15

2-2. General Airport Stormwater Considerations 2-19

2-2.1. Safety and Emergency Access 2-19

2-2.2. Maintenance 2-19

2-2.3. Target Pollutants 2-19

2-2.4. Community Planning 2-19

Chapter 3. Stormwater and Wildlife Planning 3-1

Draft

3-1. Identifying and Monitoring Species of Concern 3-1
3-1.1. Wildlife Monitoring 3-2
3-1.2. Wildlife of Concern 3-3
Waterfowl 3-3
Raptors 3-4
Doves and Pigeons 3-4
Cranes 3-5
Herons 3-5
Shorebirds 3-5
Crows/Ravens 3-6
Other Small Birds 3-6
Deer 3-6
Coyotes 3-6
3-2. Site Planning and Layout Considerations 3-7
3-2.1. Existing Habitat 3-7
3-2.2. Low Impact Development 3-7
3-2.3. Urban Encroachment 3-8
3-3. General BMP Design Considerations 3-8
3-3.1. Vegetation Considerations 3-9
3-3.2. Structural Considerations 3-10
3-3.3. Adaptive Management at Airports 3-11
3-4. Adaptive Stormwater Facility Design 3-11
3-4.1. Customizing the Design of Stormwater BMPs for Specific Species of Concern 3-11
3-4.2. Adaptive Management of Open Water Areas 3-12
Habitat Suitability Reduction 3-13
Open Water Covers 3-15
Open Water Access Control 3-17
Chapter 4. Best Management Practice (BMP) Selection Process 4-21
4-1. Flow Control Requirements 4-21
4-2. Treatment Targets 4-21
4-3. Source Control BMPs 4-22
4-4. Selection Process for Flow Control BMPs 4-22
4-4.1. Step 1: Determine if Site Conditions are Appropriate for Dispersion and/or Infiltration 4-25
4-4.2. Step 1A: Select Infiltration/Dispersion BMP 4-25
4-4.3. Step 2: Identify Regional Facility 4-26
4-4.4. Step 2A: Determine Feasibility of Regional Facility 4-26
4-4.5. Step 3: Determine Feasibility of Detention Pond 4-26
4-4.6. Step 4A: Determine Feasibility of Detention Vault or Tank 4-27
4-4.7. Step 4B: Emerging Technologies 4-27

Draft

4-4.8. Step 4C: Consider Demonstrative Approach 4-27
4-4.9. Step 5: Implement Selected Flow Control BMPs 4-28
4-5. Selection Process for Runoff Treatment BMPs 4-28
4-5.1. Step 1: Flow Control Result 4-28
4-5.2. Step 1A: Dispersion BMPs 4-31
4-5.3. Step 1B: Select Pretreatment BMPs 4-31
4-5.4. Step 1C: Infiltration BMPs 4-31
4-5.5. Step 2: Receiving Waters 4-31
4-5.6. Step 3: Determine Whether Oil Control is Needed 4-31
4-5.7. Step 3A: Oil Control BMPs 4-32
4-5.8. Step 4: Determine Whether Phosphorus Control is Needed 4-32
4-5.9. Step 4A: Phosphorus Control BMPs 4-32
4-5.10. Step 5: Determine Whether Enhanced Treatment is Needed 4-32
4-5.11. Step 5A: Enhanced Treatment BMPs 4-33
4-5.12. Step 6: Basic Treatment BMPs 4-33
4-5.13. Step 7: Underground Facilities 4-34
4-5.14. Step 8: Emerging Technologies 4-34
4-5.15. Step 9: Consider Demonstrative Approach 4-34
4-5.16. Step 10: Implement Selected Runoff Treatment BMPs 4-35
Chapter 5. Hydrologic Considerations for Airports 5-1
5-1. Airport-specific Hydrologic Design Considerations 5-1
5-2. Methods of Analysis 5-2
5-2.1. Western Washington 5-3
Runoff Treatment and Flow Control BMPs Other Than Wet Pool Treatment Facilities 5-3
Wet Pool Facilities 5-3
5-2.2. Eastern Washington 5-4
Runoff Treatment Facilities 5-4
Flow Control Facilities 5-4
Eastern Washington Design Storm Events 5-4
5-3. Infiltration Design Guidance 5-5
5-3.1. Site Suitability Criteria (SSC) 5-6
SSC 1 – Setback Requirements 5-6
SSC 2 – Groundwater Protection Areas 5-7
SSC 3 – High Vehicle Traffic Areas 5-7
SSC 4 – Soil Infiltration Rate 5-8
SSC 5 – Depth to Bedrock, Water Table, or Impermeable Layer 5-9
SSC 6 – Soil Physical and Chemical Suitability for Treatment 5-9
SSC 7 – Seepage Analysis and Control 5-10
SSC 8 – Cold Climate and Impact of Deicers 5-10

Draft

SSC 9 – Verification Testing of the Completed Facility 5-10
5-3.2. Simplified Approach to Determining Infiltration Rates (Western Washington) 5-11
5-3.3. Detailed Approach to Determining Infiltration Rates (Western Washington) 5-11
5-3.4. Design Infiltration Rate Determination (Eastern Washington)..... 5-21
5-4. General BMP Design Guidelines..... 5-22
5-4.1. Infiltration Facilities..... 5-22
Design Criteria – Sizing Facilities (Western Washington)..... 5-22
Additional Design Criteria 5-23
Design Criteria – Sizing Facilities (Eastern Washington) 5-23
Construction Criteria..... 5-26
Maintenance Criteria..... 5-26
Verification of Performance 5-26
5-4.2. Design of Compost-Amended Vegetated Filter Strips 5-27
Determining Infiltration Rates for Soil Amendment BMPs 5-27
Design Procedure for Compost-Amended Vegetated Filter Strips (CAVFS) for Western Washington..... 5-29
5-4.3. Design Procedures for Volume-Based Runoff Treatment BMPs 5-31
Chapter 6. Stormwater BMP Design, Operations and Maintenance..... 6-1
6-1. BMPs for Stormwater Source Control..... 6-1
6-2. BMP Design Criteria 6-1
6-2.1. AR.01 – Natural Dispersion..... 6-3
Introduction..... 6-3
Site Design Elements 6-5
6-2.2. AR.02 – Engineered Dispersion..... 6-13
Introduction..... 6-13
Design Flow Elements 6-14
Structural Design Considerations 6-15
Site Design Elements 6-15
6-2.3. AR.03 – Bioinfiltration Pond (Eastern Washington Only) 6-23
Introduction..... 6-23
Design Flow Elements 6-26
Structural Design Considerations 6-26
Site Design Elements 6-27
Site Design Elements 6-27
6-2.4. AR.04 – Infiltration Pond..... 6-31
Introduction..... 6-31
Design Flow Elements 6-33
Structural Design Considerations 6-35
Groundwater Issues..... 6-35
Runoff Treatment..... 6-36

Draft

Site Design Elements 6-36
6-2.5. AR.05 – Infiltration Trench 6-41
Introduction 6-42
Design Flow Elements 6-42
Structural Design Considerations 6-48
Groundwater Issues 6-49
Site Design Elements 6-49
6-2.6. AR.06 – Infiltration Vault 6-53
Introduction 6-53
Design Flow Elements 6-54
Structural Design Considerations 6-55
Groundwater Issues 6-57
6-2.7. AR.07 – Drywell 6-59
Introduction 6-59
Design Flow Elements 6-60
Structural Design Considerations 6-61
Groundwater Issues 6-61
Site Design Elements 6-62
6-2.8. AR.08 – Permeable Pavement Surfaces 6-63
Introduction 6-64
General Design Criteria 6-67
Design Flow Elements 6-68
Facility Design Considerations 6-70
6-2.9. AR.09 – Detention Pond 6-77
Introduction 6-77
Design Flow Elements 6-80
Structural Design Considerations 6-86
Groundwater Issues 6-90
Site Design Elements 6-90
6-2.10. AR.10 – Detention Vault 6-93
Introduction 6-93
Design Flow Elements 6-95
Structural Design Considerations 6-96
Groundwater Issues 6-96
Site Design Elements 6-97
6-2.11. AR.11 – Detention Tank 6-99
Introduction 6-99
Design Flow Elements 6-99
Structural Design Considerations 6-101
Groundwater Issues 6-103
Site Design Elements 6-103
6-2.12. AR.12 – Vegetated Filter Strip 6-105
Introduction 6-105

Draft

Design Flow Elements 6-110
Structural Design Considerations 6-110
6-2.13. AR.13 – Biofiltration Swale 6-119
Introduction 6-119
Design Flow Elements 6-122
Structural Design Considerations 6-122
Site Design Elements 6-134
6-2.14. AR.14 – Media Filter Drain (previously referred to as the Ecology Embankment) 6-137
Introduction 6-137
Design Flow Elements 6-147
Structural Design Considerations 6-147
Site Design Elements 6-152
6-2.15. AR.15 – Linear Sand Filter 6-153
Introduction 6-153
Design Flow Elements 6-155
Structural Design Considerations 6-155
Site Design Elements 6-156
6-2.16. AR.16 – Sand Filter Basin 6-157
Introduction 6-157
Design Flow Elements 6-161
Structural Design Considerations 6-164
Site Design Elements 6-169
6-2.17. AR.17 – Sand Filter Vault 6-171
Introduction 6-171
Design Flow Elements 6-174
Structural Design Considerations 6-175
Site Design Elements 6-176
6-2.18. AR.18 – Amended Sand Filters 6-177
Introduction 6-177
Design Flow Elements 6-177
Structural Design Considerations 6-178
6-2.19. AR.19 – Media Filters 6-181
Introduction 6-181
6-2.20. AR.20 – Submerged Gravel Biofilter 6-183
Introduction 6-183
Design Flow Elements 6-184
Structural Design Considerations 6-186
Site Design Elements 6-191
6-2.21. AR.21 – Baffle-Type (API) Oil/Water Separator 6-193
Introduction 6-193
Design Flow Elements 6-197
Structural Design Considerations 6-197

Draft

Site Design Elements 6-201
6-2.22. AR.22 – Coalescing Plate Oil/Water Separator 6-203
Introduction 6-203
Design Flow Elements 6-205
Structural Design Considerations 6-206
Site Design Elements 6-208
6-2.23. AR.23 – Wet Vault 6-211
Introduction 6-211
Design Flow Elements 6-211
Structural Design Considerations 6-213
Site Design Elements 6-216
6-2.24. AR.24 – Combined Wet/Detention Vault 6-217
Introduction 6-217
Design Flow Elements 6-217
Structural Design Considerations 6-218
Groundwater Issues 6-218
Site Design Elements 6-219
6-2.25. AR.25 – Treatment Train Approach 6-221
Vegetated Filter Strip (AR.12) / Linear Sand Filter (AR.15) 6-222
Biofiltration Swale (AR.13) / Linear Sand Filter (AR.15) 6-223
6-3. Operations and Maintenance 6-225

References R-1

Glossary of Terms G-1

Appendix A Vegetation Recommendations for Airport Settings
Appendix B Detention and Infiltration Pond Design Analyses–Technical Documentation (Parametrix Technical Memorandum)

Draft

Tables

Table 1-1. New Facility 1-2

Table 1-2. Existing Facility, Hazardous Wildlife Issues 1-2

Table 1-3. Existing Facility, No Wildlife Issues 1-3

Table 5-1. Criteria for sizing runoff treatment facilities in western Washington. 5-2

Table 5-2. Criteria for sizing runoff treatment facilities in eastern Washington. 5-3

Table 5-3. Infiltration rate reduction factors to account for biofouling and siltation effects for ponds. 5-20

Table 5-4. Presumptive infiltration rates based on USDA soil classification 5-22

Table AR.08.1. Permeable surface application matrix. 6-69

Table AR.12.1. Surface roughness/Manning's *n* for vegetated filter strip design calculations. 6-112

Table AR.13.1. Biofiltration swale design criteria. 6-123

Table AR.13.2. Flow resistance coefficient in basic and continuous inflow biofiltration swales. 6-123

Table AR.14.1. Design widths for media filter drains. 6-150

Table AR.14.2. MFD mix. 6-151

Table AR.16.1. Sand medium specification. 6-168

Table AR.20-1. Typical media characteristics for submerged gravel biofilters. 6-190

Table AR.25.1 Treatment train combinations for phosphorus removal. 6-221

Table AR.25.2 Treatment train combinations for dissolved metals removal (enhanced treatment). 6-222

Table 6-1. Maintenance standards for BMPs AR.01 (Natural Dispersion), AR.02 (Engineered Dispersion), and AR.12 (Vegetated Filter Strip). 6-225

Table 6-2. Maintenance standards for Infiltration BMPs: AR.03 (Bioinfiltration Pond); AR.04 (Infiltration Pond); AR.05 (Infiltration Trench); AR.09 (Detention Pond); AR.06 (Infiltration Vault); AR.07 (Dry Well). 6-226

Table 6-3. Maintenance standards for BMP AR.08 (Permeable Pavement). 6-229

Table 6-4. Maintenance standards for closed detention and wet vault system BMPs: AR.10 (Detention Vault), AR.11 (Detention Tank), AR.23 (Wet Vault), and AR.24 (Combined Wet Vault/Detention Vault). 6-230

Table 6-5. Maintenance standards for BMP AR.13 (Biofiltration Swale). 6-231

Draft

Table 6-6. Maintenance standards for BMP AR.14 (Media Filter Drain)..... 6-232

Table 6-7. Maintenance standards for above-ground sand filter BMPs: AR.15 (Linear Sand Filter) and AR.16 (Sand Filter Basin). 6-233

Table 6-8. Maintenance standards for below-ground sand filter BMP: AR 17 (Sand Filter Vault). 6-234

Table 6-9. Maintenance standards for BMP AR.21 (API Oil/Water Separator)..... 6-235

Table 6-10. Maintenance standards for BMP AR.22 (Coalescing Plate Separator)..... 6-236

Draft

Figures

Figure 2-1. Stormwater Facility Restrictions within Airport Operation Zones. 2-17

Figure 4-1. Flow Control BMP Selection Process for Airport Projects. 4-23

Figure 4-2. Selection Process for Runoff Treatment BMPs for Airport Projects. 4-29

Figure 5-1. Engineering design steps for final design of infiltration facilities using the continuous hydrograph method (western Washington). 5-12

Figure 5-2. Engineering design steps for final design of infiltration facilities using the single hydrograph method (eastern Washington). 5-13

Figure 5-3. Determining the infiltration rate of soil amendments. 5-28

Figure 5-4. Flow-through CAVFS as simulated using Darcy's Equation. 5-30

Figure AR.01.1. Natural dispersion area. 6-7

Figure AR.02.1. Engineered dispersion area. 6-17

Figure AR.03.1. Bioinfiltration pond. 6-24

Figure AR.04.1. Infiltration pond. 6-32

Figure AR.05.1. Parking lot perimeter trench design. 6-43

Figure AR.05.2. Infiltration trench system. 6-44

Figure AR.05.3. Median strip trench design. 6-45

Figure AR.05.4. Oversize pipe trench design. 6-46

Figure AR.05.5. Underground trench and oil/grit chamber. 6-47

Figure AR.05.6. Observation well detail. 6-50

Figure AR.06.1. Infiltration vault constructed with corrugated pipe. 6-56

Figure AR.08.1. Permeable pavement surface detail. 6-71

Figure AR.09.1. Detention pond. 6-78

Figure AR.09.2. Detention pond: cross sections. 6-79

Figure AR.09.3. Overflow spillway cross section. 6-85

Figure AR.10.1. Detention vault. 6-94

Figure AR.11.1. Detention tank. 6-100

Figure AR.11.2. Detention tank access riser detail. 6-102

Figure AR.12.1. Typical vegetated filter strip. 6-106

Figure AR.12.2. Narrow area vegetated filter strip design graph. 6-116

Draft

Figure AR.13.1. Biofiltration swale: plan view. 6-120
Figure AR.13.2. Biofiltration swale: cross section. 6-121
Figure AR.13.3. Biofiltration swale: underdrain detail. 6-124
Figure AR.13.4. Biofiltration swale: low-flow drain detail. 6-125
Figure AR.13.5. Geometric elements of common cross sections. 6-127
Figure AR.13.6. Open channel flow parameter, Qn/(1.49 $s^{0.5}$), versus bottom width (b) at different flow depths (z=3). 6-128
Figure AR.13.7. Open channel flow parameter, Qn/(1.49 $s^{0.5}$), versus bottom width (b) at different flow depths (z=4). 6-129
Figure AR.14.1. Media filter drain: cross section. 6-139
Figure AR.14.2. Dual media filter drain: cross section. 6-141
Figure AR.14.3. Media filter drain without underdrain trench. 6-143
Figure AR.15.1. Linear sand filter with sediment chamber. 6-154
Figure AR.16.1. Sand filter basin with flow spreader. 6-158
Figure AR.16.2. Sand filter basin with flow spreader: detail and cross sections. 6-159
Figure AR.16.3. System layout options for sand filters with detention BMPs. 6-163
Figure AR.17.1. Sand filter vault. 6-172
Figure AR.17.2. Sand filter vault: Cross sections. 6-173
Figure AR.20.1. Submerged gravel biofilter: plan and section. 6-185
Figure AR.21.1. Baffle-type (API) oil/water separator. 6-194
Figure AR.21.2. Spill control separator. 6-195
Figure AR.21.3. Turbulence factor plot. 6-200
Figure AR.22.1. Coalescing plate separator. 6-204
Figure AR.23.1. Wet vault. 6-212

Draft

Acknowledgements

Consultant Authors:

Dave Felstul, Project Manager, Herrera Environmental Consultants
Mark Ewbank, Principal in Charge, Herrera Environmental Consultants
Mary Larkin, Lead Author for Hydrology and BMP Design Details, Herrera Environmental Consultants

Members of the Wildlife Attractants Task Force:

Ed Abbasi, WA Dept. of Ecology
Peter Birch, WA Dept. Fish & Wildlife
Brenda Buchanan, Sierra Club
Jason Callahan, WA State House, Nat'l Resource, Parks & Ecology
Michael Cheyne, WA Airport Management Assoc.
Lynn Deardorff, FAA
Brett Fish, Sierra Club
John Grettenberger, US Fish & Wildlife Service
Tom Hanson, WSDOT Research Office
Carlos Herrera, Herrera Environmental Consultants, Inc.
Eric Johnson, WA Public Ports Association
Jerry Kilpatrick, WA Airport Management Assoc.
DeeAnn Kirkpatrick, NOAA
Elizabeth Leavitt, Port of Seattle
Mike Linnell, US Dept. of Agriculture
Mo McBroom, WA Environmental Council
Cayla Morgan, FAA
Heath Grant Packard, Audubon Society
Dave Peeler, WA Dept. of Ecology
Jeffrey Robb, Port of Port Angeles
Richard Rodger, WA State Senate, Water, Energy & Environ.
Laurence Schafer, US Dept. of Agriculture
Melodie Selby, WA Dept. of Ecology
John Shambaugh, WSDOT Aviation
Thomas Sibley, NOAA
John Sibold, WSDOT Aviation
Kelly Simpson, WA State Senate, Transportation Committee
Becky Stanley, Sierra Club
Mike Stephens, WSDOT Environmental Services Office
Sam Thompson, WA State Senate, Water, Energy & Environ.
Suzie Tracy, WA Airport Management Assoc.
Greg Wingard, Waste Action Project
Bruce Wishart, People for Puget Sound

Draft

Technical Advisory Committee:

Peter Birch, Ph.D., Deputy Assistant Director – Habitat Program, WDFW
Matt Breen, Manager, Construction Services, Spokane Airport
Lynn Deardorff, Airport Certification Safety Inspector, FAA
Bob Dolan, Snohomish County Airport
Robert Duffner, Port of Seattle
Elizabeth Leavitt, Manager of Aviation Environmental Programs, Port of Seattle
Mark Maurer, Roadside and Site Development Manager, WSDOT
Aaron Moldver, Port of Seattle
Robb Parish, Pullman-Moscow Regional Airport
Rob Putnam, Arlington Airport
Jeff Robb, Airport/Marinas Manager, Port of Port Angeles
Laurence Schafer, Wildlife Services, USDA
Christopher May, Seattle Public Utilities – Urban Watersheds

WSDOT:

John Shambaugh, Senior Planner WSDOT Aviation
Mike Stephens, P.E., Manager, Hazardous Materials and Solid Waste Program, WSDOT
Rose Peralta, P.E., (formerly) Hydraulics Designer, WSDOT Hydraulics Branch
Alex Nguyen, P.E., Hydraulics Designer, WSDOT Hydraulics Branch
Glorilyn Maw, P.E., (formerly) Hydraulics Designer, WSDOT Hydraulics Branch
James Morin, Eastern Washington Roadside Maintenance Manager, WSDOT
Sandy Salisbury, Regional Liaison Landscape Architect, WSDOT
Dick Gersib, WSDOT Environmental Services
Steve Yach, ESO Compliance Branch, Environmental Performance and Permits, WSDOT

Others:

Paul Fendt, P.E., Senior Engineer, (formerly) Parametrix
Jenna Friebel, Engineer, Parametrix
David J. Kliewer, Spokane Area Manager, J-U-B Engineers, Inc.

Draft