DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

------- LOW BIDDER -------	------- 2ND BIDDER -------	------- 3RD BIDDER -------
TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
98004-5732	PO BOX 1330	
BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF. / AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF. / AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF. / AMT.DIFF.
	PREPARATION								
1	MOBILIZATION								
		L.S.			2.05%		2.56%		10.58%
			975,000.00	995,000.00	20,000.00	1,000,000.00	25,000.00	1,078,188.00	103,188.00
2	CLEARING AND GRUBBING								
	10.9000	ACRE	5,000.0000	5,000.0000	0.00%	4,125.0000	-17.50%	7,500.0000	50.00%
			54,500.00	54,500.00	0.00	44,962.50	-9,537.50	81,750.00	27,250.00
3	REMOVING DRAINAGE STRUCTURE								
	7.0000	EACH	400.0000	700.0000	75.00%	350.0000	-12.50%	1,500.0000	275.00%
			2,800.00	4,900.00	2,100.00	2,450.00	-350.00	10,500.00	7,700.00
4	REMOVING DRAINAGE PIPE								
	737.0000	L.F.	25.0000	30.0000	20.00%	8.0000	-68.00%	25.0000	0.00%
			18,425.00	22,110.00	3,685.00	5,896.00	-12,529.00	18,425.00	0.00
5	REMOVAL OF STRUCTURE AND OBSTRUCTION								
		L.S.			0.00%		100.00%		-44.30%
			5,000.00	5,000.00	0.00	10,000.00	5,000.00	2,785.00	-2,215.00
6	REMOVING CEMENT CONC. SIDEWALK								
	777.0000	S.Y.	15.0000	2.0000	-86.67%	6.0000	-60.00%	15.0000	0.00%
			11,655.00	1,554.00	-10,101.00	4,662.00	-6,993.00	11,655.00	0.00
7	REMOVING CEMENT CONC. CURB AND GUTTER								
	1360.0000	L.F.	8.0000	2.0000	-75.00%	4.0000	-50.00%	10.0000	25.00%
			10,880.00	2,720.00	-8,160.00	5,440.00	-5,440.00	13,600.00	2,720.00
8	REMOVING ASPHALT CONC. PAVEMENT								
	5484.0000	S.Y.	7.0000	6.0000	-14.29%	10.0000	42.86%	8.0000	14.29%
			38,388.00	32,904.00	-5,484.00	54,840.00	16,452.00	43,872.00	5,484.00
9	REMOVING GUARDRAIL								
	120.0000	L.F.	8.0000	5.0000	-37.50%	6.0000	-25.00%	15.0000	87.50%
			960.00	600.00	-360.00	720.00	-240.00	1,800.00	840.00
10	REMOVING GUARDRAIL ANCHOR								
	3.0000	EACH	250.0000	200.0000	-20.00%	200.0000	-20.00%	400.0000	60.00%
			750.00	600.00	-150.00	600.00	-150.00	1,200.00	450.00
11	REMOVING GUIDE POST								
	8.0000	EACH	10.0000	15.0000	50.00%	7.0000	-30.00%	20.0000	100.00%
			80.00	120.00	40.00	56.00	-24.00	160.00	80.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

------- LOW BIDDER -------	------- 2ND BIDDER -------	------- 3RD BIDDER -------
TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
98004-5732	PO BOX 1330	
BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF./ AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF./ AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF./ AMT.DIFF.
	PREPARATION								
12	REMOVING PAINT LINE								
	1450.0000	L.F.	0.5000	0.5000	0.00%	0.5000	0.00%	1.0000	100.00%
			725.00	725.00	0.00	725.00	0.00	1,450.00	725.00
13	REMOVING PLASTIC TRAFFIC MARKING								
	12.0000	EACH	100.0000	55.0000	-45.00%	55.0000	-45.00%	50.0000	-50.00%
			1,200.00	660.00	-540.00	660.00	-540.00	600.00	-600.00
14	REMOVING RAISED PAVEMENT MARKER								
	11.1000	HUND	100.0000	100.0000	0.00%	110.0000	10.00%	150.0000	50.00%
			1,110.00	1,110.00	0.00	1,221.00	111.00	1,665.00	555.00
15	REMOVING CHAIN LINK FENCE								
	1910.0000	L.F.	3.0000	3.5000	16.67%	4.0000	33.33%	15.0000	400.00%
			5,730.00	6,685.00	955.00	7,640.00	1,910.00	28,650.00	22,920.00
16	HIGH VISIBILITY CONSTRUCTION FENCING								
	3720.0000	L.F.	4.0000	4.0000	0.00%	4.0000	0.00%	5.0000	25.00%
			14,880.00	14,880.00	0.00	14,880.00	0.00	18,600.00	3,720.00
	GRADING								
17	POND EXCAVATION INCL. HAUL								
	12170.0000	C.Y.	22.0000	12.0000	-45.45%	11.0000	-50.00%	12.0000	-45.45%
			267,740.00	146,040.00	-121,700.00	133,870.00	-133,870.00	146,040.00	-121,700.00
18	ROADWAY EXCAVATION INCL. HAUL								
	6210.0000	C.Y.	30.0000	18.0000	-40.00%	11.0000	-63.33%	12.0000	-60.00%
			186,300.00	111,780.00	-74,520.00	68,310.00	-117,990.00	74,520.00	-111,780.00
19	GRAVEL BORROW INCL. HAUL								
	84260.0000	TON	12.0000	1.0000	-91.67%	16.0000	33.33%	10.6000	-11.67%
			1,011,120.00	84,260.00	-926,860.00	1,348,160.00	337,040.00	893,156.00	-117,964.00
20	EMBANKMENT COMPACTION								
	47930.0000	C.Y.	5.0000	6.0000	20.00%	1.2500	-75.00%	9.0000	80.00%
			239,650.00	287,580.00	47,930.00	59,912.50	-179,737.50	431,370.00	191,720.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

------- LOW BIDDER -------	------- 2ND BIDDER -------	------- 3RD BIDDER -------
TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
98004-5732	PO BOX 1330	
BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	DRAINAGE								
21	ECOLOGY MIX								
	40.0000	C.Y.	40.0000	80.0000	100.00%	71.0000	77.50%	97.0000	142.50%
			1,600.00	3,200.00	1,600.00	2,840.00	1,240.00	3,880.00	2,280.00
22	COMPACTED TILL LINER								
	1010.0000	TON	20.0000	18.0000	-10.00%	21.0000	5.00%	50.0000	150.00%
			20,200.00	18,180.00	-2,020.00	21,210.00	1,010.00	50,500.00	30,300.00
23	DITCH EXCAVATION INCL. HAUL								
	1130.0000	C.Y.	18.0000	15.0000	-16.67%	11.0000	-38.89%	16.0000	-11.11%
			20,340.00	16,950.00	-3,390.00	12,430.00	-7,910.00	18,080.00	-2,260.00
24	GRATE INLET TYPE 1								
	1.0000	EACH	3,000.0000	3,000.0000	0.00%	2,500.0000	-16.67%	4,200.0000	40.00%
			3,000.00	3,000.00	0.00	2,500.00	-500.00	4,200.00	1,200.00
25	QUARRY SPALLS								
	170.0000	TON	40.0000	50.0000	25.00%	32.0000	-20.00%	75.0000	87.50%
			6,800.00	8,500.00	1,700.00	5,440.00	-1,360.00	12,750.00	5,950.00
26	UNDERDRAIN PIPE 6 IN. DIAM.								
	648.0000	L.F.	24.0000	10.0000	-58.33%	13.0000	-45.83%	40.0000	66.67%
			15,552.00	6,480.00	-9,072.00	8,424.00	-7,128.00	25,920.00	10,368.00
27	DRAIN PIPE 6 IN. DIAM.								
	56.0000	L.F.	25.0000	12.0000	-52.00%	20.0000	-20.00%	45.0000	80.00%
			1,400.00	672.00	-728.00	1,120.00	-280.00	2,520.00	1,120.00
28	SCHEDULE A CULV. PIPE 18 IN. DIAM.								
	37.0000	L.F.	40.0000	50.0000	25.00%	34.0000	-15.00%	70.0000	75.00%
			1,480.00	1,850.00	370.00	1,258.00	-222.00	2,590.00	1,110.00
	STORM SEWER								
29	CATCH BASIN TYPE 2 48 IN DIAM WITH JAIL HOUSE GRATE								
	1.0000	EACH	5,000.0000	4,000.0000	-20.00%	2,000.0000	-60.00%	4,000.0000	-20.00%
			5,000.00	4,000.00	-1,000.00	2,000.00	-3,000.00	4,000.00	-1,000.00
30	CATCH BASIN TYPE 1								
	7.0000	EACH	1,600.0000	1,500.0000	-6.25%	1,000.0000	-37.50%	4,200.0000	162.50%
			11,200.00	10,500.00	-700.00	7,000.00	-4,200.00	29,400.00	18,200.00

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

------- LOW BIDDER -------	------- 2ND BIDDER -------	------- 3RD BIDDER -------
TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
98004-5732	PO BOX 1330	
BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF. / AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF. / AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF. / AMT.DIFF.
	STORM SEWER								
31	CATCH BASIN TYPE 2 48 IN. DIAM.								
	16.0000	EACH	4,000.0000	3,000.0000	-25.00%	2,000.0000	-50.00%	3,600.0000	-10.00%
			64,000.00	48,000.00	-16,000.00	32,000.00	-32,000.00	57,600.00	-6,400.00
32	TESTING STORM SEWER PIPE								
	1902.0000	L.F.	3.0000	1.5000	-50.00%	1.0000	-66.67%	5.0000	66.67%
			5,706.00	2,853.00	-2,853.00	1,902.00	-3,804.00	9,510.00	3,804.00
33	CL. V REINF. CONC. STORM SEWER PIPE 12 IN. DIAM.								
	121.0000	L.F.	60.0000	50.0000	-16.67%	40.0000	-33.33%	75.0000	25.00%
			7,260.00	6,050.00	-1,210.00	4,840.00	-2,420.00	9,075.00	1,815.00
34	CL. V REINF. CONC. STORM SEWER PIPE 18 IN. DIAM.								
	125.0000	L.F.	75.0000	65.0000	-13.33%	46.0000	-38.67%	85.0000	13.33%
			9,375.00	8,125.00	-1,250.00	5,750.00	-3,625.00	10,625.00	1,250.00
35	SCHEDULE A STORM SEWER PIPE 12 IN. DIAM.								
	873.0000	L.F.	40.0000	37.0000	-7.50%	20.0000	-50.00%	60.0000	50.00%
			34,920.00	32,301.00	-2,619.00	17,460.00	-17,460.00	52,380.00	17,460.00
36	SCHEDULE A STORM SEWER PIPE 18 IN. DIAM.								
	475.0000	L.F.	50.0000	45.0000	-10.00%	30.0000	-40.00%	75.0000	50.00%
			23,750.00	21,375.00	-2,375.00	14,250.00	-9,500.00	35,625.00	11,875.00
37	SCHEDULE A STORM SEWER PIPE 24 IN. DIAM.								
	290.0000	L.F.	70.0000	60.0000	-14.29%	42.0000	-40.00%	85.0000	21.43%
			20,300.00	17,400.00	-2,900.00	12,180.00	-8,120.00	24,650.00	4,350.00
38	SCHEDULE A STORM SEWER PIPE 30 IN. DIAM.								
	18.0000	L.F.	90.0000	120.0000	33.33%	70.0000	-22.22%	125.0000	38.89%
			1,620.00	2,160.00	540.00	1,260.00	-360.00	2,250.00	630.00
	STRUCTURE								
39	SEW REDMOND FINISH								
	7088.0000	S.F.	12.0000	6.0000	-50.00%	6.0000	-50.00%	6.0000	-50.00%
			85,056.00	42,528.00	-42,528.00	42,528.00	-42,528.00	42,528.00	-42,528.00
40	SEW RANDOM BOARD FINISH								
	1084.0000	S.F.	4.0000	7.0000	75.00%	6.0000	50.00%	9.0000	125.00%
			4,336.00	7,588.00	3,252.00	6,504.00	2,168.00	9,756.00	5,420.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	LOW BIDDER	2ND BIDDER	3RD BIDDER
	TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
	350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
	98004-5732	PO BOX 1330	
	BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
	CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF. / AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF. / AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF. / AMT.DIFF.
	STRUCTURE								
41	STRUCTURE EXCAVATION CLASS A INCL. HAUL								
	2246.0000	C.Y.	25.0000	14.0000	-44.00%	20.0000	-20.00%	25.0000	0.00%
			56,150.00	31,444.00	-24,706.00	44,920.00	-11,230.00	56,150.00	0.00
42	SHORING OR EXTRA EXCAVATION CL. A FLYOVER RAMP								
		L.S.			482.63%		111.86%		95.97%
			47,200.00	275,000.00	227,800.00	100,000.00	52,800.00	92,500.00	45,300.00
43	GRAVEL BACKFILL FOR WALL								
	460.0000	TON	32.0000	25.0000	-21.88%	16.0000	-50.00%	25.0000	-21.88%
			14,720.00	11,500.00	-3,220.00	7,360.00	-7,360.00	11,500.00	-3,220.00
44	ST. REINF. BAR FOR BRIDGE								
	256200.0000	LB.	1.0000	1.7500	75.00%	1.5000	50.00%	1.0000	0.00%
			256,200.00	448,350.00	192,150.00	384,300.00	128,100.00	256,200.00	0.00
45	ST. REINF. BAR FOR RETAINING WALL								
	12480.0000	LB.	1.0000	1.7500	75.00%	1.5000	50.00%	1.1000	10.00%
			12,480.00	21,840.00	9,360.00	18,720.00	6,240.00	13,728.00	1,248.00
46	CONC. CLASS 3000 FOR GUTTER BEHIND WALL BL6								
	4.4000	C.Y.	575.0000	2,000.0000	247.83%	1,250.0000	117.39%	1,100.0000	91.30%
			2,530.00	8,800.00	6,270.00	5,500.00	2,970.00	4,840.00	2,310.00
47	CONC. CLASS 4000 FOR BRIDGE								
	1390.0000	C.Y.	500.0000	350.0000	-30.00%	550.0000	10.00%	530.0000	6.00%
			695,000.00	486,500.00	-208,500.00	764,500.00	69,500.00	736,700.00	41,700.00
48	CONC. CLASS 4000 FOR RETAINING WALL								
	153.2000	C.Y.	610.0000	750.0000	22.95%	750.0000	22.95%	750.0000	22.95%
			93,452.00	114,900.00	21,448.00	114,900.00	21,448.00	114,900.00	21,448.00
49	PRESTRESSED CONC. GIRDER WF74G								
	2117.0000	L.F.	230.0000	300.0000	30.43%	375.0000	63.04%	350.0000	52.17%
			486,910.00	635,100.00	148,190.00	793,875.00	306,965.00	740,950.00	254,040.00
50	SUPERSTRUCTURE BL LINE RAMP OVER SR 202								
		L.S.			34.58%		-13.04%		1.97%
			966,000.00	1,300,000.00	334,000.00	840,000.00	-126,000.00	985,000.00	19,000.00
51	BRIDGE RAILING TYPE BP								
	1890.0000	L.F.	100.0000	50.0000	-50.00%	60.0000	-40.00%	70.0000	-30.00%
			189,000.00	94,500.00	-94,500.00	113,400.00	-75,600.00	132,300.00	-56,700.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	------- LOW BIDDER -------	------- 2ND BIDDER -------	------- 3RD BIDDER -------
	TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
	350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
	98004-5732	PO BOX 1330	
	BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
	CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF. / AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF. / AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF. / AMT.DIFF.
	STRUCTURE								
52	TRAFFIC BARRIER								
	970.0000	L.F.	100.0000	90.0000	-10.00%	75.0000	-25.00%	90.0000	-10.00%
			97,000.00	87,300.00	-9,700.00	72,750.00	-24,250.00	87,300.00	-9,700.00
53	PEDESTRIAN BARRIER								
	34.3000	L.F.	155.0000	95.0000	-38.71%	190.0000	22.58%	200.0000	29.03%
			5,316.50	3,258.50	-2,058.00	6,517.00	1,200.50	6,860.00	1,543.50
54	SEW TRAFFIC BARRIER								
	512.0000	L.F.	308.0000	250.0000	-18.83%	280.0000	-9.09%	295.0000	-4.22%
			157,696.00	128,000.00	-29,696.00	143,360.00	-14,336.00	151,040.00	-6,656.00
55	STRUCTURAL EARTH WALL								
	8172.0000	S.F.	23.0000	28.0000	21.74%	30.0000	30.43%	25.0000	8.70%
			187,956.00	228,816.00	40,860.00	245,160.00	57,204.00	204,300.00	16,344.00
56	BACKFILL FOR STRUCTURAL EARTH WALL INCL. HAUL								
	9460.0000	TON	20.0000	20.0000	0.00%	15.0000	-25.00%	20.0000	0.00%
			189,200.00	189,200.00	0.00	141,900.00	-47,300.00	189,200.00	0.00
	SURFACING								
57	PERMEABLE BASE COURSE AGGREGATE								
	1070.0000	TON	30.0000	25.0000	-16.67%	23.0000	-23.33%	25.0000	-16.67%
			32,100.00	26,750.00	-5,350.00	24,610.00	-7,490.00	26,750.00	-5,350.00
58	SHOULDER BALLAST								
	3550.0000	TON	25.0000	25.0000	0.00%	25.0000	0.00%	25.0000	0.00%
			88,750.00	88,750.00	0.00	88,750.00	0.00	88,750.00	0.00
59	CRUSHED SURFACING BASE COURSE								
	7400.0000	TON	24.0000	20.0000	-16.67%	18.0000	-25.00%	18.0000	-25.00%
			177,600.00	148,000.00	-29,600.00	133,200.00	-44,400.00	133,200.00	-44,400.00

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	LOW BIDDER	2ND BIDDER	3RD BIDDER
	TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
	350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
	98004-5732	PO BOX 1330	
	BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
	CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF. / AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF. / AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF. / AMT.DIFF.
	LIQUID ASPHALT								
60	ANTI-STRIPPING ADDITIVE								
		EST.			0.00%		0.00%		0.00%
			5,010.00	5,010.00		5,010.00		5,010.00	
	CEMENT CONCRETE PAVEMENT								
61	BRIDGE APPROACH SLAB								
	263.0000	S.Y.	225.0000	300.0000	33.33%	240.0000	6.67%	245.0000	8.89%
			59,175.00	78,900.00	19,725.00	63,120.00	3,945.00	64,435.00	5,260.00
	HOT MIX ASPHALT								
62	PERVIOUS HMA CL 3/4 IN. PG 58-22								
	600.0000	TON	120.0000	105.0000	-12.50%	105.0000	-12.50%	105.0000	-12.50%
			72,000.00	63,000.00	-9,000.00	63,000.00	-9,000.00	63,000.00	-9,000.00
63	CRACK SEALING								
		EST.			0.00%		0.00%		0.00%
			5,000.00	5,000.00		5,000.00		5,000.00	
64	PLANING BITUMINOUS PAVEMENT								
	1601.0000	S.Y.	10.0000	6.0000	-40.00%	5.0000	-50.00%	6.0000	-40.00%
			16,010.00	9,606.00	-6,404.00	8,005.00	-8,005.00	9,606.00	-6,404.00
65	HMA FOR PAVEMENT REPAIR CL. 1/2 IN. PG 68-22								
	200.0000	TON	100.0000	80.0000	-20.00%	76.0000	-24.00%	75.0000	-25.00%
			20,000.00	16,000.00	-4,000.00	15,200.00	-4,800.00	15,000.00	-5,000.00
66	HMA CL. 1/2 IN. PG 68-22								
	7530.0000	TON	80.0000	64.0000	-20.00%	65.0000	-18.75%	60.0000	-25.00%
			602,400.00	481,920.00	-120,480.00	489,450.00	-112,950.00	451,800.00	-150,600.00
67	JOB MIX COMPLIANCE PRICE ADJUSTMENT								
		CALC			0.00%		0.00%		0.00%
			9,882.00	9,882.00		9,882.00		9,882.00	
68	COMPACTION PRICE ADJUSTMENT								
		CALC			0.00%		0.00%		0.00%
			6,588.00	6,588.00		6,588.00		6,588.00	

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	LOW BIDDER	2ND BIDDER	3RD BIDDER
	TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
	350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
	98004-5732	PO BOX 1330	
	BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
	CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF. / AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF. / AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF. / AMT.DIFF.
	HOT MIX ASPHALT								
69	ASPHALT COST PRICE ADJUSTMENT								
		CALC			0.00%		0.00%		0.00%
			1,311.00	1,311.00		1,311.00		1,311.00	
70	HMA FOR APPROACH CL. 1/2 IN. PG 68-22								
	220.0000	TON	90.0000	100.0000	11.11%	86.0000	-4.44%	85.0000	-5.56%
			19,800.00	22,000.00	2,200.00	18,920.00	-880.00	18,700.00	-1,100.00
71	CYCLIC DENSITY PRICE ADJUSTMENT								
		CALC			0.00%		0.00%		0.00%
			-1.00	-1.00		-1.00		-1.00	
72	SMOOTHNESS COMPLIANCE ADJUSTMENT								
		CALC			0.00%		0.00%		0.00%
			1.00	1.00		1.00		1.00	
	EROSION CONTROL AND PLANTING								
73	WET NATIVE SEEDING AND MULCHING								
	0.4100	ACRE	4,300.0000	7,000.0000	62.79%	6,000.0000	39.53%	7,500.0000	74.42%
			1,763.00	2,870.00	1,107.00	2,460.00	697.00	3,075.00	1,312.00
74	STRUCTURAL SOIL MIX								
	358.0000	C.Y.	38.5000	40.0000	3.90%	35.0000	-9.09%	20.0000	-48.05%
			13,783.00	14,320.00	537.00	12,530.00	-1,253.00	7,160.00	-6,623.00
75	2"-4" QUARRY ROCK								
	20.0000	TON	40.0000	35.0000	-12.50%	30.0000	-25.00%	50.0000	25.00%
			800.00	700.00	-100.00	600.00	-200.00	1,000.00	200.00
76	GRAVEL BACKFILL FOR DRYWELLS								
	20.0000	TON	35.0000	35.0000	0.00%	40.0000	14.29%	100.0000	185.71%
			700.00	700.00	0.00	800.00	100.00	2,000.00	1,300.00
77	ESC LEAD								
	180.0000	DAY	170.0000	1.0000	-99.41%	100.0000	-41.18%	120.0000	-29.41%
			30,600.00	180.00	-30,420.00	18,000.00	-12,600.00	21,600.00	-9,000.00
78	CHECK DAM								
	24.0000	L.F.	55.0000	8.0000	-85.45%	20.0000	-63.64%	12.0000	-78.18%
			1,320.00	192.00	-1,128.00	480.00	-840.00	288.00	-1,032.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

------- LOW BIDDER -------	------- 2ND BIDDER -------	------- 3RD BIDDER -------
TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
98004-5732	PO BOX 1330	
BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF. / AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF. / AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF. / AMT.DIFF.
	EROSION CONTROL AND PLANTING								
79	STABILIZED CONSTRUCTION ENTRANCE								
	1150.0000	S.Y.	20.0000	16.0000	-20.00%	16.0000	-20.00%	30.0000	50.00%
			23,000.00	18,400.00	-4,600.00	18,400.00	-4,600.00	34,500.00	11,500.00
80	STREET CLEANING								
	1600.0000	HR	140.0000	90.0000	-35.71%	85.0000	-39.29%	95.0000	-32.14%
			224,000.00	144,000.00	-80,000.00	136,000.00	-88,000.00	152,000.00	-72,000.00
81	INLET PROTECTION								
	38.0000	EACH	80.0000	60.0000	-25.00%	65.0000	-18.75%	95.0000	18.75%
			3,040.00	2,280.00	-760.00	2,470.00	-570.00	3,610.00	570.00
82	SILT FENCE								
	2600.0000	L.F.	5.0000	4.0000	-20.00%	5.0000	0.00%	7.0000	40.00%
			13,000.00	10,400.00	-2,600.00	13,000.00	0.00	18,200.00	5,200.00
83	COMPOST SOCK								
	974.0000	L.F.	10.0000	10.0000	0.00%	6.5000	-35.00%	8.0000	-20.00%
			9,740.00	9,740.00	0.00	6,331.00	-3,409.00	7,792.00	-1,948.00
84	EROSION/WATER POLLUTION CONTROL								
		EST.			0.00%		0.00%		0.00%
			450,000.00	450,000.00		450,000.00		450,000.00	
85	TEMPORARY CURB								
	130.0000	L.F.	7.5000	9.0000	20.00%	45.0000	500.00%	9.0000	20.00%
			975.00	1,170.00	195.00	5,850.00	4,875.00	1,170.00	195.00
86	TEMPORARY PIPE SLOPE DRAIN								
	991.0000	L.F.	20.0000	20.0000	0.00%	30.0000	50.00%	15.0000	-25.00%
			19,820.00	19,820.00	0.00	29,730.00	9,910.00	14,865.00	-4,955.00
87	SEEDING, FERTILIZING, AND MULCHING								
	0.8600	ACRE	1,800.0000	2,000.0000	11.11%	1,200.0000	-33.33%	1,500.0000	-16.67%
			1,548.00	1,720.00	172.00	1,032.00	-516.00	1,290.00	-258.00
88	TOPSOIL TYPE A								
	1746.0000	C.Y.	40.0000	50.0000	25.00%	54.0000	35.00%	50.0000	25.00%
			69,840.00	87,300.00	17,460.00	94,284.00	24,444.00	87,300.00	17,460.00
89	PLANT SELECTION SLOUGH SEDGE, BARE ROOT								
	425.0000	EACH	1.5000	3.0000	100.00%	2.0000	33.33%	2.0000	33.33%
			637.50	1,275.00	637.50	850.00	212.50	850.00	212.50

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

------- LOW BIDDER -------	------- 2ND BIDDER -------	------- 3RD BIDDER -------
TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
98004-5732	PO BOX 1330	
BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF. / AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF. / AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF. / AMT.DIFF.
	EROSION CONTROL AND PLANTING								
90	PLANT SELECTION SOFTSTEM BULRUSH, BARE ROOT								
	425.0000	EACH	1.5000	3.0000	100.00%	2.0000	33.33%	2.0000	33.33%
			637.50	1,275.00	637.50	850.00	212.50	850.00	212.50
91	PLANT SELECTION SLENDER RUSH, BARE ROOT								
	1050.0000	EACH	1.5000	3.0000	100.00%	2.0000	33.33%	2.0000	33.33%
			1,575.00	3,150.00	1,575.00	2,100.00	525.00	2,100.00	525.00
92	PLANT SELECTION SMALL FRUITED BULRUSH, BARE ROOT								
	1475.0000	EACH	1.5000	3.0000	100.00%	2.0000	33.33%	2.0000	33.33%
			2,212.50	4,425.00	2,212.50	2,950.00	737.50	2,950.00	737.50
93	PLANT SELECTION HARDSTEM BULRUSH BARE ROOT								
	1175.0000	EACH	1.5000	3.0000	100.00%	2.0000	33.33%	2.0000	33.33%
			1,762.50	3,525.00	1,762.50	2,350.00	587.50	2,350.00	587.50
94	PSIPE BOWHALL RED MAPLE, 2" CAL., B&B								
	9.0000	EACH	238.0000	300.0000	26.05%	300.0000	26.05%	225.0000	-5.46%
			2,142.00	2,700.00	558.00	2,700.00	558.00	2,025.00	-117.00
95	PSIPE DEODAR CEDAR, 4' HT, B&B								
	64.0000	EACH	76.2500	60.0000	-21.31%	105.0000	37.70%	55.0000	-27.87%
			4,880.00	3,840.00	-1,040.00	6,720.00	1,840.00	3,520.00	-1,360.00
96	PSIPE DOUGLAS FIR, 4' HT, B&B								
	47.0000	EACH	46.0000	60.0000	30.43%	85.0000	84.78%	55.0000	19.57%
			2,162.00	2,820.00	658.00	3,995.00	1,833.00	2,585.00	423.00
97	PSIPE RED SUNSET MAPLE, 2" CAL, B&B								
	22.0000	EACH	240.0000	240.0000	0.00%	300.0000	25.00%	225.0000	-6.25%
			5,280.00	5,280.00	0.00	6,600.00	1,320.00	4,950.00	-330.00
98	PSIPE BOSTON IVY, 10" RUNNER, #1 CONT.								
	34.0000	EACH	12.0000	12.0000	0.00%	11.0000	-8.33%	10.0000	-16.67%
			408.00	408.00	0.00	374.00	-34.00	340.00	-68.00
99	PSIPE WESTERN RED CEDAR 4' HT, B&B								
	54.0000	EACH	66.2500	60.0000	-9.43%	85.0000	28.30%	50.0000	-24.53%
			3,577.50	3,240.00	-337.50	4,590.00	1,012.50	2,700.00	-877.50
100	PSIPE CORALBERRY, 9" HT., #1 CONT.								
	1444.0000	EACH	6.0000	12.0000	100.00%	9.0000	50.00%	10.0000	66.67%
			8,664.00	17,328.00	8,664.00	12,996.00	4,332.00	14,440.00	5,776.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	LOW BIDDER	2ND BIDDER	3RD BIDDER
	TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
	350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
	98004-5732	PO BOX 1330	
	BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
	CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF. / AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF. / AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF. / AMT.DIFF.
	EROSION CONTROL AND PLANTING								
101	PSIPE BEAKED HAZELNUT, 12" HT., #1 CONT.								
	34.0000	EACH	8.0000	10.0000	25.00%	11.0000	37.50%	8.0000	0.00%
			272.00	340.00	68.00	374.00	102.00	272.00	0.00
102	PSIPE RED ELDERBERRY, 12" HT., #1 CONT.								
	34.0000	EACH	8.0000	10.0000	25.00%	9.0000	12.50%	8.0000	0.00%
			272.00	340.00	68.00	306.00	34.00	272.00	0.00
103	PSIPE COMPACT OREGON GRAPE, 6" HT, #1 CONT.								
	89.0000	EACH	14.0000	12.0000	-14.29%	11.0000	-21.43%	10.0000	-28.57%
			1,246.00	1,068.00	-178.00	979.00	-267.00	890.00	-356.00
104	PSIPE SALMONBERRY, 12" HT., #1 CONT.								
	34.0000	EACH	8.0000	10.0000	25.00%	8.0000	0.00%	8.0000	0.00%
			272.00	340.00	68.00	272.00	0.00	272.00	0.00
105	PSIPE SERVICEBERRY, 12" HT., #1 CONT.								
	34.0000	EACH	11.0000	10.0000	-9.09%	8.0000	-27.27%	8.0000	-27.27%
			374.00	340.00	-34.00	272.00	-102.00	272.00	-102.00
106	PSIPE PRIVET HONEYSUCKLE, 12" HT., #1 CONT.								
	89.0000	EACH	9.5000	10.0000	5.26%	11.0000	15.79%	8.0000	-15.79%
			845.50	890.00	44.50	979.00	133.50	712.00	-133.50
107	PSIPE SHADBLOW SEVICEBERRY, 5' HT., 5 GAL. CONT.								
	45.0000	EACH	48.0000	60.0000	25.00%	38.0000	-20.83%	50.0000	4.17%
			2,160.00	2,700.00	540.00	1,710.00	-450.00	2,250.00	90.00
108	PSIPE RD-OSIER DOGWOOD, 12" HT, #1 CONT.								
	384.0000	EACH	6.7500	10.0000	48.15%	7.0000	3.70%	8.0000	18.52%
			2,592.00	3,840.00	1,248.00	2,688.00	96.00	3,072.00	480.00
109	PSIPE SITKA WILLOW, 36" HT., LIVE STAKE								
	120.0000	EACH	3.0000	4.0000	33.33%	5.0000	66.67%	3.0000	0.00%
			360.00	480.00	120.00	600.00	240.00	360.00	0.00
110	PLANT ESTABLISHMENT - SECOND YEAR								
		EST.			0.00%		0.00%		0.00%
			12,500.00	12,500.00		12,500.00		12,500.00	
111	PLANT ESTABLISHMENT - THIRD YEAR								
		EST.			0.00%		0.00%		0.00%
			12,500.00	12,500.00		12,500.00		12,500.00	

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

				LOW BIDDER		2ND BIDDER		3RD BIDDER	
				TRI-STATE CONSTRUCTION, INC.		MOWAT CONSTRUCTION COMPANY		BILFINGER BERGER CIVIL INC.	
				350 - 106TH AVE NE		20210 142ND AVE NE 98072		1000 SE TECH CENTER DR STE 17(	
				98004-5732		PO BOX 1330			
				BELLEVUE WA 980093686		WOODINVILLE WA 980721330		VANCOUVER WA 986835549	
				CONTRACTOR NUMBER : 829961		CONTRACTOR NUMBER : 551010		CONTRACTOR NUMBER : 100437	
ITEM NO.	ITEM DESCRIPTION EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT/ TOTAL AMOUNT	PRICE PER UNIT/ TOTAL AMOUNT	% DIFF./ AMT.DIFF.	PRICE PER UNIT/ TOTAL AMOUNT	% DIFF./ AMT.DIFF.	PRICE PER UNIT/ TOTAL AMOUNT	% DIFF./ AMT.DIFF.
	EROSION CONTROL AND PLANTING								
112	REMOVAL OF BURIED MAN-MADE DEBRIS								
		EST.			0.00%		0.00%		0.00%
			1,000.00	1,000.00		1,000.00		1,000.00	
113	FINE COMPOST								
	197.0000	C.Y.	45.0000	40.0000	-11.11%	40.0000	-11.11%	30.0000	-33.33%
			8,865.00	7,880.00	-985.00	7,880.00	-985.00	5,910.00	-2,955.00
114	WEED CONTROL								
		EST.			0.00%		0.00%		0.00%
			1,600.00	1,600.00		1,600.00		1,600.00	
115	SOIL AMENDMENT								
	608.0000	C.Y.	42.0000	50.0000	19.05%	35.0000	-16.67%	45.0000	7.14%
			25,536.00	30,400.00	4,864.00	21,280.00	-4,256.00	27,360.00	1,824.00
116	BARK OR WOOD CHIP MULCH								
	593.0000	C.Y.	31.5000	45.0000	42.86%	35.0000	11.11%	40.0000	26.98%
			18,679.50	26,685.00	8,005.50	20,755.00	2,075.50	23,720.00	5,040.50
117	WATER FOR EMERGENT PLANTS								
	30.0000	EACH	1,125.0000	800.0000	-28.89%	500.0000	-55.56%	765.0000	-32.00%
			33,750.00	24,000.00	-9,750.00	15,000.00	-18,750.00	22,950.00	-10,800.00
	TRAFFIC								
118	SENSITIVE AREA SIGN								
	20.0000	EACH	50.0000	50.0000	0.00%	45.0000	-10.00%	42.0000	-16.00%
			1,000.00	1,000.00	0.00	900.00	-100.00	840.00	-160.00
119	TEMPORARY SIGNAL DETECTION								
		L.S.			89.39%		89.39%		89.39%
			13,200.00	25,000.00	11,800.00	25,000.00	11,800.00	25,000.00	11,800.00
120	TEMPORARY SIGNAL REMOVAL PLAN								
		L.S.			66.67%		233.33%		0.00%
			1,500.00	2,500.00	1,000.00	5,000.00	3,500.00	1,500.00	0.00
121	BEAM GUARDRAIL TYPE 31 NON-FLARED TERMINAL								
	3.0000	EACH	2,500.0000	2,500.0000	0.00%	2,500.0000	0.00%	2,215.0000	-11.40%
			7,500.00	7,500.00	0.00	7,500.00	0.00	6,645.00	-855.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	LOW BIDDER	2ND BIDDER	3RD BIDDER
	TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
	350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
	98004-5732	PO BOX 1330	
	BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
	CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF. / AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF. / AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF. / AMT.DIFF.
	TRAFFIC								
122	BEAM GUARDRAIL TYPE 31								
	303.0000	L.F.	40.0000	25.0000	-37.50%	25.0000	-37.50%	23.0000	-42.50%
			12,120.00	7,575.00	-4,545.00	7,575.00	-4,545.00	6,969.00	-5,151.00
123	CEMENT CONC. TRAFFIC CURB AND GUTTER								
	291.0000	L.F.	20.0000	30.0000	50.00%	18.0000	-10.00%	30.0000	50.00%
			5,820.00	8,730.00	2,910.00	5,238.00	-582.00	8,730.00	2,910.00
124	EXTRUDED CURB								
	1170.0000	L.F.	7.0000	5.0000	-28.57%	5.0000	-28.57%	6.0000	-14.29%
			8,190.00	5,850.00	-2,340.00	5,850.00	-2,340.00	7,020.00	-1,170.00
125	BEAM GUARDRAIL TYPE 1								
	888.0000	L.F.	35.0000	22.0000	-37.14%	21.0000	-40.00%	21.0000	-40.00%
			31,080.00	19,536.00	-11,544.00	18,648.00	-12,432.00	18,648.00	-12,432.00
126	BEAM GUARDRAIL TRANSITION SECTION TYPE 4								
	1.0000	EACH	1,200.0000	750.0000	-37.50%	650.0000	-45.83%	615.0000	-48.75%
			1,200.00	750.00	-450.00	650.00	-550.00	615.00	-585.00
127	BEAM GUARDRAIL TRANSITION SECTION TYPE 20								
	3.0000	EACH	1,500.0000	1,500.0000	0.00%	1,500.0000	0.00%	1,310.0000	-12.67%
			4,500.00	4,500.00	0.00	4,500.00	0.00	3,930.00	-570.00
128	BEAM GUARDRAIL NON-FLARED TERMINAL								
	1.0000	EACH	2,600.0000	2,500.0000	-3.85%	2,200.0000	-15.38%	2,135.0000	-17.88%
			2,600.00	2,500.00	-100.00	2,200.00	-400.00	2,135.00	-465.00
129	BEAM GUARDRAIL ANCHOR TYPE 1								
	1.0000	EACH	700.0000	750.0000	7.14%	650.0000	-7.14%	630.0000	-10.00%
			700.00	750.00	50.00	650.00	-50.00	630.00	-70.00
130	PRECAST SINGLE SLOPE CONC. BARRIER								
	1542.0000	L.F.	85.0000	65.0000	-23.53%	56.0000	-34.12%	61.0000	-28.24%
			131,070.00	100,230.00	-30,840.00	86,352.00	-44,718.00	94,062.00	-37,008.00
131	CAST IN PLACE SINGLE SLOPE CONC. BARRIER								
	1408.0000	L.F.	200.0000	95.0000	-52.50%	75.0000	-62.50%	115.0000	-42.50%
			281,600.00	133,760.00	-147,840.00	105,600.00	-176,000.00	161,920.00	-119,680.00
132	SINGLE SLOPE CONC. BARRIER LIGHT STANDARD FOUNDATION								
	5.0000	EACH	10,000.0000	6,000.0000	-40.00%	7,500.0000	-25.00%	10,500.0000	5.00%
			50,000.00	30,000.00	-20,000.00	37,500.00	-12,500.00	52,500.00	2,500.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

------- LOW BIDDER -------	------- 2ND BIDDER -------	------- 3RD BIDDER -------
TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
98004-5732	PO BOX 1330	
BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	TRAFFIC								
133	TEMPORARY CONC. BARRIER								
	3571.0000	L.F.	15.0000	4.0000	-73.33%	6.0000	-60.00%	16.0000	6.67%
			53,565.00	14,284.00	-39,281.00	21,426.00	-32,139.00	57,136.00	3,571.00
134	TEMPORARY IMPACT ATTENUATOR								
	4.0000	EACH	5,000.0000	3,500.0000	-30.00%	3,000.0000	-40.00%	4,850.0000	-3.00%
			20,000.00	14,000.00	-6,000.00	12,000.00	-8,000.00	19,400.00	-600.00
135	RESETTING IMPACT ATTENUATOR								
	2.0000	EACH	1,000.0000	1,500.0000	50.00%	750.0000	-25.00%	800.0000	-20.00%
			2,000.00	3,000.00	1,000.00	1,500.00	-500.00	1,600.00	-400.00
136	TRUCK-MOUNTED IMPACT ATTENUATOR								
	1.0000	EACH	15,000.0000	5,000.0000	-66.67%	15,000.0000	0.00%	9,800.0000	-34.67%
			15,000.00	5,000.00	-10,000.00	15,000.00	0.00	9,800.00	-5,200.00
137	OPERATION OF TRUCK-MOUNTED IMPACT ATTENUATOR								
	250.0000	HR	50.0000	50.0000	0.00%	65.0000	30.00%	35.0000	-30.00%
			12,500.00	12,500.00	0.00	16,250.00	3,750.00	8,750.00	-3,750.00
138	REPAIR TRUCK-MOUNTED IMPACT ATTENUATOR								
		EST.			0.00%		0.00%		0.00%
			5,000.00	5,000.00		5,000.00		5,000.00	
139	FLEXIBLE GUIDE POST								
	4.0000	EACH	30.0000	28.0000	-6.67%	35.0000	16.67%	30.0000	0.00%
			120.00	112.00	-8.00	140.00	20.00	120.00	0.00
140	PLASTIC LINE								
	8648.0000	L.F.	1.7500	1.5000	-14.29%	1.5000	-14.29%	2.0000	14.29%
			15,134.00	12,972.00	-2,162.00	12,972.00	-2,162.00	17,296.00	2,162.00
141	PLASTIC WIDE LINE								
	3120.0000	L.F.	2.0000	3.0000	50.00%	3.0000	50.00%	3.0000	50.00%
			6,240.00	9,360.00	3,120.00	9,360.00	3,120.00	9,360.00	3,120.00
142	PLASTIC DOTTED WIDE LINE								
	250.0000	L.F.	2.0000	2.0000	0.00%	2.0000	0.00%	2.0000	0.00%
			500.00	500.00	0.00	500.00	0.00	500.00	0.00
143	PLASTIC STOP LINE								
	90.0000	L.F.	12.0000	11.0000	-8.33%	11.0000	-8.33%	12.0000	0.00%
			1,080.00	990.00	-90.00	990.00	-90.00	1,080.00	0.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	LOW BIDDER	2ND BIDDER	3RD BIDDER
	TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
	350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
	98004-5732	PO BOX 1330	
	BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
	CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF. / AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF. / AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF. / AMT.DIFF.
	TRAFFIC								
144	PLASTIC TRAFFIC ARROW								
	29.0000	EACH	125.0000	110.0000	-12.00%	110.0000	-12.00%	120.0000	-4.00%
			3,625.00	3,190.00	-435.00	3,190.00	-435.00	3,480.00	-145.00
145	PLASTIC DRAINAGE MARKING								
	17.0000	EACH	20.0000	30.0000	50.00%	30.0000	50.00%	25.0000	25.00%
			340.00	510.00	170.00	510.00	170.00	425.00	85.00
146	RAISED PAVEMENT MARKER TYPE 1								
	17.7000	HUND	200.0000	175.0000	-12.50%	165.0000	-17.50%	250.0000	25.00%
			3,540.00	3,097.50	-442.50	2,920.50	-619.50	4,425.00	885.00
147	RAISED PAVEMENT MARKER TYPE 2								
	3.8000	HUND	200.0000	320.0000	60.00%	310.0000	55.00%	350.0000	75.00%
			760.00	1,216.00	456.00	1,178.00	418.00	1,330.00	570.00
148	TEMPORARY PAVEMENT MARKING								
	20000.0000	L.F.	1.0000	0.6500	-35.00%	0.6500	-35.00%	1.0000	0.00%
			20,000.00	13,000.00	-7,000.00	13,000.00	-7,000.00	20,000.00	0.00
149	PERMANENT SIGNING								
		L.S.			53.85%		-3.84%		23.08%
			25,999.00	40,000.00	14,001.00	25,000.00	-999.00	32,000.00	6,001.00
150	CANTILEVER SIGN STRUCTURE NO. 1								
		L.S.			62.50%		-37.50%		53.75%
			40,000.00	65,000.00	25,000.00	25,000.00	-15,000.00	61,500.00	21,500.00
151	ILLUMINATION SYSTEM SUA 4027								
		L.S.			5.42%		5.42%		-0.60%
			166,000.00	175,000.00	9,000.00	175,000.00	9,000.00	165,000.00	-1,000.00
152	TRAFFIC DATA ACCUMULATION AND RAMP METERING SYSTEM 4027								
		L.S.			34.96%		34.96%		31.59%
			148,188.00	200,000.00	51,812.00	200,000.00	51,812.00	195,000.00	46,812.00
153	TRAFFIC SIGNAL SYSTEM SUA 4027								
		L.S.			31.58%		-1.32%		31.58%
			15,200.00	20,000.00	4,800.00	15,000.00	-200.00	20,000.00	4,800.00
154	SEQUENTIAL ARROW SIGN								
	800.0000	HR	6.0000	3.0000	-50.00%	4.0000	-33.33%	10.0000	66.67%
			4,800.00	2,400.00	-2,400.00	3,200.00	-1,600.00	8,000.00	3,200.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	LOW BIDDER	2ND BIDDER	3RD BIDDER
	TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
	350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
	98004-5732	PO BOX 1330	
	BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
	CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF. / AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF. / AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF. / AMT.DIFF.
	TRAFFIC								
155	PORTABLE CHANGEABLE MESSAGE SIGN								
	2.0000	EACH	4,100.0000	2,500.0000	-39.02%	10,000.0000	143.90%	22,512.0000	449.07%
			8,200.00	5,000.00	-3,200.00	20,000.00	11,800.00	45,024.00	36,824.00
156	OPERATION OF PORTABLE CHANGEABLE MESSAGE SIGN								
	4800.0000	HR	3.0000	3.0000	0.00%	0.5000	-83.33%	4.0000	33.33%
			14,400.00	14,400.00	0.00	2,400.00	-12,000.00	19,200.00	4,800.00
157	OTHER TEMPORARY TRAFFIC CONTROL								
		L.S.			247.38%		-72.21%		-53.68%
			43,180.00	150,000.00	106,820.00	12,000.00	-31,180.00	20,000.00	-23,180.00
158	FLAGGERS AND SPOTTERS								
	3600.0000	HR	20.0000	36.0000	80.00%	35.0000	75.00%	42.0000	110.00%
			72,000.00	129,600.00	57,600.00	126,000.00	54,000.00	151,200.00	79,200.00
159	OTHER TRAFFIC CONTROL LABOR								
	3888.0000	HR	45.0000	36.0000	-20.00%	40.0000	-11.11%	56.0000	24.44%
			174,960.00	139,968.00	-34,992.00	155,520.00	-19,440.00	217,728.00	42,768.00
160	TRAFFIC CONTROL SUPERVISOR								
		L.S.			11.11%		-86.67%		-55.56%
			90,000.00	100,000.00	10,000.00	12,000.00	-78,000.00	40,000.00	-50,000.00
161	CONSTRUCTION SIGNS CLASS A								
	770.0000	S.F.	9.0000	15.0000	66.67%	20.0000	122.22%	20.0000	122.22%
			6,930.00	11,550.00	4,620.00	15,400.00	8,470.00	15,400.00	8,470.00
162	PLASTIC HOV LANE SYMBOL								
	11.0000	EACH	180.0000	155.0000	-13.89%	155.0000	-13.89%	200.0000	11.11%
			1,980.00	1,705.00	-275.00	1,705.00	-275.00	2,200.00	220.00
	OTHER ITEMS								
163	TYPE C PROGRESS SCHEDULE								
		L.S.			150.00%		0.00%		200.00%
			10,000.00	25,000.00	15,000.00	10,000.00	0.00	30,000.00	20,000.00
164	STRUCTURE EXCAVATION CLASS B INCL. HAUL								
	1850.0000	C.Y.	25.0000	20.0000	-20.00%	12.0000	-52.00%	18.0000	-28.00%
			46,250.00	37,000.00	-9,250.00	22,200.00	-24,050.00	33,300.00	-12,950.00

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

------- LOW BIDDER -------	------- 2ND BIDDER -------	------- 3RD BIDDER -------
TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
98004-5732	PO BOX 1330	
BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF. / AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF. / AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF. / AMT.DIFF.
	OTHER ITEMS								
165	SHORING OR EXTRA EXCAVATION CLASS B								
	9600.0000	S.F.	5.0000	0.5000	-90.00%	1.0000	-80.00%	2.2500	-55.00%
			48,000.00	4,800.00	-43,200.00	9,600.00	-38,400.00	21,600.00	-26,400.00
166	CURE BOX								
		L.S.			50.00%		150.00%		700.00%
			1,000.00	1,500.00	500.00	2,500.00	1,500.00	8,000.00	7,000.00
167	PLUGGING EXISTING PIPE								
	2.0000	EACH	300.0000	350.0000	16.67%	300.0000	0.00%	250.0000	-16.67%
			600.00	700.00	100.00	600.00	0.00	500.00	-100.00
168	STRUCTURE SURVEYING								
		L.S.			-20.00%		-50.00%		9.60%
			50,000.00	40,000.00	-10,000.00	25,000.00	-25,000.00	54,800.00	4,800.00
169	ROADWAY SURVEYING								
		L.S.			-25.00%		-37.50%		-40.06%
			80,000.00	60,000.00	-20,000.00	50,000.00	-30,000.00	47,950.00	-32,050.00
170	CEMENT CONC. SIDEWALK								
	50.0000	S.Y.	60.0000	60.0000	0.00%	35.0000	-41.67%	50.0000	-16.67%
			3,000.00	3,000.00	0.00	1,750.00	-1,250.00	2,500.00	-500.00
171	CEMENT CONC. SIDEWALK RAMP TYPE 1B								
	1.0000	EACH	2,000.0000	2,000.0000	0.00%	1,500.0000	-25.00%	1,500.0000	-25.00%
			2,000.00	2,000.00	0.00	1,500.00	-500.00	1,500.00	-500.00
172	CONC. SLOPE PROTECTION								
	35.0000	S.Y.	75.0000	250.0000	233.33%	165.0000	120.00%	60.0000	-20.00%
			2,625.00	8,750.00	6,125.00	5,775.00	3,150.00	2,100.00	-525.00
173	CHAIN LINK FENCE TYPE 3								
	271.0000	L.F.	20.0000	20.0000	0.00%	20.0000	0.00%	18.0000	-10.00%
			5,420.00	5,420.00	0.00	5,420.00	0.00	4,878.00	-542.00
174	CHAIN LINK FENCE TYPE 4								
	1621.0000	L.F.	15.0000	15.0000	0.00%	12.0000	-20.00%	12.0000	-20.00%
			24,315.00	24,315.00	0.00	19,452.00	-4,863.00	19,452.00	-4,863.00
175	END, GATE, CORNER, AND PULL POST FOR CHAIN LINK FENCE								
	18.0000	EACH	250.0000	200.0000	-20.00%	200.0000	-20.00%	200.0000	-20.00%
			4,500.00	3,600.00	-900.00	3,600.00	-900.00	3,600.00	-900.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	LOW BIDDER	2ND BIDDER	3RD BIDDER
	TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
	350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
	98004-5732	PO BOX 1330	
	BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
	CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF. / AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF. / AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF. / AMT.DIFF.
	OTHER ITEMS								
176	GRAVITY BLOCK WALL								
	387.0000	S.F.	30.0000	20.0000	-33.33%	35.0000	16.67%	25.0000	-16.67%
			11,610.00	7,740.00	-3,870.00	13,545.00	1,935.00	9,675.00	-1,935.00
177	CONNECTION TO DRAINAGE STRUCTURE								
	6.0000	EACH	2,000.0000	750.0000	-62.50%	500.0000	-75.00%	200.0000	-90.00%
			12,000.00	4,500.00	-7,500.00	3,000.00	-9,000.00	1,200.00	-10,800.00
178	ADJUST CATCH BASIN								
	7.0000	EACH	500.0000	300.0000	-40.00%	500.0000	0.00%	600.0000	20.00%
			3,500.00	2,100.00	-1,400.00	3,500.00	0.00	4,200.00	700.00
179	LOCKING SOLID METAL COVER AND FRAME FOR CATCH BASIN								
	11.0000	EACH	400.0000	200.0000	-50.00%	500.0000	25.00%	1,000.0000	150.00%
			4,400.00	2,200.00	-2,200.00	5,500.00	1,100.00	11,000.00	6,600.00
180	CLEANING EXISTING DRAINAGE STRUCTURE								
		L.S.			-25.00%		150.00%		25.00%
			4,000.00	3,000.00	-1,000.00	10,000.00	6,000.00	5,000.00	1,000.00
181	FORCE ACCOUNT FOR TEMPORARY SIGNAL REMOVAL								
		EST.			0.00%		0.00%		0.00%
			50,000.00	50,000.00		50,000.00		50,000.00	
182	FORCE ACCOUNT FOR MINOR ELECTRICAL REPAIR WORK								
		EST.			0.00%		0.00%		0.00%
			20,000.00	20,000.00		20,000.00		20,000.00	
183	FORCE ACCOUNT FOR POTHOLING								
		EST.			0.00%		0.00%		0.00%
			20,000.00	20,000.00		20,000.00		20,000.00	
184	FORCE ACCOUNT FOR UNIDENTIFIED UTILITIES								
		EST.			0.00%		0.00%		0.00%
			20,000.00	20,000.00		20,000.00		20,000.00	
185	FORCE ACCOUNT FOR OFFSITE DRAINAGE								
		EST.			0.00%		0.00%		0.00%
			20,000.00	20,000.00		20,000.00		20,000.00	
186	ROADSIDE CLEANUP								
		EST.			0.00%		0.00%		0.00%
			10,000.00	10,000.00		10,000.00		10,000.00	

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

------- LOW BIDDER -------	------- 2ND BIDDER -------	------- 3RD BIDDER -------
TRI-STATE CONSTRUCTION, INC.	MOWAT CONSTRUCTION COMPANY	BILFINGER BERGER CIVIL INC.
350 - 106TH AVE NE	20210 142ND AVE NE 98072	1000 SE TECH CENTER DR STE 17(
98004-5732	PO BOX 1330	
BELLEVUE WA 980093686	WOODINVILLE WA 980721330	VANCOUVER WA 986835549
CONTRACTOR NUMBER : 829961	CONTRACTOR NUMBER : 551010	CONTRACTOR NUMBER : 100437

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER PRICE PER UNIT / TOTAL AMOUNT	LOW BIDDER % DIFF. / AMT.DIFF.	2ND BIDDER PRICE PER UNIT / TOTAL AMOUNT	2ND BIDDER % DIFF. / AMT.DIFF.	3RD BIDDER PRICE PER UNIT / TOTAL AMOUNT	3RD BIDDER % DIFF. / AMT.DIFF.
	OTHER ITEMS								
187	REIMBURSEMENT FOR THIRD PARTY DAMAGE								
		EST.			0.00%		0.00%		0.00%
			5.00	5.00		5.00		5.00	
188	MINOR CHANGE								
		CALC			0.00%		0.00%		0.00%
			-1.00	-1.00		-1.00		-1.00	
189	FUEL COST ADJUSTMENT								
		CALC			0.00%		0.00%		0.00%
			6,100.00	6,100.00		6,100.00		6,100.00	
190	AGGREGATE COMPLIANCE PRICE ADJUSTMENT								
		CALC			0.00%		0.00%		0.00%
			69,798.00	69,798.00		69,798.00		69,798.00	
191	SPCC PLAN								
		L.S.			400.00%		25.00%		25.00%
			4,000.00	20,000.00	16,000.00	5,000.00	1,000.00	5,000.00	1,000.00
192	CONSTRUCTION GEOTEXTILE FOR UNDERGROUND DRAINAGE								
	1190.0000	S.Y.	3.0000	3.0000	0.00%	5.0000	66.67%	1.5000	-50.00%
			3,570.00	3,570.00	0.00	5,950.00	2,380.00	1,785.00	-1,785.00
193	PLASTIC CROSSWALK LINE								
	440.0000	S.F.	5.0000	6.0000	20.00%	6.0000	20.00%	6.0000	20.00%
			2,200.00	2,640.00	440.00	2,640.00	440.00	2,640.00	440.00
194	WILDFLOWER SEEDING AND MULCHING								
	1.8800	ACRE	2,200.0000	2,000.0000	-9.09%	2,100.0000	-4.55%	1,550.0000	-29.55%
			4,136.00	3,760.00	-376.00	3,948.00	-188.00	2,914.00	-1,222.00
	CONTRACT TOTAL		$10,849,265.00	$9,987,659.00	-7.94%	$10,280,552.50	-5.24%	$10,944,341.00	0.88%
	BASE TOTAL		$10,849,265.00	$9,987,659.00	-7.94%	$10,280,552.50	-5.24%	$10,944,341.00	0.88%

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	4TH BIDDER	5TH BIDDER
	WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
	1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
	EVERETT WA 982011927	RENTON WA 980561057
	CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	PREPARATION						
1	MOBILIZATION						
		L.S.			2.87%		12.82%
			975,000.00	1,003,000.00	28,000.00	1,100,000.00	125,000.00
2	CLEARING AND GRUBBING						
	10.9000	ACRE	5,000.0000	7,400.0000	48.00%	4,000.0000	-20.00%
			54,500.00	80,660.00	26,160.00	43,600.00	-10,900.00
3	REMOVING DRAINAGE STRUCTURE						
	7.0000	EACH	400.0000	400.0000	0.00%	1,500.0000	275.00%
			2,800.00	2,800.00	0.00	10,500.00	7,700.00
4	REMOVING DRAINAGE PIPE						
	737.0000	L.F.	25.0000	9.0000	-64.00%	52.0000	108.00%
			18,425.00	6,633.00	-11,792.00	38,324.00	19,899.00
5	REMOVAL OF STRUCTURE AND OBSTRUCTION						
		L.S.			91.97%		-60.00%
			5,000.00	9,598.50	4,598.50	2,000.00	-3,000.00
6	REMOVING CEMENT CONC. SIDEWALK						
	777.0000	S.Y.	15.0000	10.0000	-33.33%	27.0000	80.00%
			11,655.00	7,770.00	-3,885.00	20,979.00	9,324.00
7	REMOVING CEMENT CONC. CURB AND GUTTER						
	1360.0000	L.F.	8.0000	5.0000	-37.50%	12.0000	50.00%
			10,880.00	6,800.00	-4,080.00	16,320.00	5,440.00
8	REMOVING ASPHALT CONC. PAVEMENT						
	5484.0000	S.Y.	7.0000	5.0000	-28.57%	15.0000	114.29%
			38,388.00	27,420.00	-10,968.00	82,260.00	43,872.00
9	REMOVING GUARDRAIL						
	120.0000	L.F.	8.0000	3.0000	-62.50%	4.8500	-39.38%
			960.00	360.00	-600.00	582.00	-378.00
10	REMOVING GUARDRAIL ANCHOR						
	3.0000	EACH	250.0000	200.0000	-20.00%	190.0000	-24.00%
			750.00	600.00	-150.00	570.00	-180.00
11	REMOVING GUIDE POST						
	8.0000	EACH	10.0000	10.0000	0.00%	6.5000	-35.00%
			80.00	80.00	0.00	52.00	-28.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	4TH BIDDER	5TH BIDDER
	WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
	1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
	EVERETT WA 982011927	RENTON WA 980561057
	CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	PREPARATION						
12	REMOVING PAINT LINE						
	1450.0000	L.F.	0.5000	0.5000	0.00%	0.5000	0.00%
			725.00	725.00	0.00	725.00	0.00
13	REMOVING PLASTIC TRAFFIC MARKING						
	12.0000	EACH	100.0000	60.0000	-40.00%	35.0000	-65.00%
			1,200.00	720.00	-480.00	420.00	-780.00
14	REMOVING RAISED PAVEMENT MARKER						
	11.1000	HUND	100.0000	120.0000	20.00%	100.0000	0.00%
			1,110.00	1,332.00	222.00	1,110.00	0.00
15	REMOVING CHAIN LINK FENCE						
	1910.0000	L.F.	3.0000	3.0000	0.00%	4.0000	33.33%
			5,730.00	5,730.00	0.00	7,640.00	1,910.00
16	HIGH VISIBILITY CONSTRUCTION FENCING						
	3720.0000	L.F.	4.0000	3.0000	-25.00%	5.0000	25.00%
			14,880.00	11,160.00	-3,720.00	18,600.00	3,720.00
	GRADING						
17	POND EXCAVATION INCL. HAUL						
	12170.0000	C.Y.	22.0000	21.0000	-4.55%	41.0000	86.36%
			267,740.00	255,570.00	-12,170.00	498,970.00	231,230.00
18	ROADWAY EXCAVATION INCL. HAUL						
	6210.0000	C.Y.	30.0000	25.0000	-16.67%	44.0000	46.67%
			186,300.00	155,250.00	-31,050.00	273,240.00	86,940.00
19	GRAVEL BORROW INCL. HAUL						
	84260.0000	TON	12.0000	15.0000	25.00%	1.0000	-91.67%
			1,011,120.00	1,263,900.00	252,780.00	84,260.00	-926,860.00
20	EMBANKMENT COMPACTION						
	47930.0000	C.Y.	5.0000	5.0000	0.00%	24.0000	380.00%
			239,650.00	239,650.00	0.00	1,150,320.00	910,670.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

4TH BIDDER	5TH BIDDER
WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
EVERETT WA 982011927	RENTON WA 980561057
CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	DRAINAGE						
21	ECOLOGY MIX						
	40.0000	C.Y.	40.0000	110.0000	175.00%	60.0000	50.00%
			1,600.00	4,400.00	2,800.00	2,400.00	800.00
22	COMPACTED TILL LINER						
	1010.0000	TON	20.0000	20.0000	0.00%	20.0000	0.00%
			20,200.00	20,200.00	0.00	20,200.00	0.00
23	DITCH EXCAVATION INCL. HAUL						
	1130.0000	C.Y.	18.0000	27.0000	50.00%	25.0000	38.89%
			20,340.00	30,510.00	10,170.00	28,250.00	7,910.00
24	GRATE INLET TYPE 1						
	1.0000	EACH	3,000.0000	3,400.0000	13.33%	1,500.0000	-50.00%
			3,000.00	3,400.00	400.00	1,500.00	-1,500.00
25	QUARRY SPALLS						
	170.0000	TON	40.0000	55.0000	37.50%	45.0000	12.50%
			6,800.00	9,350.00	2,550.00	7,650.00	850.00
26	UNDERDRAIN PIPE 6 IN. DIAM.						
	648.0000	L.F.	24.0000	5.0000	-79.17%	12.0000	-50.00%
			15,552.00	3,240.00	-12,312.00	7,776.00	-7,776.00
27	DRAIN PIPE 6 IN. DIAM.						
	56.0000	L.F.	25.0000	21.0000	-16.00%	15.0000	-40.00%
			1,400.00	1,176.00	-224.00	840.00	-560.00
28	SCHEDULE A CULV. PIPE 18 IN. DIAM.						
	37.0000	L.F.	40.0000	44.0000	10.00%	50.0000	25.00%
			1,480.00	1,628.00	148.00	1,850.00	370.00
	STORM SEWER						
29	CATCH BASIN TYPE 2 48 IN DIAM WITH JAIL HOUSE GRATE						
	1.0000	EACH	5,000.0000	3,400.0000	-32.00%	2,700.0000	-46.00%
			5,000.00	3,400.00	-1,600.00	2,700.00	-2,300.00
30	CATCH BASIN TYPE 1						
	7.0000	EACH	1,600.0000	1,300.0000	-18.75%	1,500.0000	-6.25%
			11,200.00	9,100.00	-2,100.00	10,500.00	-700.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

------- 4TH BIDDER -------	------- 5TH BIDDER -------
WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
EVERETT WA 982011927	RENTON WA 980561057
CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT/ TOTAL AMOUNT	PRICE PER UNIT/ TOTAL AMOUNT	% DIFF./ AMT.DIFF.	PRICE PER UNIT/ TOTAL AMOUNT	% DIFF./ AMT.DIFF.
	STORM SEWER						
31	CATCH BASIN TYPE 2 48 IN. DIAM.						
	16.0000	EACH	4,000.0000	2,600.0000	-35.00%	2,500.0000	-37.50%
			64,000.00	41,600.00	-22,400.00	40,000.00	-24,000.00
32	TESTING STORM SEWER PIPE						
	1902.0000	L.F.	3.0000	3.0000	0.00%	2.0000	-33.33%
			5,706.00	5,706.00	0.00	3,804.00	-1,902.00
33	CL. V REINF. CONC. STORM SEWER PIPE 12 IN. DIAM.						
	121.0000	L.F.	60.0000	48.0000	-20.00%	22.0000	-63.33%
			7,260.00	5,808.00	-1,452.00	2,662.00	-4,598.00
34	CL. V REINF. CONC. STORM SEWER PIPE 18 IN. DIAM.						
	125.0000	L.F.	75.0000	78.0000	4.00%	25.0000	-66.67%
			9,375.00	9,750.00	375.00	3,125.00	-6,250.00
35	SCHEDULE A STORM SEWER PIPE 12 IN. DIAM.						
	873.0000	L.F.	40.0000	42.0000	5.00%	18.0000	-55.00%
			34,920.00	36,666.00	1,746.00	15,714.00	-19,206.00
36	SCHEDULE A STORM SEWER PIPE 18 IN. DIAM.						
	475.0000	L.F.	50.0000	28.0000	-44.00%	22.0000	-56.00%
			23,750.00	13,300.00	-10,450.00	10,450.00	-13,300.00
37	SCHEDULE A STORM SEWER PIPE 24 IN. DIAM.						
	290.0000	L.F.	70.0000	58.0000	-17.14%	24.0000	-65.71%
			20,300.00	16,820.00	-3,480.00	6,960.00	-13,340.00
38	SCHEDULE A STORM SEWER PIPE 30 IN. DIAM.						
	18.0000	L.F.	90.0000	87.0000	-3.33%	40.0000	-55.56%
			1,620.00	1,566.00	-54.00	720.00	-900.00
	STRUCTURE						
39	SEW REDMOND FINISH						
	7088.0000	S.F.	12.0000	7.0000	-41.67%	26.5000	120.83%
			85,056.00	49,616.00	-35,440.00	187,832.00	102,776.00
40	SEW RANDOM BOARD FINISH						
	1084.0000	S.F.	4.0000	11.0000	175.00%	26.5000	562.50%
			4,336.00	11,924.00	7,588.00	28,726.00	24,390.00

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	4TH BIDDER	5TH BIDDER
	WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
	1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
	EVERETT WA 982011927	RENTON WA 980561057
	CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	STRUCTURE						
41	STRUCTURE EXCAVATION CLASS A INCL. HAUL						
	2246.0000	C.Y.	25.0000	26.0000	4.00%	60.0000	140.00%
			56,150.00	58,396.00	2,246.00	134,760.00	78,610.00
42	SHORING OR EXTRA EXCAVATION CL. A FLYOVER RAMP						
		L.S.			370.34%		164.83%
			47,200.00	222,000.00	174,800.00	125,000.00	77,800.00
43	GRAVEL BACKFILL FOR WALL						
	460.0000	TON	32.0000	20.0000	-37.50%	24.0000	-25.00%
			14,720.00	9,200.00	-5,520.00	11,040.00	-3,680.00
44	ST. REINF. BAR FOR BRIDGE						
	256200.0000	LB.	1.0000	1.2000	20.00%	0.8500	-15.00%
			256,200.00	307,440.00	51,240.00	217,770.00	-38,430.00
45	ST. REINF. BAR FOR RETAINING WALL						
	12480.0000	LB.	1.0000	1.2000	20.00%	0.8500	-15.00%
			12,480.00	14,976.00	2,496.00	10,608.00	-1,872.00
46	CONC. CLASS 3000 FOR GUTTER BEHIND WALL BL6						
	4.4000	C.Y.	575.0000	780.0000	35.65%	700.0000	21.74%
			2,530.00	3,432.00	902.00	3,080.00	550.00
47	CONC. CLASS 4000 FOR BRIDGE						
	1390.0000	C.Y.	500.0000	470.0000	-6.00%	573.0000	14.60%
			695,000.00	653,300.00	-41,700.00	796,470.00	101,470.00
48	CONC. CLASS 4000 FOR RETAINING WALL						
	153.2000	C.Y.	610.0000	890.0000	45.90%	775.0000	27.05%
			93,452.00	136,348.00	42,896.00	118,730.00	25,278.00
49	PRESTRESSED CONC. GIRDER WF74G						
	2117.0000	L.F.	230.0000	330.0000	43.48%	350.0000	52.17%
			486,910.00	698,610.00	211,700.00	740,950.00	254,040.00
50	SUPERSTRUCTURE BL LINE RAMP OVER SR 202						
		L.S.			0.36%		0.62%
			966,000.00	969,500.00	3,500.00	972,000.00	6,000.00
51	BRIDGE RAILING TYPE BP						
	1890.0000	L.F.	100.0000	55.0000	-45.00%	55.0000	-45.00%
			189,000.00	103,950.00	-85,050.00	103,950.00	-85,050.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	4TH BIDDER	5TH BIDDER
	WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
	1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
	EVERETT WA 982011927	RENTON WA 980561057
	CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	STRUCTURE						
52	TRAFFIC BARRIER						
	970.0000	L.F.	100.0000	88.0000	-12.00%	180.0000	80.00%
			97,000.00	85,360.00	-11,640.00	174,600.00	77,600.00
53	PEDESTRIAN BARRIER						
	34.3000	L.F.	155.0000	150.0000	-3.23%	60.0000	-61.29%
			5,316.50	5,145.00	-171.50	2,058.00	-3,258.50
54	SEW TRAFFIC BARRIER						
	512.0000	L.F.	308.0000	350.0000	13.64%	195.0000	-36.69%
			157,696.00	179,200.00	21,504.00	99,840.00	-57,856.00
55	STRUCTURAL EARTH WALL						
	8172.0000	S.F.	23.0000	35.0000	52.17%	24.0000	4.35%
			187,956.00	286,020.00	98,064.00	196,128.00	8,172.00
56	BACKFILL FOR STRUCTURAL EARTH WALL INCL. HAUL						
	9460.0000	TON	20.0000	17.0000	-15.00%	34.0000	70.00%
			189,200.00	160,820.00	-28,380.00	321,640.00	132,440.00
	SURFACING						
57	PERMEABLE BASE COURSE AGGREGATE						
	1070.0000	TON	30.0000	35.0000	16.67%	35.0000	16.67%
			32,100.00	37,450.00	5,350.00	37,450.00	5,350.00
58	SHOULDER BALLAST						
	3550.0000	TON	25.0000	27.0000	8.00%	29.0000	16.00%
			88,750.00	95,850.00	7,100.00	102,950.00	14,200.00
59	CRUSHED SURFACING BASE COURSE						
	7400.0000	TON	24.0000	27.0000	12.50%	27.0000	12.50%
			177,600.00	199,800.00	22,200.00	199,800.00	22,200.00

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

4TH BIDDER	5TH BIDDER
WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
EVERETT WA 982011927	RENTON WA 980561057
CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	LIQUID ASPHALT						
60	ANTI-STRIPPING ADDITIVE						
		EST.			0.00%		0.00%
			5,010.00	5,010.00		5,010.00	
	CEMENT CONCRETE PAVEMENT						
61	BRIDGE APPROACH SLAB						
	263.0000	S.Y.	225.0000	330.0000	46.67%	140.0000	-37.78%
			59,175.00	86,790.00	27,615.00	36,820.00	-22,355.00
	HOT MIX ASPHALT						
62	PERVIOUS HMA CL 3/4 IN. PG 58-22						
	600.0000	TON	120.0000	115.0000	-4.17%	105.0000	-12.50%
			72,000.00	69,000.00	-3,000.00	63,000.00	-9,000.00
63	CRACK SEALING						
		EST.			0.00%		0.00%
			5,000.00	5,000.00		5,000.00	
64	PLANING BITUMINOUS PAVEMENT						
	1601.0000	S.Y.	10.0000	6.0000	-40.00%	6.0000	-40.00%
			16,010.00	9,606.00	-6,404.00	9,606.00	-6,404.00
65	HMA FOR PAVEMENT REPAIR CL. 1/2 IN. PG 68-22						
	200.0000	TON	100.0000	85.0000	-15.00%	75.0000	-25.00%
			20,000.00	17,000.00	-3,000.00	15,000.00	-5,000.00
66	HMA CL. 1/2 IN. PG 68-22						
	7530.0000	TON	80.0000	67.0000	-16.25%	62.0000	-22.50%
			602,400.00	504,510.00	-97,890.00	466,860.00	-135,540.00
67	JOB MIX COMPLIANCE PRICE ADJUSTMENT						
		CALC			0.00%		0.00%
			9,882.00	9,882.00		9,882.00	
68	COMPACTION PRICE ADJUSTMENT						
		CALC			0.00%		0.00%
			6,588.00	6,588.00		6,588.00	

PS&E JOB NO : 06A026 REVISION NO : 5 BIDS OPENED ON : Mar 7 2007
CONTRACT NO : 007272 REGION NO : 1 AWARDED ON : Mar 16 2007
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

------- 4TH BIDDER -------	------- 5TH BIDDER -------
WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
EVERETT WA 982011927	RENTON WA 980561057
CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	HOT MIX ASPHALT						
69	ASPHALT COST PRICE ADJUSTMENT						
		CALC			0.00%		0.00%
			1,311.00	1,311.00		1,311.00	
70	HMA FOR APPROACH CL. 1/2 IN. PG 68-22						
	220.0000	TON	90.0000	90.0000	0.00%	85.0000	-5.56%
			19,800.00	19,800.00	0.00	18,700.00	-1,100.00
71	CYCLIC DENSITY PRICE ADJUSTMENT						
		CALC			0.00%		0.00%
			-1.00	-1.00		-1.00	
72	SMOOTHNESS COMPLIANCE ADJUSTMENT						
		CALC			0.00%		0.00%
			1.00	1.00		1.00	
	EROSION CONTROL AND PLANTING						
73	WET NATIVE SEEDING AND MULCHING						
	0.4100	ACRE	4,300.0000	7,200.0000	67.44%	8,000.0000	86.05%
			1,763.00	2,952.00	1,189.00	3,280.00	1,517.00
74	STRUCTURAL SOIL MIX						
	358.0000	C.Y.	38.5000	41.0000	6.49%	60.0000	55.84%
			13,783.00	14,678.00	895.00	21,480.00	7,697.00
75	2"-4" QUARRY ROCK						
	20.0000	TON	40.0000	37.0000	-7.50%	45.0000	12.50%
			800.00	740.00	-60.00	900.00	100.00
76	GRAVEL BACKFILL FOR DRYWELLS						
	20.0000	TON	35.0000	31.0000	-11.43%	70.0000	100.00%
			700.00	620.00	-80.00	1,400.00	700.00
77	ESC LEAD						
	180.0000	DAY	170.0000	170.0000	0.00%	100.0000	-41.18%
			30,600.00	30,600.00	0.00	18,000.00	-12,600.00
78	CHECK DAM						
	24.0000	L.F.	55.0000	12.0000	-78.18%	200.0000	263.64%
			1,320.00	288.00	-1,032.00	4,800.00	3,480.00

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	4TH BIDDER	5TH BIDDER
	WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
	1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
	EVERETT WA 982011927	RENTON WA 980561057
	CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	EROSION CONTROL AND PLANTING						
79	STABILIZED CONSTRUCTION ENTRANCE						
	1150.0000	S.Y.	20.0000	16.0000	-20.00%	20.0000	0.00%
			23,000.00	18,400.00	-4,600.00	23,000.00	0.00
80	STREET CLEANING						
	1600.0000	HR	140.0000	0.0100	-99.99%	105.0000	-25.00%
			224,000.00	16.00	-223,984.00	168,000.00	-56,000.00
81	INLET PROTECTION						
	38.0000	EACH	80.0000	97.0000	21.25%	200.0000	150.00%
			3,040.00	3,686.00	646.00	7,600.00	4,560.00
82	SILT FENCE						
	2600.0000	L.F.	5.0000	5.0000	0.00%	8.0000	60.00%
			13,000.00	13,000.00	0.00	20,800.00	7,800.00
83	COMPOST SOCK						
	974.0000	L.F.	10.0000	9.0000	-10.00%	8.0000	-20.00%
			9,740.00	8,766.00	-974.00	7,792.00	-1,948.00
84	EROSION/WATER POLLUTION CONTROL						
		EST.			0.00%		0.00%
			450,000.00	450,000.00		450,000.00	
85	TEMPORARY CURB						
	130.0000	L.F.	7.5000	9.0000	20.00%	20.0000	166.67%
			975.00	1,170.00	195.00	2,600.00	1,625.00
86	TEMPORARY PIPE SLOPE DRAIN						
	991.0000	L.F.	20.0000	7.0000	-65.00%	25.0000	25.00%
			19,820.00	6,937.00	-12,883.00	24,775.00	4,955.00
87	SEEDING, FERTILIZING, AND MULCHING						
	0.8600	ACRE	1,800.0000	1,500.0000	-16.67%	1,200.0000	-33.33%
			1,548.00	1,290.00	-258.00	1,032.00	-516.00
88	TOPSOIL TYPE A						
	1746.0000	C.Y.	40.0000	50.0000	25.00%	54.0000	35.00%
			69,840.00	87,300.00	17,460.00	94,284.00	24,444.00
89	PLANT SELECTION SLOUGH SEDGE, BARE ROOT						
	425.0000	EACH	1.5000	2.0000	33.33%	2.0000	33.33%
			637.50	850.00	212.50	850.00	212.50

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	4TH BIDDER	5TH BIDDER
	WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
	1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
	EVERETT WA 982011927	RENTON WA 980561057
	CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	EROSION CONTROL AND PLANTING						
90	PLANT SELECTION SOFTSTEM BULRUSH, BARE ROOT						
	425.0000	EACH	1.5000	2.0000	33.33%	2.0000	33.33%
			637.50	850.00	212.50	850.00	212.50
91	PLANT SELECTION SLENDER RUSH, BARE ROOT						
	1050.0000	EACH	1.5000	2.0000	33.33%	2.0000	33.33%
			1,575.00	2,100.00	525.00	2,100.00	525.00
92	PLANT SELECTION SMALL FRUITED BULRUSH, BARE ROOT						
	1475.0000	EACH	1.5000	2.0000	33.33%	2.0000	33.33%
			2,212.50	2,950.00	737.50	2,950.00	737.50
93	PLANT SELECTION HARDSTEM BULRUSH BARE ROOT						
	1175.0000	EACH	1.5000	2.0000	33.33%	2.0000	33.33%
			1,762.50	2,350.00	587.50	2,350.00	587.50
94	PSIPE BOWHALL RED MAPLE, 2" CAL., B&B						
	9.0000	EACH	238.0000	315.0000	32.35%	300.0000	26.05%
			2,142.00	2,835.00	693.00	2,700.00	558.00
95	PSIPE DEODAR CEDAR, 4' HT, B&B						
	64.0000	EACH	76.2500	110.0000	44.26%	105.0000	37.70%
			4,880.00	7,040.00	2,160.00	6,720.00	1,840.00
96	PSIPE DOUGLAS FIR, 4' HT, B&B						
	47.0000	EACH	46.0000	90.0000	95.65%	85.0000	84.78%
			2,162.00	4,230.00	2,068.00	3,995.00	1,833.00
97	PSIPE RED SUNSET MAPLE, 2" CAL, B&B						
	22.0000	EACH	240.0000	315.0000	31.25%	300.0000	25.00%
			5,280.00	6,930.00	1,650.00	6,600.00	1,320.00
98	PSIPE BOSTON IVY, 10" RUNNER, #1 CONT.						
	34.0000	EACH	12.0000	11.0000	-8.33%	11.0000	-8.33%
			408.00	374.00	-34.00	374.00	-34.00
99	PSIPE WESTERN RED CEDAR 4' HT, B&B						
	54.0000	EACH	66.2500	85.0000	28.30%	85.0000	28.30%
			3,577.50	4,590.00	1,012.50	4,590.00	1,012.50
100	PSIPE CORALBERRY, 9" HT., #1 CONT.						
	1444.0000	EACH	6.0000	11.0000	83.33%	9.0000	50.00%
			8,664.00	15,884.00	7,220.00	12,996.00	4,332.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	4TH BIDDER	5TH BIDDER
	WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
	1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
	EVERETT WA 982011927	RENTON WA 980561057
	CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	EROSION CONTROL AND PLANTING						
101	PSIPE BEAKED HAZELNUT, 12" HT., #1 CONT.						
	34.0000	EACH	8.0000	12.0000	50.00%	11.0000	37.50%
			272.00	408.00	136.00	374.00	102.00
102	PSIPE RED ELDERBERRY, 12" HT., #1 CONT.						
	34.0000	EACH	8.0000	8.0000	0.00%	9.0000	12.50%
			272.00	272.00	0.00	306.00	34.00
103	PSIPE COMPACT OREGON GRAPE, 6" HT, #1 CONT.						
	89.0000	EACH	14.0000	11.0000	-21.43%	11.0000	-21.43%
			1,246.00	979.00	-267.00	979.00	-267.00
104	PSIPE SALMONBERRY, 12" HT., #1 CONT.						
	34.0000	EACH	8.0000	8.0000	0.00%	8.0000	0.00%
			272.00	272.00	0.00	272.00	0.00
105	PSIPE SERVICEBERRY, 12" HT., #1 CONT.						
	34.0000	EACH	11.0000	8.0000	-27.27%	8.0000	-27.27%
			374.00	272.00	-102.00	272.00	-102.00
106	PSIPE PRIVET HONEYSUCKLE, 12" HT., #1 CONT.						
	89.0000	EACH	9.5000	12.0000	26.32%	11.0000	15.79%
			845.50	1,068.00	222.50	979.00	133.50
107	PSIPE SHADBLOW SEVICEBERRY, 5' HT., 5 GAL. CONT.						
	45.0000	EACH	48.0000	57.0000	18.75%	38.0000	-20.83%
			2,160.00	2,565.00	405.00	1,710.00	-450.00
108	PSIPE RD-OSIER DOGWOOD, 12" HT, #1 CONT.						
	384.0000	EACH	6.7500	8.0000	18.52%	7.0000	3.70%
			2,592.00	3,072.00	480.00	2,688.00	96.00
109	PSIPE SITKA WILLOW, 36" HT., LIVE STAKE						
	120.0000	EACH	3.0000	6.0000	100.00%	5.0000	66.67%
			360.00	720.00	360.00	600.00	240.00
110	PLANT ESTABLISHMENT - SECOND YEAR						
		EST.			0.00%		0.00%
			12,500.00	12,500.00		12,500.00	
111	PLANT ESTABLISHMENT - THIRD YEAR						
		EST.			0.00%		0.00%
			12,500.00	12,500.00		12,500.00	

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	4TH BIDDER	5TH BIDDER
	WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
	1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
	EVERETT WA 982011927	RENTON WA 980561057
	CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	EROSION CONTROL AND PLANTING						
112	REMOVAL OF BURIED MAN-MADE DEBRIS						
		EST.			0.00%		0.00%
			1,000.00	1,000.00		1,000.00	
113	FINE COMPOST						
	197.0000	C.Y.	45.0000	40.0000	-11.11%	40.0000	-11.11%
			8,865.00	7,880.00	-985.00	7,880.00	-985.00
114	WEED CONTROL						
		EST.			0.00%		0.00%
			1,600.00	1,600.00		1,600.00	
115	SOIL AMENDMENT						
	608.0000	C.Y.	42.0000	47.0000	11.90%	35.0000	-16.67%
			25,536.00	28,576.00	3,040.00	21,280.00	-4,256.00
116	BARK OR WOOD CHIP MULCH						
	593.0000	C.Y.	31.5000	43.0000	36.51%	35.0000	11.11%
			18,679.50	25,499.00	6,819.50	20,755.00	2,075.50
117	WATER FOR EMERGENT PLANTS						
	30.0000	EACH	1,125.0000	530.0000	-52.89%	500.0000	-55.56%
			33,750.00	15,900.00	-17,850.00	15,000.00	-18,750.00
	TRAFFIC						
118	SENSITIVE AREA SIGN						
	20.0000	EACH	50.0000	15.0000	-70.00%	50.0000	0.00%
			1,000.00	300.00	-700.00	1,000.00	0.00
119	TEMPORARY SIGNAL DETECTION						
		L.S.			74.24%		74.55%
			13,200.00	23,000.00	9,800.00	23,040.00	9,840.00
120	TEMPORARY SIGNAL REMOVAL PLAN						
		L.S.			240.00%		-7.13%
			1,500.00	5,100.00	3,600.00	1,393.00	-107.00
121	BEAM GUARDRAIL TYPE 31 NON-FLARED TERMINAL						
	3.0000	EACH	2,500.0000	510.0000	-79.60%	2,215.0000	-11.40%
			7,500.00	1,530.00	-5,970.00	6,645.00	-855.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	4TH BIDDER	5TH BIDDER
	WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
	1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
	EVERETT WA 982011927	RENTON WA 980561057
	CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	TRAFFIC						
122	BEAM GUARDRAIL TYPE 31						
	303.0000	L.F.	40.0000	34.0000	-15.00%	23.0000	-42.50%
			12,120.00	10,302.00	-1,818.00	6,969.00	-5,151.00
123	CEMENT CONC. TRAFFIC CURB AND GUTTER						
	291.0000	L.F.	20.0000	28.0000	40.00%	25.0000	25.00%
			5,820.00	8,148.00	2,328.00	7,275.00	1,455.00
124	EXTRUDED CURB						
	1170.0000	L.F.	7.0000	5.0000	-28.57%	4.0000	-42.86%
			8,190.00	5,850.00	-2,340.00	4,680.00	-3,510.00
125	BEAM GUARDRAIL TYPE 1						
	888.0000	L.F.	35.0000	34.0000	-2.86%	21.0000	-40.00%
			31,080.00	30,192.00	-888.00	18,648.00	-12,432.00
126	BEAM GUARDRAIL TRANSITION SECTION TYPE 4						
	1.0000	EACH	1,200.0000	1,000.0000	-16.67%	615.0000	-48.75%
			1,200.00	1,000.00	-200.00	615.00	-585.00
127	BEAM GUARDRAIL TRANSITION SECTION TYPE 20						
	3.0000	EACH	1,500.0000	2,700.0000	80.00%	1,310.0000	-12.67%
			4,500.00	8,100.00	3,600.00	3,930.00	-570.00
128	BEAM GUARDRAIL NON-FLARED TERMINAL						
	1.0000	EACH	2,600.0000	3,500.0000	34.62%	2,135.0000	-17.88%
			2,600.00	3,500.00	900.00	2,135.00	-465.00
129	BEAM GUARDRAIL ANCHOR TYPE 1						
	1.0000	EACH	700.0000	1,000.0000	42.86%	630.0000	-10.00%
			700.00	1,000.00	300.00	630.00	-70.00
130	PRECAST SINGLE SLOPE CONC. BARRIER						
	1542.0000	L.F.	85.0000	75.0000	-11.76%	80.0000	-5.88%
			131,070.00	115,650.00	-15,420.00	123,360.00	-7,710.00
131	CAST IN PLACE SINGLE SLOPE CONC. BARRIER						
	1408.0000	L.F.	200.0000	85.0000	-57.50%	150.0000	-25.00%
			281,600.00	119,680.00	-161,920.00	211,200.00	-70,400.00
132	SINGLE SLOPE CONC. BARRIER LIGHT STANDARD FOUNDATION						
	5.0000	EACH	10,000.0000	8,600.0000	-14.00%	5,000.0000	-50.00%
			50,000.00	43,000.00	-7,000.00	25,000.00	-25,000.00

PS&E JOB NO : 06A026 REVISION NO : 5 BIDS OPENED ON : Mar 7 2007
CONTRACT NO : 007272 REGION NO : 1 AWARDED ON : Mar 16 2007
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

------- 4TH BIDDER -------	------- 5TH BIDDER -------
WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
EVERETT WA 982011927	RENTON WA 980561057
CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	TRAFFIC						
133	TEMPORARY CONC. BARRIER						
	3571.0000	L.F.	15.0000	13.0000	-13.33%	4.0000	-73.33%
			53,565.00	46,423.00	-7,142.00	14,284.00	-39,281.00
134	TEMPORARY IMPACT ATTENUATOR						
	4.0000	EACH	5,000.0000	1,300.0000	-74.00%	10,000.0000	100.00%
			20,000.00	5,200.00	-14,800.00	40,000.00	20,000.00
135	RESETTING IMPACT ATTENUATOR						
	2.0000	EACH	1,000.0000	640.0000	-36.00%	700.0000	-30.00%
			2,000.00	1,280.00	-720.00	1,400.00	-600.00
136	TRUCK-MOUNTED IMPACT ATTENUATOR						
	1.0000	EACH	15,000.0000	20,000.0000	33.33%	10,000.0000	-33.33%
			15,000.00	20,000.00	5,000.00	10,000.00	-5,000.00
137	OPERATION OF TRUCK-MOUNTED IMPACT ATTENUATOR						
	250.0000	HR	50.0000	71.0000	42.00%	50.0000	0.00%
			12,500.00	17,750.00	5,250.00	12,500.00	0.00
138	REPAIR TRUCK-MOUNTED IMPACT ATTENUATOR						
		EST.			0.00%		0.00%
			5,000.00	5,000.00		5,000.00	
139	FLEXIBLE GUIDE POST						
	4.0000	EACH	30.0000	31.0000	3.33%	26.0000	-13.33%
			120.00	124.00	4.00	104.00	-16.00
140	PLASTIC LINE						
	8648.0000	L.F.	1.7500	2.0000	14.29%	2.0000	14.29%
			15,134.00	17,296.00	2,162.00	17,296.00	2,162.00
141	PLASTIC WIDE LINE						
	3120.0000	L.F.	2.0000	3.5000	75.00%	3.2000	60.00%
			6,240.00	10,920.00	4,680.00	9,984.00	3,744.00
142	PLASTIC DOTTED WIDE LINE						
	250.0000	L.F.	2.0000	2.0000	0.00%	2.0000	0.00%
			500.00	500.00	0.00	500.00	0.00
143	PLASTIC STOP LINE						
	90.0000	L.F.	12.0000	12.0000	0.00%	12.0000	0.00%
			1,080.00	1,080.00	0.00	1,080.00	0.00

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	4TH BIDDER	5TH BIDDER
	WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
	1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
	EVERETT WA 982011927	RENTON WA 980561057
	CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	TRAFFIC						
144	PLASTIC TRAFFIC ARROW						
	29.0000	EACH	125.0000	125.0000	0.00%	120.0000	-4.00%
			3,625.00	3,625.00	0.00	3,480.00	-145.00
145	PLASTIC DRAINAGE MARKING						
	17.0000	EACH	20.0000	26.0000	30.00%	25.0000	25.00%
			340.00	442.00	102.00	425.00	85.00
146	RAISED PAVEMENT MARKER TYPE 1						
	17.7000	HUND	200.0000	170.0000	-15.00%	250.0000	25.00%
			3,540.00	3,009.00	-531.00	4,425.00	885.00
147	RAISED PAVEMENT MARKER TYPE 2						
	3.8000	HUND	200.0000	360.0000	80.00%	350.0000	75.00%
			760.00	1,368.00	608.00	1,330.00	570.00
148	TEMPORARY PAVEMENT MARKING						
	20000.0000	L.F.	1.0000	0.7000	-30.00%	0.4000	-60.00%
			20,000.00	14,000.00	-6,000.00	8,000.00	-12,000.00
149	PERMANENT SIGNING						
		L.S.			53.85%		31.19%
			25,999.00	40,000.00	14,001.00	34,107.00	8,108.00
150	CANTILEVER SIGN STRUCTURE NO. 1						
		L.S.			75.00%		56.63%
			40,000.00	70,000.00	30,000.00	62,653.00	22,653.00
151	ILLUMINATION SYSTEM SUA 4027						
		L.S.			7.83%		1.18%
			166,000.00	179,000.00	13,000.00	167,965.00	1,965.00
152	TRAFFIC DATA ACCUMULATION AND RAMP METERING SYSTEM 4027						
		L.S.			45.09%		34.48%
			148,188.00	215,000.00	66,812.00	199,276.00	51,088.00
153	TRAFFIC SIGNAL SYSTEM SUA 4027						
		L.S.			31.58%		9.14%
			15,200.00	20,000.00	4,800.00	16,590.00	1,390.00
154	SEQUENTIAL ARROW SIGN						
	800.0000	HR	6.0000	4.0000	-33.33%	10.0000	66.67%
			4,800.00	3,200.00	-1,600.00	8,000.00	3,200.00

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

	4TH BIDDER	5TH BIDDER
	WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
	1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
	EVERETT WA 982011927	RENTON WA 980561057
	CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	TRAFFIC						
155	PORTABLE CHANGEABLE MESSAGE SIGN						
	2.0000	EACH	4,100.0000	28,000.0000	582.93%	10,000.0000	143.90%
			8,200.00	56,000.00	47,800.00	20,000.00	11,800.00
156	OPERATION OF PORTABLE CHANGEABLE MESSAGE SIGN						
	4800.0000	HR	3.0000	2.0000	-33.33%	10.0000	233.33%
			14,400.00	9,600.00	-4,800.00	48,000.00	33,600.00
157	OTHER TEMPORARY TRAFFIC CONTROL						
		L.S.			-36.54%		38.95%
			43,180.00	27,400.00	-15,780.00	60,000.00	16,820.00
158	FLAGGERS AND SPOTTERS						
	3600.0000	HR	20.0000	41.0000	105.00%	1.0000	-95.00%
			72,000.00	147,600.00	75,600.00	3,600.00	-68,400.00
159	OTHER TRAFFIC CONTROL LABOR						
	3888.0000	HR	45.0000	41.0000	-8.89%	1.0000	-97.78%
			174,960.00	159,408.00	-15,552.00	3,888.00	-171,072.00
160	TRAFFIC CONTROL SUPERVISOR						
		L.S.			-33.56%		-98.33%
			90,000.00	59,800.00	-30,200.00	1,500.00	-88,500.00
161	CONSTRUCTION SIGNS CLASS A						
	770.0000	S.F.	9.0000	20.0000	122.22%	25.0000	177.78%
			6,930.00	15,400.00	8,470.00	19,250.00	12,320.00
162	PLASTIC HOV LANE SYMBOL						
	11.0000	EACH	180.0000	160.0000	-11.11%	100.0000	-44.44%
			1,980.00	1,760.00	-220.00	1,100.00	-880.00
	OTHER ITEMS						
163	TYPE C PROGRESS SCHEDULE						
		L.S.			0.00%		0.00%
			10,000.00	10,000.00	0.00	10,000.00	0.00
164	STRUCTURE EXCAVATION CLASS B INCL. HAUL						
	1850.0000	C.Y.	25.0000	0.0100	-99.96%	50.0000	100.00%
			46,250.00	18.50	-46,231.50	92,500.00	46,250.00

PS&E JOB NO : 06A026 REVISION NO : 5 BIDS OPENED ON : Mar 7 2007
CONTRACT NO : 007272 REGION NO : 1 AWARDED ON : Mar 16 2007
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

------- 4TH BIDDER -------	------- 5TH BIDDER -------
WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
EVERETT WA 982011927	RENTON WA 980561057
CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	OTHER ITEMS						
165	SHORING OR EXTRA EXCAVATION CLASS B						
	9600.0000	S.F.	5.0000	0.0100	-99.80%	10.0000	100.00%
			48,000.00	96.00	-47,904.00	96,000.00	48,000.00
166	CURE BOX						
		L.S.			330.00%		300.00%
			1,000.00	4,300.00	3,300.00	4,000.00	3,000.00
167	PLUGGING EXISTING PIPE						
	2.0000	EACH	300.0000	580.0000	93.33%	750.0000	150.00%
			600.00	1,160.00	560.00	1,500.00	900.00
168	STRUCTURE SURVEYING						
		L.S.			22.40%		-38.00%
			50,000.00	61,200.00	11,200.00	31,000.00	-19,000.00
169	ROADWAY SURVEYING						
		L.S.			12.50%		12.50%
			80,000.00	90,000.00	10,000.00	90,000.00	10,000.00
170	CEMENT CONC. SIDEWALK						
	50.0000	S.Y.	60.0000	39.0000	-35.00%	35.0000	-41.67%
			3,000.00	1,950.00	-1,050.00	1,750.00	-1,250.00
171	CEMENT CONC. SIDEWALK RAMP TYPE 1B						
	1.0000	EACH	2,000.0000	1,700.0000	-15.00%	1,500.0000	-25.00%
			2,000.00	1,700.00	-300.00	1,500.00	-500.00
172	CONC. SLOPE PROTECTION						
	35.0000	S.Y.	75.0000	77.0000	2.67%	200.0000	166.67%
			2,625.00	2,695.00	70.00	7,000.00	4,375.00
173	CHAIN LINK FENCE TYPE 3						
	271.0000	L.F.	20.0000	20.0000	0.00%	17.0000	-15.00%
			5,420.00	5,420.00	0.00	4,607.00	-813.00
174	CHAIN LINK FENCE TYPE 4						
	1621.0000	L.F.	15.0000	13.0000	-13.33%	11.0000	-26.67%
			24,315.00	21,073.00	-3,242.00	17,831.00	-6,484.00
175	END, GATE, CORNER, AND PULL POST FOR CHAIN LINK FENCE						
	18.0000	EACH	250.0000	180.0000	-28.00%	190.0000	-24.00%
			4,500.00	3,240.00	-1,260.00	3,420.00	-1,080.00

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

------- 4TH BIDDER -------	------- 5TH BIDDER -------
WILDER CONSTRUCTION COMPANY	KIEWIT PACIFIC CO.
1525 E MARINE VIEW DR	4904 LAKE WASHINGTON BLVD NE
EVERETT WA 982011927	RENTON WA 980561057
CONTRACTOR NUMBER : 892000	CONTRACTOR NUMBER : 446001

ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	OTHER ITEMS						
176	GRAVITY BLOCK WALL						
	387.0000	S.F.	30.0000	23.0000	-23.33%	46.0000	53.33%
			11,610.00	8,901.00	-2,709.00	17,802.00	6,192.00
177	CONNECTION TO DRAINAGE STRUCTURE						
	6.0000	EACH	2,000.0000	1,100.0000	-45.00%	730.0000	-63.50%
			12,000.00	6,600.00	-5,400.00	4,380.00	-7,620.00
178	ADJUST CATCH BASIN						
	7.0000	EACH	500.0000	370.0000	-26.00%	560.0000	12.00%
			3,500.00	2,590.00	-910.00	3,920.00	420.00
179	LOCKING SOLID METAL COVER AND FRAME FOR CATCH BASIN						
	11.0000	EACH	400.0000	110.0000	-72.50%	650.0000	62.50%
			4,400.00	1,210.00	-3,190.00	7,150.00	2,750.00
180	CLEANING EXISTING DRAINAGE STRUCTURE						
		L.S.			70.00%		400.00%
			4,000.00	6,800.00	2,800.00	20,000.00	16,000.00
181	FORCE ACCOUNT FOR TEMPORARY SIGNAL REMOVAL						
		EST.			0.00%		0.00%
			50,000.00	50,000.00		50,000.00	
182	FORCE ACCOUNT FOR MINOR ELECTRICAL REPAIR WORK						
		EST.			0.00%		0.00%
			20,000.00	20,000.00		20,000.00	
183	FORCE ACCOUNT FOR POTHOLING						
		EST.			0.00%		0.00%
			20,000.00	20,000.00		20,000.00	
184	FORCE ACCOUNT FOR UNIDENTIFIED UTILITIES						
		EST.			0.00%		0.00%
			20,000.00	20,000.00		20,000.00	
185	FORCE ACCOUNT FOR OFFSITE DRAINAGE						
		EST.			0.00%		0.00%
			20,000.00	20,000.00		20,000.00	
186	ROADSIDE CLEANUP						
		EST.			0.00%		0.00%
			10,000.00	10,000.00		10,000.00	

DOT_RGGB01

WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
* * * BID CHECK REPORT * * *

DATE: 03/06/2007
TIME: 09:03

PS&E JOB NO : 06A026 REVISION NO : 5
CONTRACT NO : 007272 REGION NO : 1
VERSION NO : 10 WORK ORDER# : XL2028
HWY : SR 520
TITLE : SR 520
W LAKE SAMMAMISH PKWY TO SR 202
FLYOVER RAMP
06A026
PROJECT :
COUNTY(S) : KING

BIDS OPENED ON : Mar 7 2007
AWARDED ON : Mar 16 2007

				4TH BIDDER		5TH BIDDER	
				WILDER CONSTRUCTION COMPANY		KIEWIT PACIFIC CO.	
				1525 E MARINE VIEW DR		4904 LAKE WASHINGTON BLVD NE	
				EVERETT WA 982011927		RENTON WA 980561057	
				CONTRACTOR NUMBER : 892000		CONTRACTOR NUMBER : 446001	
ITEM NO.	ITEM DESCRIPTION / EST. QUANTITY	UNIT MEAS	ENGR'S. EST. PRICE PER UNIT / TOTAL AMOUNT	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.	PRICE PER UNIT / TOTAL AMOUNT	% DIFF. / AMT.DIFF.
	OTHER ITEMS						
187	REIMBURSEMENT FOR THIRD PARTY DAMAGE						
		EST.			0.00%		0.00%
			5.00	5.00		5.00	
188	MINOR CHANGE						
		CALC			0.00%		0.00%
			-1.00	-1.00		-1.00	
189	FUEL COST ADJUSTMENT						
		CALC			0.00%		0.00%
			6,100.00	6,100.00		6,100.00	
190	AGGREGATE COMPLIANCE PRICE ADJUSTMENT						
		CALC			0.00%		0.00%
			69,798.00	69,798.00		69,798.00	
191	SPCC PLAN						
		L.S.			-81.75%		25.00%
			4,000.00	730.00	-3,270.00	5,000.00	1,000.00
192	CONSTRUCTION GEOTEXTILE FOR UNDERGROUND DRAINAGE						
	1190.0000	S.Y.	3.0000	2.0000	-33.33%	5.0000	66.67%
			3,570.00	2,380.00	-1,190.00	5,950.00	2,380.00
193	PLASTIC CROSSWALK LINE						
	440.0000	S.F.	5.0000	6.0000	20.00%	6.0000	20.00%
			2,200.00	2,640.00	440.00	2,640.00	440.00
194	WILDFLOWER SEEDING AND MULCHING						
	1.8800	ACRE	2,200.0000	2,200.0000	0.00%	2,100.0000	-4.55%
			4,136.00	4,136.00	0.00	3,948.00	-188.00
	CONTRACT TOTAL		$10,849,265.00	$11,110,000.00	2.40%	$11,598,302.00	6.90%
	BASE TOTAL		$10,849,265.00	$11,110,000.00	2.40%	$11,598,302.00	6.90%