

MEDIAN BARRIER CATCH BASIN

Description

This work shall consist of constructing a cast-in-place cement concrete catch basin under a concrete median barrier and connecting to existing culverts or drainage pipes. The catch basin shall conform to the applicable portions of Section 7-05 and the details shown in the proposal. With the approval of the Engineer, a precast cement concrete catch basin conforming to the details shown may be substituted for the cast-in-place unit.

Measurement

Median barrier catch basin will be measured per each.

Payment

Payment will be made in accordance with Section 1-04.1 of the Standard Specifications for the following bid item in the proposal.

“Median Barrier Catch Basin” per each.

All costs associated with connecting to existing drainage pipes and moving and resetting of an existing concrete median barrier shall be included in the unit contract price.

Payment for structure excavation and shoring and cribbing are not included in this item of work.