

ROUNABOUT CURBS

Description

This work consists of constructing the cement concrete roundabout curbs in accordance with the details shown in the plans. All applicable portions Section 8-04 of the Standard Specifications and the following requirements are included in this work.

Measurement

Measurement of concrete roundabout curbs will be by the linear foot measured along the face of curb of the completed curb or curb and gutter as identified in the details.

Payment

Payment will be made in accordance with Section 1-04.1 of the Standard Specifications for the following bid items that are included in the proposal:

- “Roundabout Central Island Cement Concrete Curb”, per linear foot.
- “Roundabout Truck Apron Cement Concrete Curb”, per linear foot.
- “Roundabout Truck Apron Cement Concrete Curb and Gutter”, per linear foot.