⇩ Project Type	Ramps and Collector Distributors																				Cross Road											
															Ramp Terminals			Barriers													Barriers		
Design Elements ⇨	Horiz. Align.	Vert. Align.	Lane Width	Shldr Width	Lane Tran-sition	On/Off Conn.	Cross Slope Lane	Cross Slope Shldr	Fill/ Ditch Slopes	Access (3)	Clear Zone	Sign, Del., Illumin.	Basic Safety	Bike & Ped.	Turn Radii	Angle	I/S Sight Dist.	Term. & Trans. Section (12)	Std Run	Bridge Rail (14)(19)	Lane Width	Shldr Width	Fill/ Ditch Slopes	Access (3)	Clear Zone	Sign., Del., Illumin.	Basic Safety	Vert. Clear. (11)	Ped. & Bike	Term. & Trans. Section (12)	Std . Run	Bridge Rail (14)(19)
Preservation																																
Roadway																																
(4-1) Non-Interstate Freeway	DE/F	DE/F	DE/F	DE/F	DE/F	DE/F	DE/F	DE/F	DE/F	DE/F		B	B	M	DE/F	DE/F	DE/F	F	B	F	DE/F	DE/F	DE/F			B	B	F	M	F	B	F
(4-2) HMA/PCCP/BST Overlays Ramps												B	B	M			B	F	B	F						B	B	F	M	F	B	F
Structures																																
(4-3) Bridge Replacement	F(2)	F(2)	F(2)	F(2)	F	F(2)	F(2)	F(2)	F(2)	F	F	F		F	F	F	F	F	F	F	F(2)	F(2)	F(2)	F	F	F		F	F	F	F	F
(4-4) Bridge Deck Rehab.												B	B	M				F(6)	F(22)	F						B	B	F	M	F(6)	F(22)	F
Improvements (16)																																
Mobility																																
(4-5) Non-Interstate Freeway	F	F	F	F	F	F	F	F	F	F	F	F		F	F	F	F	F	F	F	F	F	F	F	F	F		F	F	F	F	F
(4-6) Urban	F(2)	F(2)	F(2)	F(2)	F	F(2)	F(2)	F(2)	F(2)	F	F	F		F	F(2)	F(2)	F	F	F	F	F(2)	F(2)	F(2)	F	F	F		F	F	F	F	F
(4-7) Rural	F(2)	F(2)	F(2)	F(2)	F	F(2)	F(2)	F(2)	F(2)	F	F	F		F	F(2)	F(2)	F	F	F	F	F(2)	F(2)	F(2)	F	F	F		F	F	F	F	F
(4-8) HOV By Pass	F(2)	F(2)	F(2)	F(2)	F	F(2)	F(2)	F(2)	F(2)	F	F	F		F	F(2)	F(2)	F	F	F	F	F(2)	F(2)	F(2)	F	F	F		F	F	F	F	F
(4-9) Bike/Ped. Connectivity	(5)	(5)	(5)	(5)	(5)		(5)	(5)	(5)	(5)	(5)	(5)		F	(5)	(5)	(5)	(5)	(5)	(5)	(5)	(5)	(5)			(5)		(5)	F	(5)	(5)	(5)
Safety																																
(4-10) Non-Interstate Freeway	F	F	F	F	F	F	F	F	F	F	F	F		M	F	F	F	F	F	F	F	F	F	F	F	F		F	M	F	F	F
(4-11) At Grade (1)(25)	F(2)	F(2)	F(2)	F(2)	F	F(2)	F(2)	F(2)	F(2)	F	F	F		F	F(2)	F(2)	F	F	F	F	F(2)	F(2)	F(2)	F	F	F		F	F	F	F	F
(4-12) Intersection (1)			F(2)	F(2)	F				F(2)	F	F	F		M	F	F	F	F	F	F			F(2)	F	F	F		F	M	F	F	F
(4-13) Guardrail Upgrades				DE/F														F	F(23)											F	F(23)	
(4-14) Bridge Rail Upgrades																														F	F(22)	F
(4-15) Risk: Roadside									F	EU/F	F	F											F	EU/F	F	F				F	F	F
(4-16) Risk: Sight Distance	F/M(21)	F/M(21)	F/M(21)	F/M(21)					F/M(21)	F(21)	F(21)	F		F	F/M(21)	F/M(21)	F	F	F	F			F/M(21)	F(21)	F(21)			F(21)	F			
(4-17) Risk: Roadway Width			F/M(21)	F/M(21)	F	F(21)	F/M(21)	F/M(21)	F/M(21)	F	F	F		F	F/M(21)	F/M(21)	F	F	F	F	F/M(21)	F/M(21)	F/M(21)	F	F			F(21)	F	F	F	F
(4-18) Risk: Realignment	F(2)	F(2)	F(2)	F(2)	F	F(2)	F(2)	F(2)	F(2)	F	F	F		F	F/M(21)	F/M(21)	F	F	F	F	F(2)	F(2)	F(2)	F	F			F(21)	F	F	F	F
Economic Development																																
(4-19) Four-Lane Trunk System	F	F	F	F	F	F	F	F	F	F	F	F		F	F	F	F	F	F	F	F	F	F	F	F	F		F		F	F	F

☐ Not Applicable
F Full design level. See Chapter 440.
M Modified design level. See Chapter 430.
B Basic design level. See Chapter 410.
F/M Full for freeways/Modified for nonfreeway
DE Design Exception
EU Evaluate Upgrade

(1) Collision Reduction (HAL, HAC, PAL), or Collision Prevention (At-Grade Removal, Signalization & Channelization). Specific deficiencies that created the project must be upgraded to design level as stated in the matrix.
(2) Modified design level may apply based on a corridor or project analysis. See 325.03(5).
(3) If designated as L/A acquired in the Access Control Tracking System, limited access requirements apply. If not, managed access applies. See 325.03(5).
(4) Full design level may apply based on a corridor or project analysis. See 325.03(5).
(5) For bike/pedestrian design see Chapters 1020 and 1025.
(6) Applies only to bridge end terminals and transition sections.
(11) See Chapter 1120.
(12) Impact attenuators are considered as terminals.
(14) Includes crossroad bridge rail. See Chapter 710.
(16) For design elements not in the matrix headings, apply full design level as found in the applicable chapters and see 325.03(2).
(19) The funding sources for bridge rail are a function of the length of the bridge. Consult programming personnel.
(21) Analyses required. See 325.03(5) for details.
(22) Upgrade barrier, if necessary, within 200 ft of the end of the bridge.
(23) See description of Guardrail Upgrades Project Type, 325.03(1) regarding length of need.
(25) For main line, use the Project Type row for Safety, Non-Interstate Freeway on Matrix 3 for NHS and on Matrix 5 for non-NHS.

Design Matrix 4
Interchange Areas, NHS (Except Interstate) and Non-NHS
Figure 325-6