

1 (December 6, 2004)

2 Section 8-02.1 is supplemented with the following:

3

4 This work shall consist of removing and disposing of buried man-made or manufactured  
5 debris that may be encountered during soil amendment incorporation or during  
6 excavation for irrigation systems included in the contract. Such debris shall be removed  
7 to a maximum depth of two feet. The excavated debris shall be removed from the  
8 project site to an approved disposal facility.