

1 (April 3, 2006)
2 When the bridge removal work includes removal of a truss, and when the
3 Contractor's removal method involves use of a crane or cranes to pick, lift, and
4 remove the truss, the Contractor shall confirm the truss dead load weight prior
5 to beginning the truss removal operation. The operation of confirming the truss
6 dead load shall be performed at both ends of the truss, and shall ensure that
7 the truss is broken free of its support bearings. The Contractor's method of
8 confirming the truss dead load, whether by hydraulic jacks or other means,
9 shall be included in the Contractor's bridge demolition plan submittal.