

1 **(August 1, 2005)**

2 ***Removal and Disposal of Hazardous Material***

3 Hazardous material is suspected to exist on this project. Approximate limits of  
4 contamination are identified in the Plans. The site history, prior studies and/or test  
5 results indicate a potential for encountering \*\*\* \$\$1\$\$ \*\*\*.  
6

7 Copies of the environmental reports are available for review at the Engineer's office. All  
8 necessary permits for this work will be furnished by the Contracting Agency. The  
9 Contractor is responsible for all work, records, and reports required to perform the work  
10 described in this section. The Contracting Agency will perform all testing of suspected  
11 hazardous or contaminated material.  
12

13 The Contractor shall notify the Engineer 10 working days prior to beginning work in the  
14 area identified in the Plans as contaminated. The Contractor shall notify the Engineer  
15 immediately if contamination is discovered in areas other than those identified in the  
16 Plans, or is suspected through observations such as an oily sheen or discolored soils  
17 that may or may not emit strong chemical odors.  
18

19 ***Contaminated Soil and Hazardous Material***

20 The Engineer will determine the limits of excavation required. All material that is  
21 designated by the Engineer to be removed shall be handled and stored in a manner that  
22 prevents the spread of contamination to adjacent soil or water. Separate stockpiles  
23 shall be maintained for known hazardous or contaminated material and for suspected  
24 hazardous or contaminated material. The Contractor shall transport hazardous or  
25 contaminated material and dispose of it at a permitted facility. The Contractor shall  
26 provide the Engineer with a copy of the shipping manifest or bill of lading indicating the  
27 amount of material hauled to disposal, and bearing the disposal site operator's  
28 confirmation for receipt of the material.  
29

30 ***Contaminated Water***

31 All water that is removed from the areas of contamination, including free water that  
32 leeches from contaminated soil stockpiles or water that is suspected of being  
33 contaminated, shall be collected, handled and stored in a manner that prevents the  
34 spread of contamination to adjacent soil or water. The Contractor shall transport  
35 contaminated water and dispose of it at a permitted facility. The Contractor shall  
36 provide the Engineer with a copy of the shipping manifest or bill of lading indicating the  
37 amount of material hauled to disposal, and bearing the disposal site operator's  
38 confirmation for receipt of the material.