

1 (March 13, 1995)  
2 Prior to emulsified asphalt pavement construction, a tack coat of asphalt CSS-1,  
3 diluted at the rate of one part water to one part emulsion, shall be applied at the  
4 rate of 0.01 to 0.18 liters per square meter of retained asphalt to the entire roadway  
5 surface. The asphalt mix shall be placed and compacted before the emulsified  
6 asphalt in the mix breaks.