

1 (December 19, 2005)  
2 The Contractor shall round and treat the areas between the bridge end slopes and  
3 the edges of the shoulders to the satisfaction of the Engineer.  
4  
5 Upon completion of the installation of the units, the voids shall be filled full with top  
6 soil. All excess fill shall be removed and the exposed concrete surfaces swept  
7 clean. The slope protection shall be seeded to grass in accordance with Section 8-  
8 01.3(2)A.