

Schedule Quality Assessment Tool

A tool to help the Primavera administrators and Project Managers measure and maintain schedule quality in their portfolios.

How do you Assess Schedule Quality?

Schedule

- Constraints
- Open ends
- Activity relationships
- Lags
- Calendar assignment
- Float
- Task settings

Reporting Standards

- Project settings
- Code assignments
- WBS
- Responsibility
- Roles assignments
- Cost assignments
- Timely

Sounds like a lot of work!

Current Situation

- The Administrator/PM manually inspects each project schedule for compliance to standards .
- Using different inspection methods
- Different standards
- Different measures
- Getting different results
- All of which is rarely understood

Wouldn't it be nice if we could measure
schedule quality automatically in a

- Fair
- Fast
- Repeatable
- Visible
- Understandable
- And Easy manner

That gave an overall view of quality

Project Controls

Filter by Portfolio: Active Pr

Expand All | Collapse All | Customize

Filter last refr

| Project Statistics | | | | | | | | | | | | | |
|---------------------------------------------------------------------------|------------|------------------|----------------------------|-----------------------------|-------------------|---------------------------------------|-------------------------------------|-----------|-------------------|-----------------|--|--|--|
| Expand Collapse Customize | | | | | | | | | | | | | |
| Display <input type="radio"/> List <input checked="" type="radio"/> Group | | | | | | | | | | | | | |
| Name | Project ID | *Baseline Status | *Standard Project Settings | *Standard Activity Settings | *MDL Coverage (%) | *Role / Resource / Owner Coverage (%) | *Critical Path Hindrance Factor (%) | Data Date | *Updated Schedule | *Referenced SPI | | | |
| [-] FUCHS, S. | | | | 38.17 | 4.72 | 5.22 | 6.31 | 8-1-10 | | 0.16 | | | |
| [-] Design/PS&E | | | | 38.17 | 4.72 | 5.22 | 6.31 | 8-1-10 | | 0.16 | | | |
| [-] Design Authorized | | | | 56.20 | 5.79 | 13.77 | 3.86 | 8-1-10 | | 0.93 | | | |
| [+] SR 162/Puyallup River Bridge - Bridge Replac... | C16219A | | | 56.20 | 5.79 | 13.77 | 3.86 | 8-1-10 | | 0.93 | | | |
| [-] Design Initiated | | | | 31.72 | 4.33 | 2.17 | 7.19 | 8-1-10 | | 0.13 | | | |
| [+] US 101/Shore Rd. to Kitchen-Dick Rd. - Wide... | C10107G | | | 31.72 | 4.33 | 2.17 | 7.19 | 8-1-10 | | 0.13 | | | |
| [-] GILES, R. | | | | 84.69 | 100.00 | 76.02 | 5.44 | 8-1-10 | | 0.97 | | | |
| [-] Design/PS&E | | | | 84.69 | 100.00 | 76.02 | 5.44 | 8-1-10 | | 0.97 | | | |
| [-] Design Initiated | | | | 84.69 | 100.00 | 76.02 | 5.44 | 8-1-10 | | 0.97 | | | |
| [+] I-90/Snoqualmie Pass East - Hyak to Keechel... | E09009B | | | 84.69 | 100.00 | 76.02 | 5.44 | 8-1-10 | | 0.97 | | | |
| [-] GOLBECK, S. (ACTING) | | | | 92.05 | 100.00 | 96.59 | 3.41 | 8-1-10 | | 0.98 | | | |
| [-] Design/PS&E | | | | 92.05 | 100.00 | 96.59 | 3.41 | 8-1-10 | | 0.98 | | | |
| [-] Design Initiated | | | | 92.05 | 100.00 | 96.59 | 3.41 | 8-1-10 | | 0.98 | | | |
| [+] I-90/Hyak to Easton | E09007X | | | 92.05 | 100.00 | 96.59 | 3.41 | 8-1-10 | | 0.98 | | | |
| [-] GONSETH, P.J. | | | | 36.12 | 17.06 | 29.43 | 15.05 | 6-1-09 | | 0.62 | | | |
| [-] Design/PS&E | | | | 36.12 | 17.06 | 29.43 | 15.05 | 6-1-09 | | 0.62 | | | |
| [-] Design Initiated | | | | 46.71 | 20.39 | 43.42 | 22.37 | 8-1-10 | | 0.54 | | | |
| [+] US 124.5 Miles East of SR 123 - Stabilize Slo... | D01207G | | | 41.38 | 19.54 | 37.93 | 31.03 | 8-1-10 | | 0.53 | | | |
| [+] US 124.4 Miles East of SR 123 - Stabilize Slo... | D01207F | | | 53.85 | 21.54 | 50.77 | 10.77 | 8-1-10 | | 0.56 | | | |
| [-] On Ad | | | | | | | | 6-1-09 | | 1.00 | | | |
| [+] US 101/SR 6 to Grays Harbor County Line-Pa... | D10105A | | | --- | --- | --- | --- | 6-1-09 | | 1.00 | | | |
| [-] PS&E Review | | | | 75.51 | 40.82 | 44.90 | 22.45 | 8-1-10 | | 0.55 | | | |
| [+] I-82/Terrace Heights Off Ramp - Improvements | E08202I | | | 75.51 | 40.82 | 44.90 | 22.45 | 8-1-10 | | 0.55 | | | |

Timeline

- Quality Measures Presentation given in Feb 2010
- Direction given by Jerry Lenzi to have measures in place by July 2010
- First iteration of the Quality Assessment Measures tool provided to WSDOT July 2010
- Regions will have the opportunity to modify and customize measures as needed

What are the measures?

Basic Measures

- Baseline Status
- Baseline Review and Exception Report
- Standard Project settings (%)
- Standard Activity settings (%)
- MDL Coverage (%)
- Role/Resource/Owner coverage (%) (*At Least One Responsible Party*)
- Critical Path Hindrance Factor (%)
- Updated Schedule

Intermediate Measures

- Questionable Dependencies Report
- SPI
- Remaining Finish Variance (%)
- CPI
- Funding – BAC Variance (\$)
- Funding – EAC Variance (\$, %)
- At Complete P6 Cost Variance (%)
- Remaining Authorization (\$, %)
- MDL Tier w/Actual Cost (%)
- MDL Tier w/Budget (%)

Measure Guide

Definitions & How to Fix

Baseline Status

Measures: The status of the baseline Plan.

Calculated: Approved by management and set by regional Primavera administrator.

Why this is important: The Baseline is management’s approved plan that provides a comparison with actual progress of work to determine if performance is meeting managements expectations.

Green – Has an approved baseline or has been submitted for approval (“OK”)

Yellow – Baseline currently under development

Red – Baseline not approved

| Project ID | *Baseline Status | *Standard Project Settings | *Standard Activity Settings (%) | *MDL Coverage (%) | *Role/Resource Coverage (%) | *Critical Path Hindrance Factor (%) | Data Date | *Updated Schedule | *Referenced SPI | *Remaining Finish Variance (%) |
|------------|------------------|----------------------------|---------------------------------|-------------------|-----------------------------|-------------------------------------|-----------|-------------------|-----------------|--------------------------------|
| | | | 55.16 | 103.66 | 17.73 | 16.48 | 07/01/10 | | 0.71 | 26.17 |
| A00522B | | | 82.82 | 288.96 | 0.61 | 57.06 | 07/01/10 | | 0.63 | 0.00 |
| A09060D | | | 72.12 | 11.54 | 0.00 | 9.62 | 07/01/10 | | 0.97 | 41.30 |
| A16718P | | | 80.36 | 75.00 | 32.14 | 15.18 | 07/01/10 | | 1.03 | 0.00 |
| A20201W | | | 25.00 | 353.79 | 0.00 | 7.58 | 07/01/10 | | 0.97 | 27.27 |
| A52234E | | | 43.40 | 23.94 | 12.53 | 10.74 | 07/01/10 | | 0.96 | 46.26 |
| A00912D | | | 78.43 | 10.78 | 1.96 | 13.73 | 07/01/10 | | 0.72 | 38.89 |
| A09946S | | | 32.73 | 63.64 | 19.39 | 13.94 | 07/01/10 | | 0.14 | 66.67 |

How to Improve (and Manage) Baseline Status

- Follow your Regional process for baseline approval.
- Many times this is done concurrently with PMP endorsement.
- A senior scheduler or above will have permission to save and assign your baseline.
- After which your status will be set to Green.
- Reference: PMRS Primavera Scheduler Version 2.2.20 Supplement - Page 22
- Periodically run the report “QC – Baseline Review and Exception Report” to review any baselines recently added to schedules that have already been coded as having an approved baseline

Standard Project Settings

Measures: Whether the standard project settings are being used.

Calculated: Green if using standard settings, yellow if a few settings deviate and are not approved, red if many settings deviate and are not approved.

Why this is important: Standard project settings ensure correct calculations throughout the project schedule and budget.

Green - All standard settings used or approved non-standard settings

Yellow – Few non-standard settings used and not reviewed or approved

Red – Non-standard settings used and not reviewed or approved

| Project ID | *Baseline Status | *Standard Project Settings | *Standard Activity Settings (%) | *MDL Coverage (%) | *Role/Resource Coverage (%) | *Critical Path Hindrance Factor (%) | Data Date | *Updated Schedule | *Referenced SPI | *Remaining Finish Variance (%) |
|------------|------------------|----------------------------|---------------------------------|-------------------|-----------------------------|-------------------------------------|-----------|-------------------|-----------------|--------------------------------|
| | | | 55.16 | 103.66 | 17.73 | 16.48 | 07/01/10 | | 0.71 | 26.17 |
| A00522B | | | 82.82 | 288.96 | 0.61 | 57.06 | 07/01/10 | | 0.63 | 0.00 |
| A09060D | | | 72.12 | 11.54 | 0.00 | 9.62 | 07/01/10 | | 0.97 | 41.30 |
| A16718P | | | 80.36 | 75.00 | 32.14 | 15.18 | 07/01/10 | | 1.03 | 0.00 |
| A20201W | | | 25.00 | 353.79 | 0.00 | 7.58 | 07/01/10 | | 0.97 | 27.27 |
| A52234E | | | 43.40 | 23.94 | 12.53 | 10.74 | 07/01/10 | | 0.96 | 46.26 |
| A00912D | | | 78.43 | 10.78 | 1.96 | 13.73 | 07/01/10 | | 0.72 | 38.89 |
| A09946S | | | 32.73 | 63.64 | 19.39 | 13.94 | 07/01/10 | | 0.14 | 66.67 |

How to Improve Project Settings

If these setting match or if deviation is approved, measure is green, if not, it is red (or yellow for minor deviations). Match the settings below.

Planning Resources Budget Log Spending Plan Budget Summary Dates Funding Codes Defaults Resources Settings

| | |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Summarized Data <input type="checkbox"/> Contains Summarized Data Only Last Summarized On 8-2-10 Summarize to WBS Level 5 Summarize project based on <input type="radio"/> High level resource planning <input checked="" type="radio"/> Detail activity resource assignments | Project Settings Character for separating code fields for the WBS tree Fiscal year begins on the 1st day of July Baseline for earned value calculations <input checked="" type="radio"/> Project baseline <input type="radio"/> User's primary baseline Define Critical Activities <input type="radio"/> Total Float less than or equal to 0h <input checked="" type="radio"/> Longest Path |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

Planning Resources Budget Log Spending Plan Budget Summary Dates Funding Codes Defaults Resources Settings

| | |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Defaults for New Activities Duration Type Fixed Duration & Units Cost Account Percent Complete Type Physical Calendar 5 D w/WSDOT Holidays Activity Type Task Dependent | Auto-numbering Defaults Activity ID Prefix A Activity ID Suffix 1000 Increment 10 <input checked="" type="checkbox"/> Increment Activity ID based on selected activity |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

Budget Log Spending Plan Budget Summary Dates Funding Codes Defaults Resources Settings Calculations

| | |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Activities Default Price / Unit for activities without resource or role Price / Units \$0/h <input checked="" type="checkbox"/> Activity percent complete based on activity steps <input checked="" type="checkbox"/> Link Planned and At Completion for not started activities <input type="radio"/> Reset Planned Duration and Units to Remaining <input checked="" type="radio"/> Reset Remaining Duration and Units to Planned | Resource Assignments When updating Actual Units or Cost <input type="radio"/> Add Actual to Remaining <input checked="" type="radio"/> Subtract Actual from At Completion <input type="checkbox"/> Recalculate Actual Units and Cost when duration % complete changes <input type="checkbox"/> Update units when costs change on resource assignments <input checked="" type="checkbox"/> Link Actual and Actual This Period Units and Cost |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

General Notebook Planning Resources Budget Log Spending Plan Budget Summary Dates Funding Codes Defaults Resources Settings Calculations

| | |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Progress Reporter <input type="checkbox"/> Resource can view activities from an inactive project <input type="checkbox"/> Resources can assign themselves to activities <input type="checkbox"/> Primary resources can mark activities as completed <input type="checkbox"/> Resources can mark assignments as completed <input type="checkbox"/> Resources can edit activity assignment percent complete <input checked="" type="checkbox"/> Resources can edit activity assignment remaining units | Assignment Defaults Specify the default Rate Type for new assignments WSDOT <input checked="" type="checkbox"/> Drive activity dates by default Resource Assignments <input checked="" type="checkbox"/> Resources can be assigned to the same activity more than once |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

Standard Activity settings

Measures: The % of activities that comply with standard activity settings.

Calculated: By dividing the number of activities that are using the standard settings by total activities in the project. An activity is considered to be standard if settings are: Duration Type set to “Fixed Duration & Units”, Percent Complete Type set to “Physical” and the calendar set to “5 D w/ WSDOT Holidays”.

Why this is important: Standard activity settings ensure correct calculations throughout the project schedule and budget.


Green - Greater than 85% are standard

Yellow – Less than 85% are standard

| Project ID | *Baseline Status | *Standard Project Settings | *Standard Activity Settings (%) | *MDL Coverage (%) | *Role/Resource Coverage (%) | *Critical Path Hindrance Factor (%) | Data Date | *Updated Schedule | *Referenced SPI | *Remaining Finish Variance (%) |
|------------|------------------|----------------------------|---------------------------------|-------------------|-----------------------------|-------------------------------------|-----------|-------------------|-----------------|--------------------------------|
| | | | 55.16 | 103.66 | 17.73 | 16.48 | 07/01/10 | | 0.71 | 26.17 |
| A00522B | 🟢 | 🟢 | 82.82 | 288.96 | 0.61 | 57.06 | 07/01/10 | 🟢 | 0.63 | 0.00 |
| A09060D | 🟢 | 🟢 | 72.12 | 11.54 | 0.00 | 9.62 | 07/01/10 | 🟢 | 0.97 | 41.30 |
| A16718P | 🟢 | 🟢 | 80.36 | 75.00 | 32.14 | 15.18 | 07/01/10 | 🟢 | 1.03 | 0.00 |
| A20201W | 🟢 | 🟢 | 25.00 | 353.79 | 0.00 | 7.58 | 07/01/10 | 🟢 | 0.97 | 27.27 |
| A52234E | 🟢 | 🟢 | 43.40 | 23.94 | 12.53 | 10.74 | 07/01/10 | 🟢 | 0.96 | 46.26 |
| A00912D | 🟢 | 🟢 | 78.43 | 10.78 | 1.96 | 13.73 | 07/01/10 | 🟢 | 0.72 | 38.89 |
| A09946S | 🟢 | 🟢 | 32.73 | 63.64 | 19.39 | 13.94 | 07/01/10 | 🟢 | 0.14 | 66.67 |

How to Improve Activity Settings

- Using Primavera Scheduler
- Open the project
- Open the Activity Layout - “QA – Review Acts w/Non-Standard Settings”



| Activity Name | Activity Count | Start | Finish | Percent Complete Type | Duration Type | Calendar |
|---------------------------------------------------------------|----------------|------------|-----------|-----------------------|-------------------------------|-----------------------|
| A00099E SR 169 and SR 900 Roadside Safety In | 103 | 07/01/08 A | 06/06/11 | | | 5 D w/ WSDOT Holidays |
| Additional Clear Zone Inventory | 1 | 10/27/09 A | 11/06/... | Physical | Fixed Units | 5 D w/ WSDOT Holidays |
| Sign Inventory | 1 | 10/27/09 A | 11/06/... | Physical | Fixed Duration and Units/Time | 5 D w/ WSDOT Holidays |
| Address Proof Copy Review Comments | 1 | 02/03/10 A | 02/16/... | Physical | Fixed Duration and Units/Time | 5 D w/ WSDOT Holidays |
| A00099E.PE Preliminary Engineering | 96 | 07/01/08 A | 06/06/11 | | | 5 D w/ WSDOT Holidays |
| A00099E.PE.PS Project Planning and Scoping | 7 | 07/01/08 A | 08/26/... | | | 5 D w/ WSDOT Holidays |
| A00099E.PE.PS.01 Preliminary Estimates & Schedules | 2 | 07/01/08 A | 07/15/... | | | 5 D w/ WSDOT Holidays |
| PE Estimate | 1 | 07/01/08 A | 07/01/... | Physical | Fixed Units | 5 D w/ WSDOT Holidays |
| CN Estimate | 1 | 07/09/08 A | 07/15/... | Physical | Fixed Units | 5 D w/ WSDOT Holidays |
| A00099E.PE.PS.08 Project Summary | 5 | 07/16/08 A | 08/26/... | | | 5 D w/ WSDOT Holidays |
| Project Definition | 1 | 07/16/08 A | 07/22/... | Physical | Fixed Units | 5 D w/ WSDOT Holidays |
| Design Decisions Summary | 1 | 07/16/08 A | 07/23/... | Physical | Fixed Units | 5 D w/ WSDOT Holidays |
| Environmental Review Summary | 1 | 07/16/08 A | 07/22/... | Physical | Fixed Units | 5 D w/ WSDOT Holidays |

- Review each activity appearing on this list for conformance to the standards.

MDL Coverage (%)

Measures: The percentage of activities that have an MDL code assigned.

Calculated: By dividing the number of activities that have an MDL code assigned by total activities in the project “Coded activities/total activities”.

Why this is important: This measures the project’s relationship to standard WSDOT deliverables.

Green - Greater than 90%

Yellow – 50%-75% and 75%-90%

Red – Fewer than 50%

| Project ID | *Baseline Status | *Standard Project Settings | *Standard Activity Settings (%) | *MDL Coverage (%) | *Role/Resource Coverage (%) | *Critical Path Hindrance Factor (%) | Data Date | *Updated Schedule | *Referenced SPI | *Remaining Finish Variance (%) |
|------------|------------------|----------------------------|---------------------------------|-------------------|-----------------------------|-------------------------------------|-----------|-------------------|-----------------|--------------------------------|
| | | | 55.16 | 103.66 | 17.73 | 16.48 | 07/01/10 | | 0.71 | 26.17 |
| A00522B | 🟢 | 🟢 | 82.82 | 288.96 | 0.61 | 57.06 | 07/01/10 | 🟢 | 0.63 | 0.00 |
| A09060D | 🟢 | 🟢 | 72.12 | 11.54 | 0.00 | 9.62 | 07/01/10 | 🟢 | 0.97 | 41.30 |
| A16718P | 🟢 | 🟢 | 80.36 | 75.00 | 32.14 | 15.18 | 07/01/10 | 🟢 | 1.03 | 0.00 |
| A20201W | 🟢 | 🟢 | 25.00 | 353.79 | 0.00 | 7.58 | 07/01/10 | 🟢 | 0.97 | 27.27 |
| A52234E | 🟢 | 🟢 | 43.40 | 23.94 | 12.53 | 10.74 | 07/01/10 | 🟢 | 0.96 | 46.26 |
| A00912D | 🟢 | 🟢 | 78.43 | 10.78 | 1.96 | 13.73 | 07/01/10 | 🟢 | 0.72 | 38.89 |
| A09946S | 🟢 | 🟢 | 32.73 | 63.64 | 19.39 | 13.94 | 07/01/10 | 🟢 | 0.14 | 66.67 |

How to improve MDL Coverage (%)

- Using Primavera Scheduler
- Open the project
- Open the Activity Layout “QA - Show Acts Without an MDL Code”

Assign an MDL Code to every activity that appears this layout.

The screenshot displays the Primavera Scheduler interface. On the left, the 'Layout' pane shows 'QA - Show Acts Without an MDL Code' selected. The main window shows a table of activities with columns for Activity ID, Activity Name, Activity Count, and Master Deliverable List. A table below shows activity details for ID 0334, including codes 0132 and 0133. On the right, the 'Assign Activity Codes' dialog is open, showing a tree view of activity codes under 'Activity Code: Master Deliverable List'.

| Activity ID | Activity Name | Activity Count | Master Deliverable List |
|------------------|------------------------------------------------------------|----------------|-------------------------|
| A00099E | SR 169 and SR 900 Roadside Safety Improve... | 21 | |
| 2085 | Address Proof Copy Review Comments | 1 | |
| A00099E.PE | Preliminary Engineering | 19 | |
| PE-ACT | PE Actual Costs | 1 | |
| A00099E.PE.PM | General Project Management & Overhead - Preliminary Eng... | 1 | |
| A00099E.PE.PM.02 | Project Management and Overhead | 1 | |
| 0055 | March Accruals | 1 | |
| A00099E.PE.EV | Environmental F | | |
| A00099E.PE.EV.01 | Endangered S | | |
| 0334 | BA Checklist | | |
| A00099E.PE.PD | Project Develop | | |
| A00099E.PE.PD.06 | Project Data, S | | |

| Activity | Code Value | Description |
|---------------|------------|-------------|
| Activity 0334 | | |
| Work Op Code | 0132 | |
| | 0133 | |

| Code Value | Description |
|---------------|---------------------------------------------|
| PE | Preliminary Engineering |
| PE.PM | Management & Overhead - Preliminary Enginee |
| PE.PM.01 | Begin Preliminary Engineering |
| PE.PM.02 | Project Management and Overhead |
| PE.PM.02.01 | General Project Management (Project Office) |
| PE.PM.02.01.1 | Disaster Damage Inspection Report (DDIR) |

Role/Resource/Owner Coverage (%)

Measures: The percentage of activities that have primary responsibility assigned.

Calculated: By dividing the number of activities that have primary responsibility assigned by total activities in the project.

Why this is important: It's easier to track down ownership and measure progress when a project task has a primary responsibility assigned. It is unrealistic to expect work to get done if no one has been assigned to be responsible to do the work.


Green – At least 85% assigned resources

Yellow – Less than 85% assigned resources

| Project ID | *Baseline Status | *Standard Project Settings | *Standard Activity Settings (%) | *MDL Coverage (%) | *Role/Resource Coverage (%) | *Critical Path Hindrance Factor (%) | Data Date | *Updated Schedule | *Referenced SPI | *Remaining Finish Variance (%) |
|------------|------------------|----------------------------|---------------------------------|-------------------|-----------------------------|-------------------------------------|-----------|-------------------|-----------------|--------------------------------|
| | | | 55.16 | 103.66 | 17.73 | 16.48 | 07/01/10 | | 0.71 | 26.17 |
| A00522B | | | 82.82 | 288.96 | 0.61 | 57.06 | 07/01/10 | | 0.63 | 0.00 |
| A09060D | | | 72.12 | 11.54 | 0.00 | 9.62 | 07/01/10 | | 0.97 | 41.30 |
| A16718P | | | 80.36 | 75.00 | 32.14 | 15.18 | 07/01/10 | | 1.03 | 0.00 |
| A20201W | | | 25.00 | 353.79 | 0.00 | 7.58 | 07/01/10 | | 0.97 | 27.27 |
| A52234E | | | 43.40 | 23.94 | 12.53 | 10.74 | 07/01/10 | | 0.96 | 46.26 |
| A00912D | | | 78.43 | 10.78 | 1.96 | 13.73 | 07/01/10 | | 0.72 | 38.89 |
| A09946S | | | 32.73 | 63.64 | 19.39 | 13.94 | 07/01/10 | | 0.14 | 66.67 |

How to improve Role/Resource/Owner Coverage (%)

- Using Primavera Scheduler
- Open the project
- Open the Activity Layout
- “QA – Missing Role/Resource/Owner”



| Activity ID | Activity Name | Start | Finish | Resources | Roles | Owner |
|--------------------|---------------------------------------------------------------|-------------|-------------|-----------|-------|-------|
| - A00099E.PE | Preliminary Engineering | 07/01/08... | 06/06/11 | | | |
| + A00099E.PE.PM | General Project Management & Overhead - Preliminary Engine... | 07/28/08... | 06/06/11 | | | |
| + A00099E.PE.PS | Project Planning and Scoping | 07/01/08... | 08/26/08... | | | |
| - A00099E.PE.EV | Environmental Review and Permitting | 02/24/09... | 02/01/10... | | | |
| - A00099E.PE.EV.01 | Endangered Species Act Compliance | 02/24/09... | 05/04/09... | | | |
| 0334 | BA Checklist | 02/24/09... | 03/10/09... | | | |
| 0335 | Environmental Biological Assessment - NE Letter Sent | 03/10/09... | 05/04/09... | | | |
| - A00099E.PE.EV.10 | Discipline Studies | 08/03/09... | 11/16/09... | | | |
| 0445 | Wetland/Biology Discipline Report | 08/03/09... | 11/16/09... | | | |
| - A00099E.PE.EV.11 | NEPA/SEPA Compliance | 09/01/09... | 10/13/09... | | | |
| 0745 | SEPA Checklist/DNS | 09/01/09... | 10/13/09... | | | |

- Assign one responsible party to every activity that appears this layout.

Critical Path Hindrance Factor (%)

Measures: The validity of the critical path calculation.

Calculated: By dividing the number of critical path hindered activities by the total number of activities in the project. An activity is considered to be critical path hindered if it's constrained, missing dependencies or is a Level of Effort activity.

Why this is important: The critical path is the longest duration path in the project. Any delay to a critical path activity will delay the end date of the project. If this calculation is hindered, the project manager will lose visibility into which activities are most important to keep on schedule.

Green - Less than 15%


Yellow – 15%-50%

Red – Greater than 50%

| Project ID | *Baseline Status | *Standard Project Settings | *Standard Activity Settings (%) | *MDL Coverage (%) | *Role/Resource Coverage (%) | *Critical Path Hindrance Factor (%) | Data Date | *Updated Schedule | *Referenced SPI | *Remaining Finish Variance (%) |
|------------|------------------|----------------------------|---------------------------------|-------------------|-----------------------------|-------------------------------------|-----------|-------------------|-----------------|--------------------------------|
| | | | 55.16 | 103.66 | 17.73 | 16.48 | 07/01/10 | | 0.71 | 26.17 |
| A00522B | 🟢 | 🟢 | 82.82 | 288.96 | 0.61 | 57.06 | 07/01/10 | 🟢 | 0.63 | 0.00 |
| A09060D | 🟢 | 🟢 | 72.12 | 11.54 | 0.00 | 9.62 | 07/01/10 | 🟢 | 0.97 | 41.30 |
| A16718P | 🟢 | 🟢 | 80.36 | 75.00 | 32.14 | 15.18 | 07/01/10 | 🟢 | 1.03 | 0.00 |
| A20201W | 🟢 | 🟢 | 25.00 | 353.79 | 0.00 | 7.58 | 07/01/10 | 🟢 | 0.97 | 27.27 |
| A52234E | 🟢 | 🟢 | 43.40 | 23.94 | 12.53 | 10.74 | 07/01/10 | 🟢 | 0.96 | 46.26 |
| A00912D | 🟢 | 🟢 | 78.43 | 10.78 | 1.96 | 13.73 | 07/01/10 | 🟢 | 0.72 | 38.89 |
| A09946S | 🟢 | 🟢 | 32.73 | 63.64 | 19.39 | 13.94 | 07/01/10 | 🟢 | 0.14 | 66.67 |

How to improve the Critical Path

- Using Primavera Scheduler
- Open the project
- Open the Activity Layout
- “QA-Show Critical Path Hindered Acts”



| Layout: QA - Show Critical Path Hindered Acts | | Filter All: QA - Critical Path Hindered | | | | | | | | |
|----------------------------------------------------------------------------|-----------------------------------------|-----------------------------------------|------------|------------|-----------------|--------------------|-------------------------|------------------|-----------------|--|
| Activity ID | Activity Name | Original Duration | Start | Finish | Activity Type | Primary Constraint | Primary Constraint Date | Predecessors | Successors | |
| SR 169 and SR 900 Roadside Safety Improvement | | 440d | 07/22/08 A | 06/06/11 | | | | | | |
| Preliminary Engineering | | 440d | 07/22/08 A | 06/06/11 | | | | | | |
| General Project Management & Overhead - Preliminary Engineering | | 440d | 07/28/08 A | 06/06/11 | | | | | | |
| Project Management and Overhead | | 440d | 07/28/08 A | 06/06/11 | | | | | | |
| 0040 | Management Reserve (LOE) | 275d | 01/08/09 A | 05/03/10 | Level of Effort | | | 0045 | | |
| 0025 | Managing the Project Hammock Task (LOE) | 440d | 01/08/09 A | 08/25/10 | Level of Effort | | | 0015, 0045 | 2630 | |
| 0055 | March Accruals | 5d | 12/01/09 A | 05/07/10 | Task Dependent | | | | | |
| 0050 | Project Contingency | 275d | 07/28/08 A | 06/06/11 | Task Dependent | | | 0015 | | |
| Project Development | | 111d | 07/22/08 A | 11/10/09 A | | | | | | |
| Constructability Reviews | | 111d | 07/22/08 A | 11/10/09 A | | | | | | |
| 1945 | 60% Constructability Meeting/Review | 7d | 11/02/09 A | 11/10/09 A | Task Dependent | Start On or ... | 10/26/09 | 1603, 1320, 1... | 1946 | |
| 1930 | Scoping Phase Review (PDR) | 0d | 07/22/08 A | 07/22/08 A | Task Dependent | | | | 0305, 0310, 030 | |
| Construction | | 1d | 08/27/10 | 08/27/10 | | | | | | |
| Construction Milestones | | 1d | 08/27/10 | 08/27/10 | | | | | | |
| Completion | | 1d | 08/27/10 | 08/27/10 | | | | | | |
| 2675 | Final Contract Completion | 1d | 08/27/10 | 08/27/10 | Task Dependent | | | 2650 | | |

- Review every constraint, missing dependency or type of activity for every activity that appears in this layout.

Questionable Dependencies

Measures: The presences of activities with SS, SF, FF, or Lag assigned to them.


Calculated: By a Report that will show lags and non-FS relationships.

Why this is important: Questionable dependencies can prevent scheduler from calculating the true critical path and will limit visibility of the full process required to produce a deliverable.

| | | |
|------------------------------------------------------------------|--------|---------|
| [-] [Report Icon] Report Group: Quality Measures | | |
| [Report Icon] QC - Project Baselines Review and Exception Report | Global | 7-27-10 |
| [Report Icon] QC - Questionable Dependency Report | Global | 7-28-10 |
| [-] [Report Icon] Report Group: Batch Reports | | |
| [Report Icon] QC - Critical Path Hindered Activities | Global | 8-2-10 |
| [Report Icon] QC - IP/Comp MDL Tier Activities | Global | 7-29-10 |
| [Report Icon] QC - MDL Coded Activities | Global | 8-3-10 |
| [Report Icon] QC - MDL Tier w/Actual Cost | Global | 7-29-10 |
| [Report Icon] QC - MDL Tier w/Budget | Global | 7-29-10 |
| [Report Icon] QC - Remaining Finish Variance | Global | 7-29-10 |
| [Report Icon] QC - Role/Resource/Owner Assignments | Global | 8-3-10 |
| [Report Icon] QC - Standard Activity Settings | Global | 8-3-10 |
| [Report Icon] QC - Total MDL Tier Activities | Global | 7-29-10 |

How to improve Questionable Dependencies

- Using Primavera Scheduler
- Open the project
- Run the Report “QC – Questionable Dependency Report”
- Review and address every dependency on this report.



Questionable Dependency Report

| <u>Project ID</u> | <u>Project Name</u> | | | | | |
|------------------------------------|------------------------------------------------------|-------------------|-------------------|-------------|--------------|------|
| Activity ID | Activity Name | Relationship Type | Original Duration | Early Start | Early Finish | Lag |
| <u>Questionable Logic</u> | | | | | | |
| A00099E | SR 169 and SR 900 Roadside Safety Improvement | | | | | |
| 0015 | Begin Preliminary Engineering | | 0d | 05/01/10 | 05/01/10 | |
| <u>Questionable Successor(s)</u> | | | | | | |
| 0025 | Managing the Project Hammock Task (LOE) | FS | 440d | 05/03/10 | 08/25/10 | 112d |
| 0025 | Managing the Project Hammock Task (LOE) | | 440d | 05/03/10 | 08/25/10 | |
| <u>Questionable Predecessor(s)</u> | | | | | | |
| 0015 | Begin Preliminary Engineering | FS | 0d | 05/01/10 | 05/01/10 | 112d |
| 0045 | PM Plan Initiation Stakeholders Meeting | SS | 0d | 05/01/10 | 05/01/10 | 112d |
| <u>Questionable Successor(s)</u> | | | | | | |
| 2630 | Construction Work Start | FF | 60d | 06/02/10 | 08/25/10 | 0d |

Updated Schedule

Measures: How current the project plan is.

Calculated: Primavera data date is compared to the current date.

Why this is important: A plan is only as good as the information put into it.

Without current status, the schedule is useless for managing the project.

Green – Less than 45 days ago

Yellow – Within 45 to 90 days in the past

Red – More than 90 days ago

| Project ID | *Baseline Status | *Standard Project Settings | *Standard Activity Settings (%) | *MDL Coverage (%) | *Role/Resource Coverage (%) | *Critical Path Hindrance Factor (%) | Data Date | *Updated Schedule | *Referenced SPI | *Remaining Finish Variance (%) |
|------------|------------------|----------------------------|---------------------------------|-------------------|-----------------------------|-------------------------------------|-----------|-------------------|-----------------|--------------------------------|
| | | | 55.16 | 103.66 | 17.73 | 16.48 | 07/01/10 | | 0.71 | 26.17 |
| A00522B | | | 82.82 | 288.96 | 0.61 | 57.06 | 07/01/10 | | 0.63 | 0.00 |
| A09060D | | | 72.12 | 11.54 | 0.00 | 9.62 | 07/01/10 | | 0.97 | 41.30 |
| A16718P | | | 80.36 | 75.00 | 32.14 | 15.18 | 07/01/10 | | 1.03 | 0.00 |
| A20201W | | | 25.00 | 353.79 | 0.00 | 7.58 | 07/01/10 | | 0.97 | 27.27 |
| A52234E | | | 43.40 | 23.94 | 12.53 | 10.74 | 07/01/10 | | 0.96 | 46.26 |
| A00912D | | | 78.43 | 10.78 | 1.96 | 13.73 | 07/01/10 | | 0.72 | 38.89 |
| A09946S | | | 32.73 | 63.64 | 19.39 | 13.94 | 07/01/10 | | 0.14 | 66.67 |

How to improve the Updated Schedule metric

- Update the status of your plan and calculate the schedule using the most recent Data Date (the first workday of the current month).

Layout: Standard Activity Status* Filter: All Activities

| Activity ID | Activity Name | Planned Duration | Remaining Duration | Schedule % Complete | Start | Finish | Total Float |
|---------------------|------------------------------------------------|------------------|--------------------|---------------------|---------|---------|-------------|
| Ponds | | 28 | 28 | 0% | 6-2-10 | 7-12-10 | 8 |
| A1220 | Ponds - Earthwork | 15 | 15 | 0% | 6-2-10 | 6-22-10 | 8 |
| A1219 | Ponds - Bioswale/Ditch (Structures D10 - 1 &2) | 3 | 3 | 0% | 6-2-10 | 6-4-10 | 33 |
| A1230 | Ponds - Drainage Structure/Spall installation | 5 | 5 | 0% | 6-23-10 | 6-29-10 | 8 |
| A1240 | Ponds - Blanket/Seeding | 5 | 5 | 0% | 6-30-10 | 7-7-10 | 8 |
| A1250 | Ponds - Erosion Control | 3 | 3 | 0% | 7-8-10 | 7-12-10 | 8 |
| A1260 | Ponds Complete | 0 | 0 | 0% | | 7-12-10 | 8 |
| SB Ramps RAB | | 40 | 40 | 0% | 6-2-10 | 7-28-10 | -4 |
| A1040 | SB Ramps RAB - Select Borrow | 15 | 15 | 0% | 6-2-10 | 6-22-10 | -4 |
| A1043 | SB Ramps RAB - CSBC | 5 | 5 | 0% | 6-23-10 | 6-29-10 | -4 |
| A1050 | SB Ramps RAB - CSBC | 5 | 5 | 0% | 6-23-10 | 6-29-10 | 15 |

General | Status | Resources | Relationships

Activity: 2390 Travel To & From the Office to the Job Site Project: A01100G

Duration: Planned 0, Actual 0, Remaining 0, At Complete 0

Total Float: 710, Free Float: 710

Schedule

Project(s) to schedule: 5

Earliest Data Date: 7-1-10

Earliest Project Forecast Start Date:

Set Data Date and Planned Start to Project Forecast Start during scheduling

Log to file

H:\archish's Documents\SchedLog.txt

Buttons: Cancel, Schedule, View Log, Help, Options...

Project: A01100G

Labor Units: Planned, Actual, Remaining, At Complete

Referenced SPI

Measures: How well the project is following its baseline schedule.

Calculated: By dividing the Value of work completed by the Value of work planned to be completed (to date) as recorded in the baseline (EV/PV).

Why this is important: This measures how closely the project is following its planned schedule dates as recorded in the baseline (This is a *hindsight* metric that assesses past performance).

Green - Within .9 to 1.1

Yellow – .8 to .9 and 1.1 to 1.2

Red– Below .8 and above 1.2

| Project ID | *Baseline Status | *Standard Project Settings | *Standard Activity Settings (%) | *MDL Coverage (%) | *Role/Resource Coverage (%) | *Critical Path Hindrance Factor (%) | Data Date | *Updated Schedule | *Referenced SPI | *Remaining Finish Variance (%) |
|------------|------------------|----------------------------|---------------------------------|-------------------|-----------------------------|-------------------------------------|-----------|-------------------|-----------------|--------------------------------|
| | | | 55.16 | 103.66 | 17.73 | 16.48 | 07/01/10 | | 0.71 | 26.17 |
| A00522B | 🟢 | 🟢 | 82.82 | 288.96 | 0.61 | 57.06 | 07/01/10 | 🟢 | 0.63 | 0.00 |
| A09060D | 🟢 | 🟢 | 72.12 | 11.54 | 0.00 | 9.62 | 07/01/10 | 🟢 | 0.97 | 41.30 |
| A16718P | 🟢 | 🟢 | 80.36 | 75.00 | 32.14 | 15.18 | 07/01/10 | 🟢 | 1.03 | 0.00 |
| A20201W | 🟢 | 🟢 | 25.00 | 353.79 | 0.00 | 7.58 | 07/01/10 | 🟢 | 0.97 | 27.27 |
| A52234E | 🟢 | 🟢 | 43.40 | 23.94 | 12.53 | 10.74 | 07/01/10 | 🟢 | 0.96 | 46.26 |
| A00912D | 🟢 | 🟢 | 78.43 | 10.78 | 1.96 | 13.73 | 07/01/10 | 🟢 | 0.72 | 38.89 |
| A09946S | 🟢 | 🟢 | 32.73 | 63.64 | 19.39 | 13.94 | 07/01/10 | 🟢 | 0.14 | 66.67 |

How to improve SPI

- Accelerate *all* work to “catch up” to the original plan (add resources, complete future work more quickly or in parallel, etc)

Layout: Standard Activity Status* Filter: All Activities

| Activity ID | Activity Name | Planned Duration | Remaining Duration | Schedule % Complete | Start | Finish | Total Float |
|---------------------|--------------------------------|------------------|--------------------|---------------------|---------|---------|-------------|
| SB Ramps RAB | | | | | | | |
| A1040 | SB Ramps RAB - Select Borrow | 15 | 15 | 0% | 6-2-10 | 6-22-10 | -4 |
| A1043 | SB Ramps RAB - CSBC | 5 | 5 | 0% | 6-23-10 | 6-29-10 | -4 |
| A1050 | Lum #'s 12, 11, 10, 7, 15 & 16 | 6 | 6 | 0% | 6-23-10 | 6-30-10 | 15 |
| A1090 | SB Ramps RAB - Drainage | 6 | 6 | 0% | 6-23-10 | 6-30-10 | 15 |
| A1060 | SB Ramps RAB - Curbing | 10 | 10 | 0% | 6-30-10 | 7-14-10 | -4 |
| A1080 | SB Ramps RAB - Truck Apron | 5 | 5 | 0% | 7-15-10 | 7-21-10 | -4 |
| A1070 | SB Ramps RAB - PCCP | 5 | 5 | 0% | 7-15-10 | 7-21-10 | 1 |
| A1200 | SB Ramps RAB - Signing | 5 | 5 | 0% | 7-22-10 | 7-28-10 | -4 |
| A1100 | SB Ramps RAB - Striping | 1 | 1 | 0% | 7-22-10 | 7-22-10 | 1 |
| Stage 4 Prep | | | | | | | |
| | | 20 | 20 | 0% | 6-2-10 | 6-29-10 | 15 |

2010
Apr May Jun Jul Aug

7-28-10

SB Ramps RAB -
SB Ramps RAB
Lum #'s 12, 11,
SB Ramps RAB
SB Ramps F
SB Ramps
SB Ramps
SB Ramps

General Status Resources Relationships

Activity: A1250 Ponds - Erosion Control Project: A01100F

| Duration | Status | Physical % | Labor Units |
|--------------|--------------------------------------------|--------------|----------------|
| Planned: 3 | <input type="checkbox"/> Started: 7-8-10 | 0% | Planned: [] |
| Actual: 0 | <input type="checkbox"/> Finished: 7-12-10 | Suspend: [] | Actual: [] |
| Remaining: 3 | Exp Finish: [] | Resume: [] | Remaining: [] |

Remaining Finish Variance (%)

Measures: The percent of not-completed activities that are at least 10 days late compared to the Baseline.

Calculated: By dividing the number of not-completed activities that are at least 10 days late by the number of not-completed activities in the schedule.

Why this is important: The amount of remaining work that is late compared to the baseline generates a risk factor in on-time delivery (This is a *foresight* metric and looks at the future or forecasted dates of delivery).

Green – Fewer than 15%


Yellow – 15% to 30%

Red – Greater than 30%

| Project ID | *Baseline Status | *Standard Project Settings | *Standard Activity Settings (%) | *MDL Coverage (%) | *Role/Resource Coverage (%) | *Critical Path Hindrance Factor (%) | Data Date | *Updated Schedule | *Referenced SPI | *Remaining Finish Variance (%) |
|------------|------------------|----------------------------|---------------------------------|-------------------|-----------------------------|-------------------------------------|-----------|-------------------|-----------------|--------------------------------|
| | | | 55.16 | 103.66 | 17.73 | 16.48 | 07/01/10 | | 0.71 | 26.17 |
| A00522B | 🟢 | 🟢 | 82.82 | 288.96 | 0.61 | 57.06 | 07/01/10 | 🟢 | 0.63 | 0.00 |
| A09060D | 🟢 | 🟢 | 72.12 | 11.54 | 0.00 | 9.62 | 07/01/10 | 🟢 | 0.97 | 41.30 |
| A16718P | 🟢 | 🟢 | 80.36 | 75.00 | 32.14 | 15.18 | 07/01/10 | 🟢 | 1.03 | 0.00 |
| A20201W | 🟢 | 🟢 | 25.00 | 353.79 | 0.00 | 7.58 | 07/01/10 | 🟢 | 0.97 | 27.27 |
| A52234E | 🟢 | 🟢 | 43.40 | 23.94 | 12.53 | 10.74 | 07/01/10 | 🟢 | 0.96 | 46.26 |
| A00912D | 🟢 | 🟢 | 78.43 | 10.78 | 1.96 | 13.73 | 07/01/10 | 🟢 | 0.72 | 38.89 |
| A09946S | 🟢 | 🟢 | 32.73 | 63.64 | 19.39 | 13.94 | 07/01/10 | 🟢 | 0.14 | 66.67 |

How to improve Remaining Finish Variance (%)

- Using Primavera Scheduler
- Open the project
- Open the Activity Layout - “QA – Remaining Finish Variance”



| Activity ID | Activity Name | Start | Finish | BL Project Finish | Variance - BL Project Finish Date |
|--------------------------------------------|------------------------------------------------------|------------|----------|-------------------|-----------------------------------|
| Filter All: QA - Remaining Finish Variance | | | | | |
| ▣ A00099E | SR 169 and SR 900 Roadside Safety Impro... | 07/28/08 A | 06/06/11 | 07/09/10 | -227d |
| ▣ A00099E.PE | Preliminary Engineering | 07/28/08 A | 06/06/11 | 07/09/10 | -227d |
| ▣ A00099E.PE.PM | General Project Management & Overhead - Prelimina... | 07/28/08 A | 06/06/11 | 07/09/10 | -227d |
| ▣ A00099E.PE.PM.02 | Project Management and Overhead | 07/28/08 A | 06/06/11 | 07/09/10 | -227d |
| 0050 | Project Contingency | 07/28/08 A | 06/06/11 | 07/08/08 | -730d |
| 0040 | Management Reserve (LOE) | 01/08/09 A | 05/03/10 | 02/02/10 | -62d |
| 0025 | Managing the Project Hammock Task (LOE) | 01/08/09 A | 08/25/10 | 07/09/10 | -33d |
| ▣ A00099E.CN | Construction | 03/16/10 A | 08/27/10 | 05/11/10 | -77d |
| ▣ A00099E.CN.10 | Construction Milestones | 03/16/10 A | 08/27/10 | 05/11/10 | -77d |
| ▣ A00099E.CN.10.01 | Contract Execution | 03/16/10 A | 06/01/10 | 05/11/10 | -15d |
| 2595 | Contract Execution | 03/16/10 A | 06/01/10 | 05/11/10 | -15d |
| ▣ A00099E.CN.10.08 | Construction Work Start | 06/02/10 | 08/25/10 | 07/01/08 | -541d |
| 2630 | Construction Work Start | 06/02/10 | 08/25/10 | 07/01/08 | -541d |
| ▣ A00099E.CN.10.21 | Operationally Complete | 08/27/10 | 08/27/10 | 07/01/08 | -543d |
| 2650 | Operationally Complete | 08/27/10 | 08/27/10 | 07/01/08 | -543d |

- Accelerating near-term work, especially *critical path* work, will move many of the planned dates for remaining activities earlier in time, reducing the finish variance of remaining work.

Referenced CPI

Measures: How well the project is following its baseline budget.

Calculated: By dividing the earned value of work by the actual cost of work (EV/AC).

Why this is important: This measures how closely the project is following its planned budget.

Green - Within 90% to 110%

Yellow – 80% to 120%

Red– Outside 80% to 120%

| Project ID | *Referenced CPI | *Funding - BAC Variance (\$) | *Funding - EAC Variance (\$) | *Funding - EAC Variance (%) | *At Complete P6 Cost Variance (%) | *Remaining Authorization | *Remaining Authorization (%) | *MDL Tier w/Budget (%) | *MDL Tier w/Actual Cost (%) |
|------------|-----------------|------------------------------|------------------------------|-----------------------------|-----------------------------------|--------------------------|------------------------------|------------------------|-----------------------------|
| | 1.17 | \$26,386,308.59 | \$142,522,798.59 | 71.91 | 67.59 | | 38.04 | 58.05 | 15.14 |
| A00522B | 0.82 | \$5,052,099.22 | \$4,969,423.08 | 86.83 | -12.32 | \$706,253.50 | 84.08 | 25.81 | 44.44 |
| A09060D | 0.87 | (\$172,736.45) | \$2,188,097.54 | 81.00 | 82.14 | \$49,938.44 | 10.51 | 94.83 | 19.23 |
| A16718P | 1.02 | (\$100,571.27) | (\$118,975.45) | -6.49 | -0.95 | \$42,614.76 | 13.94 | 84.93 | 11.11 |
| A20201W | 0.90 | (\$5,005.08) | (\$17,514.42) | -0.87 | -0.62 | \$45,014.10 | 17.73 | 87.23 | 26.19 |
| A52234E | 1.19 | \$17,568,907.10 | \$131,569,131.39 | 85.28 | 83.39 | \$7,533,565.98 | 33.46 | 0.00 | 9.48 |
| A00912D | 1.31 | (\$0.19) | \$8,626.93 | 0.58 | 0.58 | \$1,236,629.17 | 82.44 | 74.51 | 20.83 |
| A09946S | 1.09 | \$6,989,778.77 | \$6,884,404.15 | 42.15 | -1.13 | \$436,404.47 | 27.11 | 71.72 | 7.58 |

How to improve CPI

- Improve efficiency; Complete remaining work for lower actual cost than planned and budgeted in the baseline

Layout: Standard Activity Status* Filter: All Activities

| Activity ID | Activity Name | Planned Duration | Remaining Duration | Schedule % Complete | Start | Finish | Total Float |
|---------------------|--------------------------------|------------------|--------------------|---------------------|---------|---------|-------------|
| SB Ramps RAB | | | | | | | |
| A1040 | SB Ramps RAB - Select Borrow | 15 | 15 | 0% | 6-2-10 | 6-22-10 | -4 |
| A1043 | SB Ramps RAB - CSBC | 5 | 5 | 0% | 6-23-10 | 6-29-10 | -4 |
| A1050 | Lum #'s 12, 11, 10, 7, 15 & 16 | 6 | 6 | 0% | 6-23-10 | 6-30-10 | 15 |
| A1090 | SB Ramps RAB - Drainage | 6 | 6 | 0% | 6-23-10 | 6-30-10 | 15 |
| A1060 | SB Ramps RAB - Curbing | 10 | 10 | 0% | 6-30-10 | 7-14-10 | -4 |
| A1080 | SB Ramps RAB - Truck Apron | 5 | 5 | 0% | 7-15-10 | 7-21-10 | -4 |
| A1070 | SB Ramps RAB - PCCP | 5 | 5 | 0% | 7-15-10 | 7-21-10 | 1 |
| A1200 | SB Ramps RAB - Signing | 5 | 5 | 0% | 7-22-10 | 7-28-10 | -4 |
| A1100 | SB Ramps RAB - Striping | 1 | 1 | 0% | 7-22-10 | 7-22-10 | 1 |
| Stage 4 Prep | | | | | | | |
| | | 20 | 20 | 0% | 6-2-10 | 6-29-10 | 15 |

2010
Apr May Jun Jul Aug

7-28-10

SB Ramps RAB -
SB Ramps RAB
Lum #'s 12, 11,
SB Ramps RAB
SB Ramps F
SB Ramps
SB Ramps
SB Ramps

General Status Resources Relationships

Activity: A1250 Ponds - Erosion Control Project: A01100F

| Duration | Status | Physical % | Labor Units |
|--------------|--------------------------------------------|--------------|----------------|
| Planned: 3 | <input type="checkbox"/> Started: 7-8-10 | 0% | Planned: [] |
| Actual: 0 | <input type="checkbox"/> Finished: 7-12-10 | Suspend: [] | Actual: [] |
| Remaining: 3 | Exp Finish: [] | Resume: [] | Remaining: [] |

Funding – BAC Variance (\$)

Measures: The alignment of the projected at complete cost in the baseline (BAC; Baseline At Complete) to the amount of funding held in CPMS for the WIN.

Calculated: By subtracting the BAC value from the CPMS Current funding level for the WIN.

Why this is important: Accurate forecasted costs in the baseline are essential for cost and schedule metrics such as CPI, SPI, To Complete requirements, At Complete Variances, etc.

Green – Zero variance

Yellow – Positive or Negative variance

| Project ID | *Referenced CPI | *Funding - BAC Variance (\$) | *Funding - EAC Variance (\$) | *Funding - EAC Variance (%) | *At Complete P6 Cost Variance (%) | *Remaining Authorization | *Remaining Authorization (%) | *MDL Tier w/Budget (%) | *MDL Tier w/Actual Cost (%) |
|------------|-----------------|------------------------------|------------------------------|-----------------------------|-----------------------------------|--------------------------|------------------------------|------------------------|-----------------------------|
| | 1.17 | \$26,386,308.59 | \$142,522,798.59 | 71.91 | 67.59 | | 38.04 | 58.05 | 15.14 |
| A00522B | 0.82 | \$5,052,099.22 | \$4,969,423.08 | 86.83 | -12.32 | \$706,253.50 | 84.08 | 25.81 | 44.44 |
| A09060D | 0.87 | (\$172,736.45) | \$2,188,097.54 | 81.00 | 82.14 | \$49,938.44 | 10.51 | 94.83 | 19.23 |
| A16718P | 1.02 | (\$100,571.27) | (\$118,975.45) | -6.49 | -0.95 | \$42,614.76 | 13.94 | 84.93 | 11.11 |
| A20201W | 0.90 | (\$5,005.08) | (\$17,514.42) | -0.87 | -0.62 | \$45,014.10 | 17.73 | 87.23 | 26.19 |
| A52234E | 1.19 | \$17,568,907.10 | \$131,569,131.39 | 85.28 | 83.39 | \$7,533,565.98 | 33.46 | 0.00 | 9.48 |
| A00912D | 1.31 | (\$0.19) | \$8,626.93 | 0.58 | 0.58 | \$1,236,629.17 | 82.44 | 74.51 | 20.83 |
| A09946S | 1.09 | \$6,989,778.77 | \$6,884,404.15 | 42.15 | -1.13 | \$436,404.47 | 27.11 | 71.72 | 7.58 |

How to improve Funding – BAC Variance

- Correct the sum of your line-item Project Baseline budgeted values to match current funding levels

Layout: Standard Activity Status* Filter: All Activities

| Activity ID | Activity Name | BL Project Total Cost | Planned Duration | Remaining Duration | S |
|-------------|------------------------------------------------------------------------------|-----------------------|------------------|--------------------|---|
| | SR 11/I-5 Interchange-Josh Wilson Rd-Rebuild Intercha... | \$11,222,728 | 2085 | 997 | |
| | Preliminary Engineering | \$2,400,224 | 1110 | 22 | |
| | PE-ACT PE Actual Costs | \$0 | 0 | 0 | |
| | + General Project Management & Overhead - Preliminary Engineering | \$1,901,908 | 157 | 22 | |
| | + Environmental Review and Permitting | \$12,592 | 173 | 0 | |
| | + Project Development | \$485,725 | 273 | 0 | |
| | + Right of Way | \$100,000 | 465 | 0 | |
| | + Construction | \$8,722,504 | 1020 | 997 | |
| | SR 14/Dodder Creek Fish Barrier Removal | \$0 | 1075 | 916 | |

Funding – EAC Variance (\$,%)

Measures: Whether the project will be delivered on-budget, regardless of Baseline accuracy.

Calculated: By subtracting the Schedule’s Estimate At Complete value from the amount of funding held in CPMS for the WIN.

Why this is important: This is a stop-gap measure to provide an accurate assessment of on-budget performance in cases where baselines do not exist or hold incorrect BAC values. This metric in percent form provides a GMAP-based assessment of “on-budget” performance (within 5%)

Green – Dollar form- Below funding; Percent form- Less than 5% over funding level

Yellow – Dollar form - Exceeds funding; Percent form– More than 5% over funding level

| Project ID | *Referenced CPI | *Funding - BAC Variance (\$) | *Funding - EAC Variance (\$) | *Funding - EAC Variance (%) | *At Complete P6 Cost Variance (%) | *Remaining Authorization | *Remaining Authorization (%) | *MDL Tier w/Budget (%) | *MDL Tier w/Actual Cost (%) |
|------------|-----------------|------------------------------|------------------------------|-----------------------------|-----------------------------------|--------------------------|------------------------------|------------------------|-----------------------------|
| | 🚩 1.17 | 🚩 \$26,386,308.59 | 🟢 \$142,522,798.59 | 🟢 71.91 | 🟢 67.59 | | 🟢 38.04 | 🚩 58.05 | 🚩 15.14 |
| A00522B | 🚩 0.82 | 🚩 \$5,052,099.22 | 🟢 \$4,969,423.08 | 🟢 86.83 | 🚩 -12.32 | \$706,253.50 | 🟢 84.08 | 🚩 25.81 | 🟢 44.44 |
| A09060D | 🚩 0.87 | 🚩 (\$172,736.45) | 🟢 \$2,188,097.54 | 🟢 81.00 | 🟢 82.14 | \$49,938.44 | 🚩 10.51 | 🟢 94.83 | 🟢 19.23 |
| A16718P | 🟢 1.02 | 🚩 (\$100,571.27) | 🚩 (\$118,975.45) | 🚩 -6.49 | 🟢 -0.95 | \$42,614.76 | 🚩 13.94 | 🚩 84.93 | 🟢 11.11 |
| A20201W | 🟢 0.90 | 🚩 (\$5,005.08) | 🚩 (\$17,514.42) | 🟢 -0.87 | 🟢 -0.62 | \$45,014.10 | 🟢 17.73 | 🟢 87.23 | 🟢 26.19 |
| A52234E | 🚩 1.19 | 🚩 \$17,568,907.10 | 🟢 \$131,569,131.39 | 🟢 85.28 | 🟢 83.39 | \$7,533,565.98 | 🟢 33.46 | 🚩 0.00 | 🟢 9.48 |
| A00912D | 🚩 1.31 | 🚩 (\$0.19) | 🟢 \$8,626.93 | 🟢 0.58 | 🟢 0.58 | \$1,236,629.17 | 🟢 82.44 | 🚩 74.51 | 🟢 20.83 |
| A09946S | 🟢 1.09 | 🚩 \$6,989,778.77 | 🟢 \$6,884,404.15 | 🟢 42.15 | 🟢 -1.13 | \$436,404.47 | 🟢 27.11 | 🚩 71.72 | 🟢 7.58 |

How to improve Funding – EAC Variance

- Update your current schedule's remaining costs so that when combined with actual costs, the at complete cost is an accurate representation of the estimated final cost of the project. Ideally, this will match current funding levels for the WIN; If not, report the estimated cost at complete and adjust CPMS forecasts for the Phase and WIN. A PCRf may be required.

| Layout: Standard Activity Status* | | Filter: All Activities | | |
|-----------------------------------|----------------------------------------------------------------------------|------------------------|----------------------|--------------------------|
| Activity ID | Activity Name | Actual Total Cost | Remaining Total Cost | At Completion Total Cost |
| SR 11/I-5 Interchange | Josh Wilson Rd-Rebuild Intercha... | \$3,853,207 | \$9,086,429 | \$12,939,636 |
| - | Preliminary Engineering | \$2,416,696 | \$115,844 | \$2,532,541 |
| | PE-ACT PE Actual Costs | \$2,093,083 | \$0 | \$2,093,083 |
| + | General Project Management & Overhead - Preliminary Engineering | \$104,297 | \$111,444 | \$215,741 |
| + | Environmental Review and Permitting | \$0 | \$2,100 | \$2,100 |
| + | Project Development | \$219,316 | \$2,300 | \$221,616 |
| + | Right of Way | \$112,719 | \$43,359 | \$156,078 |
| + | Construction | \$1,323,791 | \$8,927,226 | \$10,251,017 |
| SR 14/Dodder Creek | Fish Barrier Removal | \$51,170 | \$0 | \$51,170 |

At Complete P6 Cost Variance (%)

Measures: Predicts if the baseline budget will be exceeded before the end of project.

Calculated: By subtracting the estimate at completion from the baseline budget and dividing by the baseline budget “(EAC-BAC)/BAC”

Why this is important: This measures the project’s variance from its planned at complete cost as recorded in the Project Baseline.

Green – Less than -5% Variance

Yellow – 5% to -20% Variance

Red – Over -20% Variance

| Project ID | *Referenced CPI | *Funding - BAC Variance (\$) | *Funding - EAC Variance (\$) | *Funding - EAC Variance (%) | *At Complete P6 Cost Variance (%) | *Remaining Authorization | *Remaining Authorization (%) | *MDL Tier w/Budget (%) | *MDL Tier w/Actual Cost (%) |
|------------|-----------------|------------------------------|------------------------------|-----------------------------|-----------------------------------|--------------------------|------------------------------|------------------------|-----------------------------|
| | 1.17 | \$26,386,308.59 | \$142,522,798.59 | 71.91 | 67.59 | | 38.04 | 58.05 | 15.14 |
| A00522B | 0.82 | \$5,052,099.22 | \$4,969,423.08 | 86.83 | -12.32 | \$706,253.50 | 84.08 | 25.81 | 44.44 |
| A09060D | 0.87 | (\$172,736.45) | \$2,188,097.54 | 81.00 | 82.14 | \$49,938.44 | 10.51 | 94.83 | 19.23 |
| A16718P | 1.02 | (\$100,571.27) | (\$118,975.45) | -6.49 | -0.95 | \$42,614.76 | 13.94 | 84.93 | 11.11 |
| A20201W | 0.90 | (\$5,005.08) | (\$17,514.42) | -0.87 | -0.62 | \$45,014.10 | 17.73 | 87.23 | 26.19 |
| A52234E | 1.19 | \$17,568,907.10 | \$131,569,131.39 | 85.28 | 83.39 | \$7,533,565.98 | 33.46 | 0.00 | 9.48 |
| A00912D | 1.31 | (\$0.19) | \$8,626.93 | 0.58 | 0.58 | \$1,236,629.17 | 82.44 | 74.51 | 20.83 |
| A09946S | 1.09 | \$6,989,778.77 | \$6,884,404.15 | 42.15 | -1.13 | \$436,404.47 | 27.11 | 71.72 | 7.58 |

How to improve At Complete P6 Cost Variance (%)

- First, be sure BAC values are correct and aligned to WIN funding levels
- Update your current schedule's remaining costs so that when combined with actual costs, the at complete cost closely matches the true estimate at complete
- If all forecasts in the baseline and the current schedule are correct and significant variation still exists, report the variance and update CPMS forecasts for the WIN. A PCRf may be required- If approved, update the baseline values for future work and review any further variances.

| Layout: Standard Activity Status* | | Filter: All Activities | | | | |
|-----------------------------------------|----------------------------------------------------------|------------------------|----------------------|--------------------------|-----------------------|----------------------------------|
| Activity ID | Activity Name | Actual Total Cost | Remaining Total Cost | At Completion Total Cost | BL Project Total Cost | Variance - BL Project Total Cost |
| SR 11/I-5 | Interchange~Josh Wilson Rd-Rebuil... | \$3,853,207 | \$9,086,429 | \$12,939,636 | \$11,222,728 | (\$1,716,907) |
| + | Preliminary Engineering | \$2,416,696 | \$115,844 | \$2,532,541 | \$2,400,224 | (\$132,316) |
| | PE-ACT PE Actual Costs | \$2,093,083 | \$0 | \$2,093,083 | \$0 | (\$2,093,083) |
| + | General Project Management & Overhead - Preliminary E... | \$104,297 | \$111,444 | \$215,741 | \$1,901,908 | \$1,686,167 |
| + | Environmental Review and Permitting | \$0 | \$2,100 | \$2,100 | \$12,592 | \$10,492 |
| + | Project Development | \$219,316 | \$2,300 | \$221,616 | \$485,725 | \$264,108 |
| + | Right of Way | \$112,719 | \$43,359 | \$156,078 | \$100,000 | (\$56,078) |
| + | Construction | \$1,323,791 | \$8,927,226 | \$10,251,017 | \$8,722,504 | (\$1,528,513) |
| SR 14/Dodder Creek Fish Barrier Removal | | \$61,170 | \$0 | \$61,170 | \$0 | (\$61,170) |

Remaining Authorization (\$,%)

Measures: Percentage of authorization remaining on the work order.

Calculated: By dividing the remaining work order authorization by the total work order authorization “(Total Authorization - Actual Cost) / Total Authorization”.

Why this is important: This measure provides a warning when the project is low on authorized funds.

Green - 15% and over

Yellow – 1% to 15%

Red – 1% or Less, or negative

| Project ID | *Referenced CPI | *Funding - BAC Variance (\$) | *Funding - EAC Variance (\$) | *Funding - EAC Variance (%) | *At Complete P6 Cost Variance (%) | *Remaining Authorization | *Remaining Authorization (%) | *MDL Tier w/Budget (%) | *MDL Tier w/Actual Cost (%) |
|------------|-----------------|------------------------------|------------------------------|-----------------------------|-----------------------------------|--------------------------|------------------------------|------------------------|-----------------------------|
| | 1.17 | \$26,386,308.59 | \$142,522,798.59 | 71.91 | 67.59 | | 38.04 | 58.05 | 15.14 |
| A00522B | 0.82 | \$5,052,099.22 | \$4,969,423.08 | 86.83 | -12.32 | \$706,253.50 | 84.08 | 25.81 | 44.44 |
| A09060D | 0.87 | (\$172,736.45) | \$2,188,097.54 | 81.00 | 82.14 | \$49,938.44 | 10.51 | 94.83 | 19.23 |
| A16718P | 1.02 | (\$100,571.27) | (\$118,975.45) | -6.49 | -0.95 | \$42,614.76 | 13.94 | 84.93 | 11.11 |
| A20201W | 0.90 | (\$5,005.08) | (\$17,514.42) | -0.87 | -0.62 | \$45,014.10 | 17.73 | 87.23 | 26.19 |
| A52234E | 1.19 | \$17,568,907.10 | \$131,569,131.39 | 85.28 | 83.39 | \$7,533,565.98 | 33.46 | 0.00 | 9.48 |
| A00912D | 1.31 | (\$0.19) | \$8,626.93 | 0.58 | 0.58 | \$1,236,629.17 | 82.44 | 74.51 | 20.83 |
| A09946S | 1.09 | \$6,989,778.77 | \$6,884,404.15 | 42.15 | -1.13 | \$436,404.47 | 27.11 | 71.72 | 7.58 |

How to improve Remaining Authorization (\$,%)

- Submit a request to increase your work order authorization total



**Washington State
Department of Transportation**

WORK ORDER AUTHORIZATION

WORK ORDER: MS 3222

WORK ITEM: H00011A

PIN: 000011A

PHASE: PE RW CN

SOURCE OF FUNDS: State Federal
 Local TIE ER

WOA TYPE: Perpetual Biennial

Reimbursable From: _____

| Receivable Agmt # | % / AMT | Date Executed |
|-------------------|---------|---------------|
| _____ | _____ | _____ |

DATE SENT: Mar 24, 1998 DATE REC'D: Mar 24, 1998

WOA TITLE: Roadway Design Software Maintenance

WORK DESC: Maintenance and Support of CAICE

ORG# / MGR: 303080/Jim Michal

COUNTY(S): 34 THURSTON SR(s): _____ From: MP: To: _____

PREVIOUS AUTHORIZATION: _____ \$0.00

Group Category:

- 01 Work Done Contractor _____
- 02 Work Done Others _____
- Payable Agmt # _____
- 03 Engineering _____
- 04 State Force Work 180,000.00
- 05 Material Furnished _____
- 06 Contingencies _____
- 07 R/W Acquisition(need true cost) _____
- 08 R/W Other _____
- 99 Vendor Supplied Serv. & Matls. _____

NEW TOTAL AUTHORIZATION \$180,000.00

FOR FA PROJECTS ONLY

| FA No. | FA % | FA Approp | FHWA Auth Date |
|--------|-------|-----------|----------------|
| _____ | _____ | _____ | _____ |

R/W cert to OSC Y N/A STIP Ref: _____

Design Approv _____ NEPA _____

The CE / PE costs equal _____ % of current est. construction

| PIN | Sub Pqgm | Fund Acct | Legis Approp | Finance Codes | Amt Change | Control Section | Distr % by Cost Sect | Notes: |
|---------|----------|-----------|--------------|---------------|------------|-----------------|----------------------|------------------------|
| 000011A | P3 | 108 | A10 | AA | 180,000.00 | 3400NT | 100 | New Setup \$180,000.00 |

MDL Tier w/Budget (%)

Definition: Activities that have a low-level MDL code and a WorkOp code

Measures: The percentage of MDL Tier activities that have budgets assigned.

Calculated: By dividing the number of MDL Tier activities with budgets by total number of MDL Tier activities.

Why this is important: When budgets exist on lower-level deliverables, management of cost forecasts by period becomes more productive and more accurate.


Green – Greater than 85%

Yellow – Less than 85%

| Project ID | *Referenced CPI | *Funding - BAC Variance (\$) | *Funding - EAC Variance (\$) | *Funding - EAC Variance (%) | *At Complete P6 Cost Variance (%) | *Remaining Authorization | *Remaining Authorization (%) | *MDL Tier w/Budget (%) | *MDL Tier w/Actual Cost (%) |
|------------|-----------------|------------------------------|------------------------------|-----------------------------|-----------------------------------|--------------------------|------------------------------|------------------------|-----------------------------|
| | 1.17 | \$26,386,308.59 | \$142,522,798.59 | 71.91 | 67.59 | | 38.04 | 58.05 | 15.14 |
| A00522B | 0.82 | \$5,052,099.22 | \$4,969,423.08 | 86.83 | -12.32 | \$706,253.50 | 84.08 | 25.81 | 44.44 |
| A09060D | 0.87 | (\$172,736.45) | \$2,188,097.54 | 81.00 | 82.14 | \$49,938.44 | 10.51 | 94.83 | 19.23 |
| A16718P | 1.02 | (\$100,571.27) | (\$118,975.45) | -6.49 | -0.95 | \$42,614.76 | 13.94 | 84.93 | 11.11 |
| A20201W | 0.90 | (\$5,005.08) | (\$17,514.42) | -0.87 | -0.62 | \$45,014.10 | 17.73 | 87.23 | 26.19 |
| A52234E | 1.19 | \$17,568,907.10 | \$131,569,131.39 | 85.28 | 83.39 | \$7,533,565.98 | 33.46 | 0.00 | 9.48 |
| A00912D | 1.31 | (\$0.19) | \$8,626.93 | 0.58 | 0.58 | \$1,236,629.17 | 82.44 | 74.51 | 20.83 |
| A09946S | 1.09 | \$6,989,778.77 | \$6,884,404.15 | 42.15 | -1.13 | \$436,404.47 | 27.11 | 71.72 | 7.58 |

How to improve MDL Tier w/Budget (%)

- Using Primavera Scheduler
- Open the project
- Open the Activity Layout -
“QA – MDL Tier Without Budget”



| Layout: QA - MDL Tier Without Budget | | Filter All: QA - MDL Tier Without Budget | | | | |
|--------------------------------------|------------------------------------------------------|------------------------------------------|-------------|-------------------------|--------------|---------------------|
| Activity ID | Activity Name | Start | Finish | Master Deliverable List | Work Op Code | Budgeted Total Cost |
| A00099E | SR 169 and SR 900 Roadside Safety Improvement | 07/01/08 A | 02/01/10 | | | \$0.00 |
| A00099E.PE | Preliminary Engineering | 07/01/08 A | 02/01/10... | | | \$0.00 |
| A00099E.PE.EV | Environmental Review and Permitting | 03/10/09 A | 11/06/09... | | | \$0.00 |
| A00099E.PE.EV.01 | Endangered Species Act Compliance | 03/10/09 A | 05/04/09... | | | \$0.00 |
| 0335 | Environmental Biological Assessment - NE Letter Sent | 03/10/09 A | 05/04/09... | PE.EV.01.01 | 0132 | \$0.00 |
| A00099E.PE.PD | Project Development | 07/22/08 A | 02/01/10... | | | \$0.00 |
| A00099E.PE.PD.06 | Project Data, Survey Data and Basemap | 01/20/09 A | 03/17/09... | | | \$0.00 |
| 1055 | As-Built Data Verified | 01/20/09 A | 01/27/09... | PE.PD.06.10.05 | 0116 | \$0.00 |
| 1060 | Maintenance Review Documentation | 02/24/09 A | 03/17/09... | PE.PD.06.10.06 | 0116 | \$0.00 |
| A00099E.PE.PD.34 | Traffic Analysis | 07/29/08 A | 07/29/08... | | | \$0.00 |
| 1560 | Collision Data | 07/29/08 A | 07/29/08... | PE.PD.34.10 | 0150 | \$0.00 |
| A00099E.PE.PD.75 | Constructability Reviews | 07/22/08 A | 11/24/09... | | | \$0.00 |
| 1930 | Scoping Phase Review (PDR) | 07/22/08 A | 07/22/08... | PE.PD.75.01 | 0180 | \$0.00 |
| 1952 | Address 90% CN Review Comments | 11/24/09 A | 11/24/09... | PE.PD.75.90 | 0180 | \$0.00 |

- Review and Distribute Budget to every activity that appears on this layout.

MDL Tier w/Actual Cost (%)

Definition: Activities that have a low-level MDL code and a WorkOp code

Measures: The percentage of MDL Tier activities that have actual costs assigned.

Calculated: By dividing the number of MDL Tier activities with actuals by the total number of MDL Tier activities.

Why this is important: When actual costs exist on lower-level deliverables and are aligned to lower-level budget values, management of costs by deliverable becomes more productive and more accurate.


Green - Greater than 85%

Yellow – Less than 85%

| Project ID | *Referenced CPI | *Funding - BAC Variance (\$) | *Funding - EAC Variance (\$) | *Funding - EAC Variance (%) | *At Complete P6 Cost Variance (%) | *Remaining Authorization | *Remaining Authorization (%) | *MDL Tier w/Budget (%) | *MDL Tier w/Actual Cost (%) |
|------------|-----------------|------------------------------|------------------------------|-----------------------------|-----------------------------------|--------------------------|------------------------------|------------------------|-----------------------------|
| | 1.17 | \$26,386,308.59 | \$142,522,798.59 | 71.91 | 67.59 | | 38.04 | 58.05 | 15.14 |
| A00522B | 0.82 | \$5,052,099.22 | \$4,969,423.08 | 86.83 | -12.32 | \$706,253.50 | 84.08 | 25.81 | 44.44 |
| A09060D | 0.87 | (\$172,736.45) | \$2,188,097.54 | 81.00 | 82.14 | \$49,938.44 | 10.51 | 94.83 | 19.23 |
| A16718P | 1.02 | (\$100,571.27) | (\$118,975.45) | -6.49 | -0.95 | \$42,614.76 | 13.94 | 84.93 | 11.11 |
| A20201W | 0.90 | (\$5,005.08) | (\$17,514.42) | -0.87 | -0.62 | \$45,014.10 | 17.73 | 87.23 | 26.19 |
| A52234E | 1.19 | \$17,568,907.10 | \$131,569,131.39 | 85.28 | 83.39 | \$7,533,565.98 | 33.46 | 0.00 | 9.48 |
| A00912D | 1.31 | (\$0.19) | \$8,626.93 | 0.58 | 0.58 | \$1,236,629.17 | 82.44 | 74.51 | 20.83 |
| A09946S | 1.09 | \$6,989,778.77 | \$6,884,404.15 | 42.15 | -1.13 | \$436,404.47 | 27.11 | 71.72 | 7.58 |

How to improve MDL Tier w/Actual Cost (%)

- Using Primavera Scheduler
- Open the project
- Open the Activity Layout -
“QA – MDL Tier Without Actual Cost”



| Activity ID | Activity Name | Start | Finish | Master Deliverable List | Work Op Code | Actual Total Cost |
|---------------------------------------------------------------|---------------------------------|-------------|-------------|-------------------------|--------------|-------------------|
| A00099E SR 169 and SR 900 Roadside Safety Improvement | | | | | | |
| 1051 | Additional Clear Zone Inventory | 10/27/09... | 11/06/09... | PE.PD.06.10.04 | 0116 | \$0.00 |
| 1610 | Sign Inventory | 10/27/09... | 11/06/09... | PE.PD.36.10 | 01TA | \$0.00 |
| A00099E.PE Preliminary Engineering | | | | | | |
| A00099E.PE.PS Project Planning and Scoping | | | | | | |
| A00099E.PE.PS.01 Preliminary Estimates & Schedules | | | | | | |
| 0160 | PE Estimate | 07/01/08... | 07/01/08... | PE.PS.01.01 | 01AP | \$0.00 |
| 0170 | CN Estimate | 07/09/08... | 07/15/08... | PE.PS.01.03 | 01AC | \$0.00 |
| A00099E.PE.PS.08 Project Summary | | | | | | |
| 0300 | Project Definition | 07/16/08... | 07/22/08... | PE.PS.08.01 | 0169 | \$0.00 |
| 0305 | Design Decisions Summary | 07/16/08... | 07/23/08... | PE.PS.08.02 | 0169 | \$0.00 |
| 0310 | Environmental Review Summary | 07/16/08... | 07/22/08... | PE.PS.08.03 | 0169 | \$0.00 |

- Review and distribute actual costs to activities appearing on this layout.

Thick Client Metrics & Indicators

Instructions to Regional Primavera
Administrators

Thick Client Metrics & Indicators

10 Global Changes are available to allow Project Controllers to quickly and easily populate activity-level indicators for some of the metrics discussed above:

- *Pop Critical Path Hindered Indicators
- *Pop IP/Comp MDL Tier w/AC Indicators #1
- *Pop IP/Comp MDL Tier w/AC Indicators #2
- *Pop MDL Indicators
- *Pop MDL Tier w/Budget Indicators #1
- *Pop MDL Tier w/Budget Indicators #2
- *Pop Remaining Finish Var Indicators #1
- *Pop Remaining Finish Var Indicators #2
- *Pop Responsibility Indicators
- *Pop Standard Act Settings Indicators

Note that some Global Change processes have two steps (#1 and #2)

Thick Client Metrics & Indicators (Cont'd)

| Layout: QC - *Metric Indicators (Thick Client) | | Filter: All Activities | | | | | | |
|------------------------------------------------------------------------------------------|----------------------------------------------------------------------|---------------------------|------------------|-------------------------|--------------------|--------------------------|-----------------------------|-------------------------|
| Activity ID | Activity Name | *Baseline Finish Variance | *MDL Assignments | *MDL Tier w/Actual Cost | *MDL Tier w/Budget | *Responsibility Coverage | *Standard Activity Settings | *Critical Path Hindered |
| A01818U SR 18/Issaquah-Hobart Rd. - Retaining Wall Repair | | | | | | | | |
| A01818U.PE Preliminary Engineering | | | | | | | | |
| PE-ACT | PE Actual Costs | | | | | | | |
| A01818U.PE.PM General Project Management & Overhead - Preliminary Engineering | | | | | | | | |
| A01818U.PE.PM.01 Begin Preliminary Engineering | | | | | | | | |
| 0015 | Begin Preliminary Engineering | | 🟢 | | | ⚠️ | ⚠️ | ⚠️ |
| A01818U.PE.PM.02 Project Management and Overhead | | | | | | | | |
| 0025 | General Project Management (Project Office) | ⚠️ | 🟢 | ⚠️ | 🟢 | 🟢 | ⚠️ | ⚠️ |
| 0035 | Environmental Project Management and Overhead | ⚠️ | ⚠️ | | | ⚠️ | ⚠️ | ⚠️ |
| 0040 | Redistributed PE Project Management and Overhead (HQ & Region) (LOE) | ⚠️ | 🟢 | ⚠️ | 🟢 | ⚠️ | ⚠️ | ⚠️ |
| 0041 | Project Contingency | | ⚠️ | | | ⚠️ | ⚠️ | ⚠️ |
| A01818U.PE.PM.03 Project Management Plan Development & Maintenance | | | | | | | | |
| 0065 | WSDOT Project Management Plan (PMP) | | 🟢 | 🟢 | 🟢 | 🟢 | 🟢 | 🟢 |
| 0070 | PMP Endorsement | | 🟢 | | | ⚠️ | ⚠️ | 🟢 |
| 0075 | Project Handoff | ❌ | ⚠️ | | | ⚠️ | 🟢 | 🟢 |
| A01818U.PE.PS Project Planning and Scoping | | | | | | | | |
| A01818U.PE.PS.01 Preliminary Estimates & Schedules | | | | | | | | |
| 0160 | PE Estimate | | 🟢 | ⚠️ | ⚠️ | ⚠️ | 🟢 | 🟢 |
| 0165 | RW Estimate | | 🟢 | ⚠️ | ⚠️ | ⚠️ | 🟢 | 🟢 |
| 0170 | CN Estimate | | 🟢 | ⚠️ | ⚠️ | ⚠️ | 🟢 | 🟢 |
| A01818U.PE.PS.03 Public Involvement for Planning | | | | | | | | |
| 0210 | Public Involvement | ⚠️ | 🟢 | ⚠️ | 🟢 | ⚠️ | ⚠️ | 🟢 |
| A01818U.PE.PS.07 Pre-Design Study | | | | | | | | |
| 0290 | Pre-Design Study | | 🟢 | ⚠️ | 🟢 | ⚠️ | 🟢 | 🟢 |
| A01818U.PE.PS.08 Project Summary | | | | | | | | |
| 0300 | Project Definition | | 🟢 | ⚠️ | ⚠️ | ⚠️ | 🟢 | 🟢 |
| 0305 | Design Decisions Summary | | 🟢 | ⚠️ | ⚠️ | ⚠️ | 🟢 | 🟢 |
| 0310 | Environmental Review Summary | | 🟢 | ⚠️ | ⚠️ | ⚠️ | 🟢 | 🟢 |

Thick Client Metrics & Indicators – How do they work?

Critical Path Hindered Activities

*Pop Critical Path Hindered Indicators

Looks for Critical Path obstructions and flags activities that do not support a critical path schedule (constraints, LOE's, missing predecessors or successors) and places a yellow flag on the activity; Also removes all other indicators (e.g. old flags from previous updates)

Results:

The Critical Path Hindered Activities process results in:

- A yellow indicator placed on any activity that does not support critical path schedules

Optional Feature:

- Secure code available to filter out acceptable deviations from critical path hindered lists. Use of this code is optional.

Thick Client Metrics & Indicators – How do they work? (Cont'd)

Remaining Finish Variance

*Pop Remaining Finish Var Indicators #1

Part 1 looks for In-Progress and Not Started Activities and flags those that exceed [negative] -10 days of total float with a yellow indicator. It then removes all other indicators (e.g. old indicators)

*Pop Remaining Finish Var Indicators #2

Part 2 looks for Activities that are not in the baseline and flags each one with a red indicator

Results:

The Remaining Finish Variance process results in:

- A yellow indicator on activities that are impacting the critical path by more than 10 days
- A red indicator on activities that are in the schedule but not in the baseline
- No indicator on all other activities

Thick Client Metrics & Indicators – How do they work? (Cont'd)

Standard Activity Settings

*Pop Standard Act Settings Indicators

Looks for activities that meet pre-established standard (calendars, duration types, and percent complete types) and flags them with a green indicator; Flags all other activities with a yellow indicator

Results:

The Standard Activity Settings process results in:

- A green indicator placed on all activities that hold all three standards
- A yellow indicator placed on all activities that do not hold all three standards

Optional Feature:

- Secure code available to filter out acceptable deviations from standard settings. Use of this code is optional.

Thick Client Metrics & Indicators – How do they work? (Cont'd)

MDL Assignments

*Pop MDL Indicators

Looks for activities that have an MDL code and flags them with a green indicator; All activities that do not have an MDL Code are flagged with a yellow indicator

Results:

The MDL Assignments process results in:

- A green indicator placed on all activities that hold an MDL Code
- A yellow indicator placed on all activities that do not hold an MDL Code

Thick Client Metrics & Indicators – How do they work? (Cont'd)

MDL Tier w/Budget

*Pop MDL Tier w/Budget Indicators #1

Looks for activities that have an MDL code (other than the top-level of PE, RW, CN) and a WorkOp code and flags those that have a budgeted cost applied with a green indicator; Also removes all other indicators from all other activities

*Pop MDL Tier w/Budget Indicators #2

Looks for activities that have an MDL code (other than the top-level of PE, RW, CN) and a WorkOp code and flags those that DO NOT have a budgeted cost applied with a yellow indicator

Results:

The MDL Tier w/Budget process results in:

- A green indicator placed on all activities that hold an MDL Code AND a WorkOp Code AND budgeted cost
- A yellow indicator placed on all activities that hold an MDL Code AND a WorkOp Code AND NO budgeted cost
- A blank indicator for all other activities

Thick Client Metrics & Indicators – How do they work? (Cont'd)

MDL Tier w/Actuals

*Pop IP/Comp MDL Tier w/AC Indicators #1

Looks for ALL activities that have an MDL code (other than the top-level of PE, RW, CN) and a WorkOp code and flags those that have an actual cost applied with a green indicator; Also removes all other indicators from all other activities

*Pop IP/Comp MDL Tier w/AC Indicators #2

Looks for In-Progress and Completed activities that have an MDL code (other than the top-level of PE, RW, CN) and a WorkOp code and flags those that DO NOT have an actual cost applied with a yellow indicator

Results:

The MDL Tier w/Budget process results in:

- A green indicator placed on all activities that hold an MDL Code AND a WorkOp Code AND actual cost
- A yellow indicator placed on all In-Progress and Completed activities that hold an MDL Code AND a WorkOp Code AND NO actual cost
- A blank indicator for all other activities

Thick Client Metrics & Indicators – Results

Every appropriate activity in your schedule will hold an indicator for each metric discussed above allowing simplified identification of potential problems or inconsistencies

Open the activity layout “QC – Metric Indicators (Thick Client)” to view results

Layout: QC - *Metric Indicators (Thick Client) Filter: All Activities

| Activity ID | Activity Name | *Baseline Finish Variance | *MDL Assignments | *MDL Tier w/Actual Cost | *MDL Tier w/Budget | *Responsibility Coverage | *Standard Activity Settings | *Critical Path Hindered |
|------------------------------------------------------------------------------------------|----------------------------------------------------------------------|---------------------------|------------------|-------------------------|--------------------|--------------------------|-----------------------------|-------------------------|
| A01818U SR 18/Issaquah-Hobart Rd. - Retaining Wall Repair | | | | | | | | |
| A01818U.PE Preliminary Engineering | | | | | | | | |
| PE-ACT | PE Actual Costs | | | | | | | |
| A01818U.PE.PM General Project Management & Overhead - Preliminary Engineering | | | | | | | | |
| A01818U.PE.PM.01 Begin Preliminary Engineering | | | | | | | | |
| 0015 | Begin Preliminary Engineering | | ● | | | ▼ | ▼ | ▼ |
| A01818U.PE.PM.02 Project Management and Overhead | | | | | | | | |
| 0025 | General Project Management (Project Office) | ▼ | ● | ▼ | ● | ● | ▼ | ▼ |
| 0035 | Environmental Project Management and Overhead | ▼ | ▼ | | | ▼ | ▼ | ▼ |
| 0040 | Redistributed PE Project Management and Overhead (HQ & Region) (LOE) | ▼ | ● | ▼ | ● | ▼ | ▼ | ▼ |
| 0041 | Project Contingency | | ▼ | | | ▼ | ▼ | ▼ |
| A01818U.PE.PM.03 Project Management Plan Development & Maintenance | | | | | | | | |
| 0065 | WSDOT Project Management Plan (PMP) | | ● | ● | ● | ● | ● | ● |
| 0070 | PMP Endorsement | | ● | | | ▼ | ▼ | ● |
| 0075 | Project Handoff | ⊗ | ▼ | | | ▼ | ● | ● |
| A01818U.PE.PS Project Planning and Scoping | | | | | | | | |
| A01818U.PE.PS.01 Preliminary Estimates & Schedules | | | | | | | | |
| 0160 | PE Estimate | | ● | ▼ | ▼ | ▼ | ● | ● |
| 0165 | R/W Estimate | | ● | ▼ | ▼ | ▼ | ● | ● |
| 0170 | CN Estimate | | ● | ▼ | ▼ | ▼ | ● | ● |
| A01818U.PE.PS.03 Public Involvement for Planning | | | | | | | | |
| 0210 | Public Involvement | ▼ | ● | ▼ | ● | ▼ | ▼ | ● |
| A01818U.PE.PS.07 Pre-Design Study | | | | | | | | |
| 0290 | Pre-Design Study | | ● | ▼ | ● | ▼ | ● | ● |
| A01818U.PE.PS.08 Project Summary | | | | | | | | |
| 0300 | Project Definition | | ● | ▼ | ▼ | ▼ | ● | ● |
| 0305 | Design Decisions Summary | | ● | ▼ | ▼ | ▼ | ● | ● |
| 0310 | Environmental Review Summary | | ● | ▼ | ▼ | ▼ | ● | ● |