

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37

(****)

Contractor Surveying – ADA Features

ADA Feature Staking Requirements

The Contractor shall be responsible for setting, maintaining, and resetting all alignment stakes, and grades necessary for the construction of the ADA features. Calculations, surveying, and measuring required for setting and maintaining the necessary lines and grades shall be the Contractor's responsibility. The Contractor shall build the ADA features within the specifications in the Standard Plans and contract documents.

ADA Feature As-Built Measurements

The Contractor shall be responsible for providing As-Built records of all ADA feature improvements completed in the Contract.

The survey work shall include but not be limited to Completing the measurements, recording the required measurements and completing other data fill-ins' found on the ADA As-Built Forms, and transmitting the Forms to the Engineer. The ADA As-Built Forms are found at the following website location:

<http://www.wsdot.wa.gov/Design/ADAGuidance.htm>

The Contractor shall submit As-Built records to the Engineer five working days prior to the pay period cutoff date. The transmittal letter shall include a statement signed by the Contractor certifying the accuracy of the measurements.

In the instance where an ADA Feature does not meet accessibility requirements, all work to replace non-conforming work and then to measure, record the as-built measurements, and transmit the Forms to the Engineer shall be completed at no additional cost to the Contracting Agency, as ordered by the Engineer.

Payment

Payment will be made for the following bid item that is included in the Proposal:

"ADA Features Surveying", lump sum.

The unit Contract price per lump sum for "ADA Features Surveying" shall be full pay for all the Work as specified.