

1
2
3
4
5

(April 2, 2018)

The Contractor shall remove piles by directly pulling, using vibratory devices, or by cutting the piles below ground level to minimize localized turbidity. If use of a clamshell bucket is necessary due to pile breakage, turbidity curtains will be employed by the Contractor.