

1 **Section 1-10, Temporary Traffic Control**
2 **January 3, 2017**

3 **1-10.1(2) Description**

4 The first paragraph is revised to read:

5

6 The Contractor shall provide flaggers and all other personnel required for labor for traffic
7 control activities that are not otherwise specified as being furnished by the Contracting
8 Agency.

9

10 In the third paragraph, "Project Engineer" is revised to read "Engineer".

11

12 The following new paragraph is inserted after the third paragraph:

13

14 The Contractor shall keep lanes, on-ramps, and off-ramps, open to traffic at all times
15 except when Work requires closures. Ramps shall not be closed on consecutive
16 interchanges at the same time, unless approved by the Engineer. Lanes and ramps
17 shall be closed for the minimum time required to complete the Work. When paving hot
18 mix asphalt the Contractor may apply water to the pavement to shorten the time
19 required before reopening to traffic.

20

21 **1-10.3(2)C Lane Closure Setup/Takedown**

22 The following new paragraph is inserted before the last paragraph:

23

24 Channelization devices shall not be moved by traffic control personnel across an open
25 lane of traffic. If an existing setup or staging of traffic control devices require crossing
26 an open lane of traffic, the traffic control devices shall be taken down completely and
27 then set up in the new configuration.