

1
2
3
4
5

(March 13, 1995)

If the soil in the footing excavation *** \$\$\$* tends to liquify before placement of the concrete footing, the Contractor shall excavate below the plan grade a maximum of 1 foot, as determined by the Engineer, and backfill with gravel backfill for foundations.