

1  
2  
3  
4  
5  
6  
7  
8  
9

(August 2, 2010)

The Contractor shall protect the existing track and facilities of the Railroad Company from damage due to the Contractor's operations, and shall shore all excavation adjacent to the existing railroad track. Shoring shall be steel sheet piling designed for a Cooper E-80 loading according to the American Railway Engineering and Maintenance Association (AREMA) Manual For Railway Engineering. Damage to the railroad track or railroad facilities, due to the Contractor's operations, will be repaired by the Railroad at the Contractor's expense.