

1
2
3
4
5
6
7

(April 1, 2013)

The Contractor shall grind a test section 1500 foot long across the full width of a lane for evaluation by the Engineer to determine if the Work meets the Specifications. If the Specifications have been met the Contractor may proceed with the remaining cement concrete pavement grinding. If the Specifications have not been met, the Contractor shall make adjustments and another test section shall be completed.