

1
2
3
4
5
6
7

(March 13, 1995)

Vertical Edge Planing

During planing of bituminous pavement in the travelled lanes, the Contractor shall coordinate the planing and paving operations such that the planed roadway surface shall not remain unpaved at the end of the work day. The Contractor shall have a contingency plan to ensure that no planed areas remain unpaved due to equipment breakdown or other emergency.