

1 (January 7, 2019)  
2 Operate the inertial profiler in accordance with AASHTO R 57. Collect two  
3 longitudinal traces, one in each wheel path. Collect profile data in a continuous  
4 pass including areas excluded from pay adjustments for each section paved. The  
5 Contractor shall determine when each section is to be tested except that the  
6 minimum length to be tested shall be 528 feet unless accepted by the Engineer.  
7 Where a completed section of concrete pavement abuts a segment to be  
8 completed later in the project, the 50 feet adjacent to uncompleted section shall be  
9 included in the testing and incentive/disincentive for the uncompleted segment.  
10 Provide seven calendar days notice to the Engineer prior to testing.