

1
2
3
4
5
6

(August 4, 2008)

Repairing Slab Left Exposed After Removing Existing Curb and Railbase

After roughening and cleaning the concrete exposed by the removal of the existing curb and railbase, that portion of the exposed surface not covered by the new traffic barrier shall be coated with epoxy mortar and finished to have the same texture, slope and grade as that of the existing deck.