(August 4, 2008)

The pavement end of the bridge approach slab shall be constructed parallel to the pavement seat.