

1 (June 26, 2000)
2 If, in the opinion of the Engineer, water conditions at the time of construction
3 do not require seals for footing construction, the Engineer may specify that the
4 seals be omitted. In such a case the Contractor shall lower and construct the
5 footing, as shown in the Plans, at the elevation shown in the Plans for the
6 bottom of seal. The height of the pier shaft or columns shall be adjusted
7 accordingly.
8
9 No adjustment will be allowed in the unit contract prices for concrete, steel
10 reinforcing bar, and excavation by reason of any increase or decrease in
11 quantities involved due to the deletion of seals.