

1 (August 3, 2015)
2 The Contractor shall furnish and install inserts for the bridge utility supports as shown in
3 the Plans. The Contractor shall verify that the hanger rods freely hang plumb in their
4 inserts, and shall make adjustments to the inserts as necessary and as accepted by the
5 Engineer prior to utility installation.