(April 6, 2015) Sciemie Betrofit Domeli

1

Seismic Retrofit Demolition Plan
The Contractor shall submit Type 2 Working Drawings showing the method of
removing the specified portions of the existing bridges required by the seismic
retrofit work. The Working Drawings shall show the sequence of demolition and
removal, the type of equipment to be used in all demolition and removal operations,
and details of the methods and equipment used for containment, collection, and
disposal of all debris. The Working Drawings shall show all stages of demolition.