

1                   **(April 6, 2015)**  
2                   **Removing Portions of Existing Concrete**  
3                   The Contractor shall remove portions of existing concrete required by the seismic  
4                   retrofit work in accordance with Section 2-02.3(2)A2 and as shown in the Plans.  
5  
6                   The Contractor shall dispose of all materials removed by the demolition operations  
7                   in accordance with Section 2-02.3.  
8  
9                   The Contractor shall roughen, clean, and saturate the existing concrete surfaces  
10                  bonding to the fresh concrete in accordance with Section 6-02.3(12).