

1
2
3
4
5
6
7
8
9
10
11

(April 6, 2015)

8. If the Contractor selects a girder launching method as the erection procedure, the Contractor shall submit plan details of the nose beam, roller assemblies, jacks, blocking, tow lines and control lines, and shall prepare an erection procedure that describes the method and equipment involved in the launching procedure, the elevation and alignment control and corrective measures enforced during the launching process, the methods of monitoring and adjusting the tow line and control line loads during the launching process, and the spare jacks, tow lines, control lines, and other critical field erection equipment provided to ensure a continuous and safe operations.