

1  
2  
3  
4  
5  
6  
7  
8  
9

(March 6, 2000)

The Contractor shall furnish and drive \*\*\* \$\$1\$\$ test piles at the following locations or at locations designated by the Engineer:

\*\*\* \$\$2\$\$ \*\*\*

The \*\*\* \$\$3\$\$ test piles shall be driven in the location of permanent piles and the number of permanent \*\*\* \$\$4\$\$ piles required for this project has been reduced by the appropriate number.