1	(August 3, 2015)
2	The *** \$\$1\$\$ *** piles *** \$\$2\$\$ *** shall be placed in prebored holes drilled
3	to elevation ***\$\$3\$\$***.
4	
5	The holes shall be of adequate diameter to isolate the pile from skin friction.
6	The hole around the pile due to oversize boring shall be filled with dry sand or
7	pea gravel after the pile is placed.