

1 (August 3, 2015)
2 The *** \$\$1\$\$ *** piles ***\$\$2\$\$*** shall be prebored to elevation *** \$\$3\$\$
3 ***.
4
5 The diameter of the preboring shall be adjusted to provide for full contact
6 between the pile casing and the surrounding soil without shattering the soil
7 formation. It is estimated that the required diameter for preboring will be
8 approximately 1 inch less than the pile diameter; however, the diameter shall
9 be adjusted by the Contractor as specified by the Engineer to accomplish the
10 results described above. Jetting will not be permitted. The Contractor shall
11 follow preboring immediately with the placing of the pile casing to prevent
12 sloughing into the excavated hole.