

1 (January 7, 2002)
2 The Contractor shall use latex modified concrete (LMC) for the total concrete
3 overlay operation, and shall provide a concrete mix to the Engineer in accordance
4 with Item 5 of Section 6-09.3(2). Use of fly ash modified concrete (FMC) or
5 microsilica modified concrete (MMC) will not be allowed.