

1 **Section 6-09, Modified Concrete Overlays**

2 **April 4, 2016**

3 **6-09.3(8)A Quality Assurance for Microsilica Modified and Fly Ash Modified**
4 **Concrete Overlays**

5 The first sentence of the first paragraph is revised to read the following two new sentences:

6

7 The Engineer will perform slump, temperature, and entrained air tests for acceptance in
8 accordance with Section 6-02.3(5)D and as specified in this Section after the Contractor
9 has turned over the concrete for acceptance testing. Concrete samples for testing shall
10 be supplied to the Engineer in accordance with Section 6-02.3(5)E.

11

12 The last paragraph is deleted.

13

14 **6-09.3(8)B Quality Assurance for Latex Modified Concrete Overlays**

15 The first two paragraphs are deleted and replaced with the following:

16

17 The Engineer will perform slump, temperature, and entrained air tests for acceptance in
18 accordance with Section 6-02.3(5)D and as specified in this Section after the Contractor
19 has turned over the concrete for acceptance testing. The Engineer will perform testing
20 as the concrete is being placed. Samples shall be taken on the first charge through
21 each mobile mixer and every other charge thereafter. The sample shall be taken after
22 the first 2 minutes of continuous mixer operation. Concrete samples for testing shall be
23 supplied to the Engineer in accordance with Section 6-02.3(5)E.

24

25 The second to last sentence of the last paragraph is revised to read:

26

27 Recommendations made by the technical representative on or off the jobsite shall be
28 adhered to by the Contractor.