

1 **Section 6-10, Concrete Barrier**
2 **August 1, 2016**

3 **6-10.3(5) Temporary Concrete Barrier**

4 This section title is revised to read:

5

6 **Temporary Barrier**

7

8 The first paragraph is revised to read:

9

10 For temporary barrier, the Contractor may use precast concrete barrier or temporary
11 steel barrier. Temporary concrete barrier shall comply with Standard Plan requirements
12 and cross-sectional dimensions, except that: (1) it may be made in other lengths than
13 those shown in the Standard Plan, and (2) it may have permanent lifting holes no larger
14 than 4 inches in diameter or lifting loops. Temporary steel barrier shall be certified that it
15 meets NCHRP 350 or MASH crash test requirements and shall be installed in
16 accordance with the manufacturer's recommendations.

17

18 **6-10.4 Measurement**

19 The first sentence of the second paragraph is revised to read:

20

21 Temporary barrier will be measured by the linear foot along the completed line and
22 slope of the barrier, one time only for each setup of barrier protected area.

23

24 **6-10.5 Payment**

25 The Bid item "Temporary Conc. Barrier", per linear foot, and the paragraph following this Bid
26 item, is revised to read:

27

28 "Temporary Barrier", per linear foot.

29

30 The unit Contract price per linear foot for "Temporary Barrier" shall be full pay for all
31 costs, including furnishing, installing, connecting, anchoring, maintaining, temporary
32 storage, and final removal of the temporary barrier.