

1
2
3
4
5
6
7
8
9

(April 3, 2017)
Specific Fabrication Requirements for Precast Concrete Panel Faced
Structural Earth Walls

ARES Modular Panel Wall System

The concrete mix for precast concrete facing panels shall be a Contractor mix design in accordance with Section 6-02.3(2)A, producing a minimum compressive strength at 28 days of 4,500 psi. The Contractor mix design for precast concrete facing panels shall not include Type III cement unless otherwise allowed by the Engineer.