

1 **Section 6-14, Geosynthetic Retaining Walls**

2 **January 3, 2017**

3 **6-14.3(2) Submittals**

4 The first sentence of the first paragraph is revised to read:

5

6 The Contractor shall submit Type 2E Working Drawings consisting of detailed plans for
7 each wall.

8

9 **6-14.5 Payment**

10 The bid item "Concrete Fascia Panel", per square foot, and the paragraph following this bid
11 item are revised to read:

12

13 "Concrete Fascia Panel For Geosynthetic Wall", per square foot.

14

15 All costs in connection with constructing the concrete fascia panels as specified shall be
16 included in the unit Contract price per square foot for "Concrete Fascia Panel For
17 Geosynthetic Wall", including all steel reinforcing bars, premolded joint filler,
18 polyethylene bond breaker strip, joint sealant, PVC pipe for weep holes, exterior surface
19 finish, and pigmented sealer (when specified), constructing and placing the concrete
20 footing, edge beam, anchor beam, anchor rod assembly, and backfill.