

1 (August 5, 2013)
2 After the initial planting area weed control, soil placement, grading, and the
3 installation of irrigation lines are completed, and prior to planting, all designated
4 planting areas shall be covered with compost.
5
6 Prior to placement of compost, the application methods shall be approved by the
7 Engineer.
8
9 Compost shall not be placed when a condition ex-ists, such as frozen or water
10 saturated soil that may be detrimental to successful application or soil structure.
11
12 The Contractor shall notify the Engineer a minimum of five working days prior to the
13 start of compost work.
14
15 Compost shall be uniformly and evenly placed in all designated areas at a depth of
16 *** \$\$1\$\$ *** inches.