

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12

**(April 6, 2015)**  
**Beam Guardrail Type WP Thrie Beam**

Whenever the Contractor is not actively working on the beam guardrail retrofit, the Contractor shall ensure that all guardrail ends are securely fastened to the rail posts and existing bridge railing system, including temporary terminal end sections as required. The Contractor shall conduct retrofit operations such that no gaps occur between the existing bridge railing system and the beam guardrail retrofit at any time.

The Contractor shall submit Type 2 Working Drawings detailing the temporary connections between the existing guardrail system and the thrie beam guardrail system, and the temporary terminal end sections.