

1 (April 3, 2017)  
2 This work consists of constructing cement concrete sidewalks, curb ramps, bus stop  
3 shelter foundations, masonry sidewalks, and ramp grinding in accordance with details  
4 shown in the Plans, Standard Plans, these Specifications, and in conformity to the lines  
5 and grades shown in the Plans, Standard Plans, and as established by the Engineer.