

1 (April 4, 2011)
2 The Contractor shall request a pre-meeting with the Engineer to be held 2 to 5 working
3 days before any work can start on cement concrete sidewalks, curb ramps or other
4 pedestrian access routes to discuss construction requirements. Those attending shall
5 include:
6

- 7 1. The Prime Contractor and Subcontractor in charge of constructing forms, and
8 placing, and finishing the cement concrete.
9
- 10 2. Project Engineer (or representative) and Project Inspectors for the cement
11 concrete sidewalk, curb ramp or pedestrian access route Work.
12

13 Items to be discussed in this meeting shall include, at a minimum, the following:
14

- 15 1. Slopes shown on the Plans.
16
- 17 2. Inspection
18
- 19 3. Traffic control
20
- 21 4. Pedestrian control, access routes and delineation
22
- 23 5. Accommodating utilities
24
- 25 6. Form work
26
- 27 7. Installation of detectable warning surfaces