

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12

**(January 3, 2011)**  
**Perforated Steel Square Sign Post System**

Where noted in the Plans, steel sign post systems shall be square, pre-punched galvanized steel tubing, that are NCHRP 350 Test Level 3 Certified and FHWA approved. The steel sign post system shall include all anchor sleeves, and other hardware required for a complete sign installation.

**System Acceptance**

Systems listed in the current QPL will be accepted per the QPL approval code. Systems not listed in the QPL will be accepted based on a Supplier's Certificate of Compliance. The Supplier's Certificate of Compliance will be a contract specific letter from the supplier stating the system is NCHRP 350 Test Level 3 compliant.