







DRAWN BY: FERN LIDDELL



NOTES

1. See **Standard Plan J-20.26** for Accessible Pedestrian Pushbutton details.
2. Where shown in the plans, install plaque (R10-32P) "PUSH BUTTON FOR 2 SECONDS FOR EXTRA CROSSING TIME" above the Accessible Pedestrian Signal (APS) assembly. Add 14" (in) to the PPB post height to accommodate plaque and leave a 2" (in) space between signs.
3. Mounting distances vary between manufacturers. See manufacturers recommendations for mounting information.
4. Junction Box serving the Standard shall preferably be located 5' - 0" (10' - 0" Max.) from the Standard.
5. Supplemental Grounding Conductor shall be non-insulated #4 AWG stranded copper and shall be clamped to vertical rebar with a connector suitable for use embedded in concrete: Provide 3' - 0" min. slack. Attach to pole grounding stud with a full circle crimp-on connector (crimped with a manufacturer recommended crimper).




ANCHOR BOLT TEMPLATE

GROUNDING CONNECTION DETAIL



* WELD STUD TO POLE WALL TO MAXIMUM EXTENT POSSIBLE ~ 1/2" (IN) MINIMUM WELD

CONFIGURATIONS VARY AMONG DIFFERENT MANUFACTURERS



SECTION B

BASE PLATE ASSEMBLY ~ 1/2" (IN) DIAMETER STEEL HEAVY HEX NUT, WITH 1/2" (IN) FLAT WASHER, TWO EACH REQUIRED PER ANCHOR BOLT ~ MINIMUM OF TWO THREADS ABOVE TOP OF NUT OR 5/8" (IN) MAXIMUM (TYP.)





TYPE PPB STANDARD DETAILS

ACCESSIBLE PEDESTRIAN PUSHBUTTON WITH CURB BASE
STANDARD PLAN J-20.11-02

SHEET 1 OF 2 SHEETS






APPROVED FOR PUBLICATION

DRAWN BY: FERN LIDDELL





REINFORCING STEEL QUANTITIES LIST

MARK	③	④	⑤	⑥
QTY.	3	2	3	7



KEY NOTE

① CONDUIT COUPLING ~ INSTALL FLUSH WITH TOP OF FOUNDATION. (DO NOT GLUE PVC STUBOUT)



ACCESSIBLE PEDESTRIAN PUSHBUTTON WITH CURB BASE

STANDARD PLAN J-20.11-02