Nighttime Construction Noise

Urban and Rural highway projects

Type of construction projects

- Mega projects
 Sound Transit, Alaskan viaduct
- Highway projectsPaving, traffic signal installation
- Urban construction
 Building demo/construction, city's arterial/Street improvements.

Nighttime construction work

- WSDOT must obtain
 variance from jurisdiction
 to work after 10:00 PM to
 7:00 AM
- WSDOT incorporates noise mitigation conditions on contract plans
- WSDOT monitors compliance during construction.
- WSDOT responds to complaints.



Selection of mitigation measurements vs. type of highway project

- Highway preservation projects Paving -
- Mobility projects HOV widening -
- Traffic/Electrical/Retrofit projects
- Structural projects
- Maintenance projects

Construction nighttime noise variance Condition types

- Minimum WSDOT standard conditions
- Special conditions required by specific jurisdiction
- Conditions that depend on the location, duration and type of project.
- Conditions identified during a public process.

Minimum WSDOT standard conditions

- Back up alarms
- Temporary Shields
- No tail gate banging allowed
- No parked or idling vehicles near residences
- Public notification by contractor of night time construction



Special conditions required by specific jurisdiction

- Provide 24hr emergency phone line
- Noise training to workers
- Construction site monitoring
- No work allowed within the same neighborhood for more than 2 consecutive weeks
- Publish notices
- Provide VMS signs



Conditions that depend on the location, duration and type of project

- On Site control
 - Work hours limitation
 - Scheduling
 - Temporary barriers
 - Equipment location
 and Traffic control site
 - Equipment & material handling
 - Back up alarms

- Off Site Strategies
 - Ear plugs
 - Public meetings/neighborhood group meetings.
 - Notices :flyers,Newspapers, signs
 - Window insulationsStyrofoam.
 - Out of the box

Conditions identified during a public process

- Relocation of resident may be justified if 2 consecutive complaints are received.
- Special notification for sensitive residences such as nursing homes and hospitals



Constrains for implementation of construction mitigation measurements

- Project construction budget.
- Type of construction operations
- Construction seasons: Summer vs. Winter
- Limitation on schedule: lane closures environmental permits
- Topographical features
- Safety issues

Mitigation strategies Approach

- Present a set of mitigation conditions to the jurisdiction that the agency is able to bid within budget
- Present effective tools to minimize nighttime construction noise nuisances.
- Coordinate efforts between jurisdiction and contracting agency to update mitigation measures in case of complaints.

Agency Coordination

Successes

- Public information
- Develop trust with jurisdiction(city or county)
- Lessons learned apply them
- Back up action plan available (practice worst, medium case scenario)

To improve

- Enforcement
- Construction
 equipment upgrade &
 maintenance
- Project changes
- Contract provisions.