

FHWA Roadway Construction Noise Model (RCNM)

Judith L. Rochat, Ph.D. and Clay N. Reherman U.S. DOT Volpe Center Acoustics Facility Environmental Measurement and Modeling

TRB ADC40 Summer Meeting Seattle, WA July 2005





Presented by:

Judith Rochat US DOT/Volpe Center 55 Broadway, DTS-34 Cambridge, MA 02142

Tel: 617/494-6338

E-mail: rochat@volpe.dot.gov



Roadway Construction Noise

- Construction is often conducted in close proximity to residences and businesses
- ♦ Should be controlled and monitored to avoid excessive noise impacts





Examples of Existing Guidance

FHWA 1977 handbook

Highway Construction Noise: Measurement, Prediction and Mitigation

Manual method for prediction

FHWA 1982 prediction tool

HICNOM, a highway construction noise computer program

- Data-intensive and comprehensive method
- Primarily used for highly complex or controversial major urban projects



Time for Guidance Updates

- Updated construction equipment
- Extensive highway construction projects in the U.S. and Canada
 - Lessons learned
 - Simple prediction tools available



Central Artery/Tunnel Project in Boston ("Big Dig")

- Largest urban construction project ever conducted in the U.S.
 - 7.5 miles (161 lane miles)
 - Includes underground expressway, river bridge, harbor tunnel, elevated highway demolition, park creation
 - 24 hours/day
 - Thousands of residential and commercial abutters





Big Dig Noise Control Program

- Construction Noise Control Specification 721.560
 - Most comprehensive in the U.S.
 - Includes proactive mitigation based on predictions
- Construction noise prediction spreadsheet developed by Erich Thalheimer of Parsons Brinckerhoff Quade & Douglas, Inc.
 - RCNM is based on the Big Dig prediction spreadsheet



RCNM


- Windows-based program
 - Incorporates noise calculations and equipment database from Big Dig spreadsheet
- Screening tool
 - Enables calculations of construction noise levels in more detail than manual methods while avoiding extensive input data collection
 - Two main uses:

Easily predict construction noise levels Determine compliance with noise limits

 Applicable to a variety of construction noise projects of varying complexities



RCNM Screen






RCNM Input

Receptor

- Allows multiple receptors
- Land use (residential, commercial, industrial)
- Baseline sound levels (Leq or L10, A-weighted)

Equipment

- Up to 15 types of equipment
- Distance to receptor
- Estimated shielding between equipment and receptor





RCNM Construction Equipment Database

Big Dig database

- Over 50 types of equipment
- Lmax dBA @ 15m (50 ft), slow
- Includes spec and measured levels










RCNM Input (continued)

- Equipment database can be modified
 - Equipment can be added or deleted
 - Default values can be restored






RCNM Input (continued)

- Choice of Leq or L10 (A-weighted) for display
- Noise limit criteria
 - Can use Big Dig default values or enter new criteria based on local ordinances
 - Entry is achieved through a pulldown menu with conditional options







RCNM Calculations

- Calculations account for spherical spreading and can adjust for shielding (guidance given for estimating shielding)
- Calculates Lmax, Leq, L10 (A-weighted) for each equipment type and as totals
 - Leq calculations based on Lmax
 - L10 = Leq + 3 dBA
 Based on extensive Big Dig data
 Offset can be modified by user
- Calculates noise limit exceedances based on baseline noise levels and lot-line noise limits



RCNM Output


- ◆ Calculated Lmax and Leq or L10 levels
 - By equipment type
 - As totals
- If noise limit criteria defined, will display ...
 - Lot-line noise limits
 - Noise limit exceedances

						N-	231 in C	17A6								
			Calculated (dBA)		Lot-Line Noise Limits (dBA)					Noise Limit Exceedance (dBA)						
			Calculated (dbA)		Day		Evening		Night		Day		Evening		Night	
	# Unit	s Equipment	Lmax	L10	Lmax	L10	Lmax	L10	Lmax	L10	Lmax	L10	Lmax	L10	Lmax	L10
1		Total	89.6	88.3	85.0	83.0	85.0	80.0	80.0	74.0	4.6	5.3	4.6	8.3	9.6	14.3
2	1	Compactor (ground)	83.2	79.2	85.0	83.0	85.0	80.0	80.0	74.0	None	None	None	None	3.2	5.2
3	1	Concrete Saw	89.6	85.6	85.0	83.0	85.0	80.0	80.0	74.0	4.6	2.6	4.6	5.6	9.6	11.6
4	1	Dozer	81.7	80.7	85.0	83.0	85.0	80.0	80.0	74.0	None	None	None	0.7	1.7	6.7
5	1	Flat Bed Truck	74.3	73.3	85.0	83.0	85.0	80.0	80.0	74.0	None	None	None	None	None	None
6	1	Excavator	80.7	79.7	85.0	83.0	85.0	80.0	80.0	74.0	None	None	None	None	0.7	5.7



RCNM Case and Files

- User's can save ...
 - Case with all receptors, equipment, results
 - Modified equipment database
- ◆ User's can export case to ...
 - Comma-delimited file
 - Text file





RCNM Availability

- In final stages of testing
- Will be available without cost or obligation
- Distribution
 - Will be downloadable from the web
 - Will be included on upcoming construction noise CD-ROM



Side Topic: Construction Noise Handbook and CD-ROM

♦ Soren Pedersen & Harvey Knauer





Purpose

- Update the 1977 FHWA document
- Incorporate experiences related to construction noise since 1977
- Include up-to-date references
 - Equipment levels
 - Mitigation techniques
 - Contacts
- Incorporate latest modeling techniques



Handbook/CD-ROM Organization

Chapte Introduc		Chapter 2: Technology	Chapter 3: Effects of Construction Noise	Chapter 4: Construction Noise Criteria and Metrics		
Chapte Measurem Constructio	ent of	Chapter 6: Prediction of Construction Noise	Chapter 7: Mitigation of Construction Noise	Chapter 8: Construction Equipment Noise Levels and Ranges		
Chapte Construction Experienc Contac	n Noise es and	Chapter 10: Construction Noise Related Training Materials	Chapter 11: Public Involvement	Chapter 12: Coordination		




Use of the Handbook/CD-ROM

- Handbook will serve as a summary document
- CD-ROM will contain more details, photos, and "clickable" links to data sources and references



Example of CD-ROM Use





Questions or Comments?

