SECTION 8-11, GUARDRAIL 1 2 July 31, 1995 8-11.3(1)C Erection of Rail 3 4 The second sentence of the first paragraph is revised to read: 5 6 No punching, cutting, or welding shall be done in the field, except that holes 7 necessary when additional posts are required or for special details in 8 extraordinary cases may be drilled in the field when approved by the Engineer. 9 8-11.3(1)D Anchor Installation 10 11 The second paragraph is supplemented with the following: 12 13 When tightening, the anchor cable shall be restrained to prevent twisting of the 14 cable. 15 16 The third paragraph is revised to read: 17 18 When steel tubes used with the Wood Breakaway Post are driven, they shall be 19 driven prior to installing the wood post. 20 21 8-11.4 Measurement 22 The first paragraph is replaced with the following two paragraphs: 23 24 Measurement of beam guardrail and beam guardrail Type 1 long posts will be by 25 the linear foot measured along the line of the completed guardrail, including 26 expansion sections, and will also include the end section for Type F connections. 27 28 Measurement of beam guardrail transition sections will be per each for the type of 29 transition section installed. End sections, except for Type F connections, will be 30 considered part of the transition section and will be included in the measurement 31 of the transition section. 32 33 The following paragraph is added after the second paragraph: 34 35 Measurement of beam quardrail terminals will be per each for the completed 36 terminal. 37 38 The third paragraph is deleted. 39 40 8-11.5 Payment Item No. 5 is revised to read: 41 42 "Beam Guardrail Transition Section Type ____", per each. 43 44 45 The unit contract price per each for "Beam Guardrail Transition Section Type 46 shall include posts, end sections, and attaching the transition section to masonry

47

structures.

1	
2	This Section is supplemented with the following:
3	
4	11. "Beam Guardrail Terminal", per each.
5	The unit contract price per each for "Beam Guardrail Terminal" shall include
6	the posts, rail, end section, and anchor.