

1 **(March 13, 1995)**

2 **Retaining Wall**

3 Wall construction shall begin at the lowest portion of the excavation and each  
4 layer shall be placed horizontally, and shall be completed entirely before the  
5 next layer is started. Geotextile splices transverse to the wall face will be  
6 allowed, provided the minimum overlap is 2 feet or the splice is sewn together.  
7 Geotextile splices parallel to the wall face will not be allowed. The geotextile  
8 shall be stretched out in the direction perpendicular to the wall face to ensure  
9 that no slack or wrinkles exist in the geotextile prior to backfilling.

10  
11 The fill material shall be placed on the geotextile in such a manner that a  
12 minimum of 6 inches of material shall be between the vehicle or equipment tires  
13 or tracks and the geotextile at all times. The backfill material shall contain no  
14 particles greater than 3 inches in size.

15  
16 The damaged geotextile section shall be replaced by the Contractor with a new  
17 section of geotextile at no cost to the State.

18  
19 A temporary form system shall be used to prevent sagging of the geotextile  
20 facing elements during construction. A typical example of a temporary form  
21 system and sequence of wall construction required when using this form are  
22 detailed in the Plans.

23  
24 The wall backfill shall be placed and compacted in accordance with the wall  
25 construction sequence detailed in the Plans. The minimum compacted backfill  
26 lift thickness of the first lift above each geotextile layer shall be 6 inches. The  
27 maximum compacted lift thickness anywhere within the wall shall be 8 inches or  
28 one half of the geotextile layer spacing, whichever is least.

29  
30 Each layer shall be compacted to 95 percent of maximum density. The water  
31 content of the wall backfill shall not deviate above the optimum water content by  
32 more than 3 percent. Sheepsfoot rollers, other rollers with protrusions, and full-  
33 size vibratory rollers will not be allowed. Small vibratory rollers will be allowed  
34 with the approval of the Engineer. Compaction within 3 feet of the wall face  
35 shall be achieved using light mechanical tampers approved by the Engineer and  
36 shall be done in a manner to cause no damage or distortion to the wall facing  
37 elements or reinforcing layers.

38  
39 If corners are to be constructed in the geotextile wall the method used to  
40 construct the geotextile wall corners shall be submitted to the Engineer for  
41 approval at least 14 calendar days prior to beginning construction of the wall.  
42 The corner shall provide a positive connection between the sections of the wall  
43 on each side of the corner such that the wall backfill material cannot spill out  
44 through the corner at any time during the design life of the wall. Furthermore,  
45 the corner shall be constructed in such a manner that the wall can be  
46 constructed with the full geotextile embedment lengths in the vicinity of the  
47 corner in both directions.

48  
49 The method of ending a geotextile wall layer at the top of the wall, where  
50 changes in wall top elevation occur, shall be submitted for approval with the wall  
51 corner details submittal. The end of each layer at the top of the wall shall be  
52 constructed in a manner which prevents wall backfill material from spilling out  
53 the face of the wall throughout the life of the wall. If the profile of the top of the  
54 wall changes at a rate of 1:1 or steeper, this change in top of wall profile shall be  
55 considered to be a corner. Also, wall angle points with an interior angle of less  
56 than 150 degrees shall be considered to be a corner.

57

1 The base of the excavation shall be completed to within  $\pm 3$  inches of the staked  
2 elevations. The external wall dimensions shall be placed to within  $\pm 2$  inches of  
3 that staked. Each layer and overlap distance shall be completed to within  $\pm 1$   
4 inch of that detailed in the Plans.  
5  
6 The maximum deviation of the wall face from the batter detailed in the Plans  
7 shall not be greater than 3 inches for permanent walls and 5 inches for  
8 temporary walls. The face batter measurement shall be made at the midpoint of  
9 each wall layer. Each wall layer depth shall be completed to within  $\pm 1$  inch of  
10 that detailed in the Plans.  
11  
12 Non-corroding alignment wires and thickness control pins shall be provided to  
13 establish thickness and plane surface. Alignment wires shall be installed at  
14 corners and offsets not established by formwork. The Contractor shall ensure  
15 that the alignment wires are tight, true to line, and placed to allow further  
16 tightening. Alignment wires shall be removed after wall construction is  
17 complete.