APPROXIMATE QUANTITIES				
Tank	Length	Concrete	Steel Reinf.	Cast Iron Soil
Capacity	(X)		Bars	Pipe & Fitting
Gal.	F†.	C.Y.	Lbs.	Lbs.
6000	6	23	3800	471
8000	8	28	4600	471
10000	10	32	5400	471
12000	12	37	6300	471
14000	14	42	7100	471

NOTES:

- 1. Approval of local health department is required before work is started.
- 2. Excavated material shall be disposed of as directed by the Engineer.
- All work shall be left open until inspected and approved by the Health Officer and the Engineer.
- 4. All grades shall be checked and approved by the Engineer.
- Water tight manhole covers shall be approved by the Engineer prior to installation.
- 6. Precast septic tanks are acceptable, subject to the approval of the Engineer. Materials shall meet or exceed those shown.
- 7. Plan dimensions may vary as site conditions and system design permit.
- 8. All concrete shall be Class 4000.
- 9. Reinforcing steel shall be Grade 300 or Grade 400.

