

(BSP July 12, 2000)

Beam Guardrail Type WP Thrie Beam

The Contractor shall field measure the depth of the existing ballast and wearing course at both wheel guard lines, and shall include the dimensions at both wheel guard lines in the steel post mounting bracket shop drawings submitted to the Engineer for approval in accordance with Section 8-11.3(1)E.

The Contractor shall remove the existing ballast and wearing course to the top of existing timber deck in the vicinity of the steel post anchorage locations, and shall dispose of the removed surfacing materials in accordance with Section 2-02.3.

When shown in the Plans, the Contractor shall place a timber block beneath the timber deck at each steel post anchorage location and against the existing exterior timber stringer.

The Contractor shall install the steel post anchorage assembly, including the deck plate, distribution plate, bearing plate, base plate, backing plate, and TS steel tube post, as shown in the Plans. Timber deck shims shall be cut and trimmed as necessary to align the top of the vertical webs of the steel post anchorage 15 millimeters below the top of the surrounding wearing course surfacing, in accordance with the existing timber deck transverse slope and existing ballast and wearing course depth specified in the shop drawings as approved by the Engineer.

The Contractor may field drill holes through the steel components in accordance with Section 6-03.3(27) except as otherwise noted. The Contractor shall identify all holes to be field drilled in the steel fabrication shop drawings submitted to the Engineer for approval. The Contractor may filed drill the holes using hand held drills provided that the Contractor submits the method and equipment used to the Engineer for approval, and that the Contractor receives the Engineer's approval of the submittal prior to beginning hand drilling. The Contractor shall repair all galvanized steel surfaces damaged by field drilling operations by painting the damaged areas with one coat of paint conforming to Formula A-11-99 as specified in Section 9-08.2.

The Contractor shall replace all existing ballast and wearing course removed in the vicinity of the steel post anchorage locations to the top of the surrounding surfacing. The Contractor shall fill the void with a surfacing material approved by the Engineer.